

Supply, Installation, Testing and Commissioning of MS Stand with White colour for all 13 Nos of HI-WALL SPLIT TYPE UNITS.

1. Scope of work

- a. Mounting/Fitting of indoor and outdoor units at the respective locations
- b. Laying of refrigerant piping and connecting with indoor and outdoor units after drilling hole/holes in the wall, if required. Holes are made by hole saw/ core cutter.
- c. Checking / Charging Refrigerant gas in the unit.
- d. Suitable electric wiring between indoor & outdoor unit and switch up to 3 meters length.
- e. Testing for satisfactory working without any abnormal noise as well as leakage test of entire system.
- f. Installation of 3 Pin, sockets, Plugs, etc. wherever necessary.
- g. Any other work which is not mentioned shall be under the scope of contractor under turnkey basis.