

कार्यालय अधिशासी अभियन्ता सिंचाई निर्माण खण्ड-प्रथम लखनऊ

ई-कोटेशन सूचना संख्या-01/सि.नि.ख.प्र.ल./2026-27

महामहिम राज्यपाल उत्तरप्रदेश की ओर से ई-कोटेशन के माध्यम से निम्न कार्य हेतु संलग्न आइटमों/ मर्चें की प्रति यूनिट दरें दिनांक 12.05.2026 को अपराह्न 03.00 बजे तक आमंत्रित की जाती हैं, जो उसी दिन दिनांक 12.05.2026 को अपराह्न 04.00 बजे अधिशासी अभियन्ता, सिंचाई निर्माण खण्ड-प्रथम, लखनऊ के कार्यालय कक्ष में खोली जायेंगी। कोटेशनदाता दिनांक 02.05.2026 की पूर्वाह्न 11.00 बजे से दिनांक 12.05.2026 की अपराह्न 03.00 बजे तक कोटेशन अपलोड एवं डाउनलोड कर सकेंगे। कार्यालय बन्द होने या छुट्टी होने पर कोटेशन अगले कार्य दिवस में खोली जायेगी।

S.No.	NAME OF ITEM	Quantity	Unit	Rate
1	Providing and fixing of Cement Fiber Board Partition including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	Sqm	
2	Providing and fixing ACP Cladding pf Metallic & Solid Colours Series Antique Bronze 8 ft x 4 ft ACP Panel - 3 mm Star Metallic & Solid including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	Sqm	
3	Supplying and fixing Internet Socket outlet modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required. including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	Job	
4	Supply & fixing of 225/230mm sweep ventilating (Light Duty) exhaust fan complete with Metallic Blade (Steel bird guard protector /Copper motor for high air suction performance /Capacitor etc.), Noise level : (45 - 50) dB, Power consumption : 45 W, Rated voltage : 230 V, Rated frequency : 50 Hz, Motor type : Normal Speed. including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	Job	
5	Supplying and fixing TV 4K Ultra HD (3840 x 2160 pixels). including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
6	Supply, Installation, Testing, and Commissioning of WIFI including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
7	Supply, Installation, Testing, and Commissioning of Instant water heater including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
8	Supply, Installation, Testing, and Commissioning of air cooling type, 2.0 Ton, Split air conditioner in recessed manner in grid type false ceiling with full function wireless remote and auto restart feature, s with indoor/outdoor unit, gas charge etc. (100% copper coil condenser) including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
9	Supply, Installation, Testing, and Commissioning of branded Split AC 1.5 Ton 3 star rating. including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
10	Supply, Installation, Testing, and Commissioning of branded Split AC 1.0 Ton 3 star rating. including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	Job	
11	Supply, Installation, Testing, and Commissioning of branded 5 KVA voltage Stabilizers with range of 130 - 280V of standard make including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
12	Supply, Installation, Testing, and Commissioning of branded 4KVA voltage Stabilizers with range of 130 - 280V of standard make including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
13	Supply, Installation, Testing, and Commissioning of branded Multimedia Projector, 3200 lumens, 15000:1 contrast Ratio, XGA resolution. including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
14	Supply, Installation, Testing, and Commissioning of branded Projector Ceiling Mount Kit including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
15	Supply, Installation, Testing, and Commissioning of branded 8'x6' Self Lock Projection screen including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
16	Supply, Installation, Testing, and Commissioning of branded Two way Wall speaker 70v,100v, 30 watt. including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
17	Supply, Installation, Testing, and Commissioning of branded Power amplifier 4 inputs, 1 aux, Multiple outputs - 70 V / 100 V and 8/4 ohm Temperature controlled forced front to back ventilation, directly stackable 120 watt including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
18	Supply, Installation, Testing, and Commissioning of branded Wireless Gooseneck microphone set of four microphone with receiver including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
19	Supply, Installation, Testing, and Commissioning of branded Supporting Cables & connector, VGA Cable, Power Cable, speaker Cable, Stereo Cable, VGA and aux connector Plate including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
20	Supply, Installation, of branded Equipment Rack of standard size as per requirement including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
21	Supply, Installation, Testing, and Commissioning of branded laptop including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	
22	Supply, Installation, Testing, and Commissioning of branded UPS with battery backup including material, labour, T&P etc. required for proper completion of work as per the direction of engineer in charge. (Rates are without GST)	1	JOB	

नियम व शर्तें:-

- कोटेशन में दी जाने वाली दरें समस्त कर एवं करैज आदि सहित होंगी, केवल जी0एस0टी0 अलग से अंकित करनी होगी।
- शर्तयुक्त दरें स्वीकार नहीं की जायेंगी।
- समस्त कोटेशन अधिशासी अभियन्ता, सिंचाई निर्माण खण्ड-प्रथम, लखनऊ के नाम से हारंगें।
- उक्त कोटेशन के माध्यम से दरें मात्र प्राक्कलन तैयार करने हेतु आमंत्रित की जा रही हैं।
- कोटेशनदाता/अधिकृत फर्मों का क्षेत्रीय/शाखा कार्यालय जनपद लखनऊ में होना अनिवार्य है।
- अधोहस्ताक्षरी को बिना कारण बताये कोटेशन निरस्त करने का पूर्ण अधिकार होगा।
- कोटेशन निर्धारित प्रारूप पर ही स्वीकार किये जायेंगे।
- कोटेशन से सम्बन्धित समस्त विवरण/शर्तें कार्यालय सहायक अभियन्ता द्वितीय एवं तृतीय (मु0), सिंचाई निर्माण खण्ड-प्रथम, लखनऊ के कार्यालय में उपलब्ध है।
- कोटेशनदाता द्वारा कार्यस्थल की स्थिति एवं प्रकृति की भली-भांति जानकारी के उपरान्त ही दरें डाली जायेंगी।