

SCHEDULE-B

FRP Fencing with cement concrete inside Distribution Transformers Center at various locations of Bardoli Town sub division under Bardoli Division.

Sr. No.	Item	Qty.	Rates/unit in Rs.	Unit	Amount in Rs.
1	Providing and fixing of FRP fencing of 1600 mm(1500+100) height above ground at Distribution Transformer Center with necessary excavation, concreting for grouting vertical posts up to 450 mm ground, hardware, accessories, fittings, lock etc complete as shown in specifications and drawing enclosed. The fencing shall comprise of one gate 2000 mm wide having two flaps and payment for the same shall be measured on Rmt basis.		3000/-	RMT	1000000/-
2	Inside fencing area to be finished with 6" thick 1:2:4 cement concrete & cement plaster supported with 6" brick wall on surrounding. (All materials required being use like cement bags, Bricks, sand, Kapchi is to be brought by the contractor at his own cost.) (Payment will be given in sq. foot for which concrete is done inside FRP fencing including wall.) (size 3x3 mtr)		81/-	Sq. foot	
Amt In Words: Ten Lacs Only.					

- **The rates quoted by Bidder will be exclusive of GST & Any escalation in rate of GST during the tenure of the contract will be paid by DGVCL as part of statutory variation.**

**Executive Engineer,
Bardoli Division Office
Bardoli**