



N.I.T. SCHEDULE FOR SHOULDER FILLING, PAINTING FIGURING ON CD, J.C, BRIDGE, ETC WORK ON DIFFERENT ROAD SUB DIVISION SEONI MALWA. (SECTION DOLARIYA)

P.A.C. 19.96 LACS

S.N.	Sor No	QTY	ITEM	RATE	UNIT	AMOUNT
1	Sor Item no. 4.16 Pg 15		Construction of Shoulders with approved material/selected soil 1/c excavation all lifts & leads 1/c grading to required slope & camber of 4% and compacting on OMC using vibratory roller of 80 to 100 kN static weight. Field compaction shall be done in corresponding layers of carriage way thickness and meet the requirements of MDD to achieve compaction (98% -100%) as per relevant clause of 400.			
		75.40	A) Hard Shoulders (CBR value >12)	398.00	Cum	30008.00
2	Sor Item no. 10.32 Pg 77		Providing painting, figuring and numbering as per IRC specifications complete with Synthetic Enamel Paint for 5th Km. Stone.			
		22.00	(i) One coat on old work.	293.00	Each	6446.00
3	Sor Item no. 10.33 Pg 77		Providing painting, figuring and numbering as per IRC specifications complete with Synthetic Enamel Paint for ordinary Km. Stone.			
		85.00	(ii) One coat on old work.	99.00	Each	8415.00
4	Sor Item no. 10.34 Pg 77		Providing painting, figuring and numbering as per IRC specifications complete with Synthetic Enamel Paint for 0.2 Km. Stones or Boundary Stones.			
		340.00	(ii) One coat on old work.	25.00	Each	8500.00
5	Sor Item no. 2.2 Pg 5		Clearing and Grubbing Road Land Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees having girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material up to a lead of 1000 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness.			
		60.16	A) In area of light jungle	29489.00	Ha	1769164.00
6	Sor Item no. 10.65 Pg 83		White washing with white cement, two coats on parapet walls, wheel guards and kerbs etc including preparation of surface by cleaning scraping etc as directed by Engineer-in-charge. Including Fevicol adhesive @ 2.5 % and 0.3% indigo of lime quantity including cost of all material etc. including aX material, labour, etc. complete.			
		6950.00		25.00	Sqm	173750.00
					TOTAL Rs	1996283.00


Sub Engineer


Sub-Divisional office
P.W.D. Sub division
Seoni Malwa

Executive Engineer
P.W.D. Division No 1
Narmadapuram