



Name of work Const. of cc road from rais bhai house to ata chakki main road in old galla market at shahjahanabad ward 11 zone 03

BOQ

Name of activity: Const. of cc road from rais bhai house t SOR: MPUADD Roads and Bridges, 2025					
S.No	Items	Qty	Unit	Rate (INR)	Amount (INR)
1	-V1_12.1.1.1_25 Earth work in excavation of foundation of structures with all lifts <(>&<)> lead up to 1000 M as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom as per section 300 and 2100 of the specifications.	17.500	CUM		
2	-V1_12.2_25 "Providing and laying levelling course in foundation, filling annular spaces around footing in rock up to top of rock in lean cement concrete M-10 nominal mix with 40 mm size coarse aggregate as per section 1000, 1500, 1700 and 2100 of the specifications using concrete mixer."	2.500	CUM		
3	-V1_12.5.2_25 "Providing and laying Plain/Reinforced cement concrete in open foundation including form work shuttering etc. complete as per drawing and technical specifications and as per sections 1000, 1500, 1700 <(>&<)> 2100 of the specifications."	6.25	CUM		
4	-V1_6.4_25 Providing and Laying Cement Concrete Grade M-20 with 20 mm graded crushed stone aggregate, mixing shall be in mechanical mixer, laying with paver compacting by use of pin, plate / screed vibrators including form work by strong steel girders fixed by spikes, separation membrane 125 micron thick, including cutting of joints @ 4 to 5 m interval and filling it with hot applied bituminous sealant (without dowel bars) (max. thickness 20 cm).	72.12	CUM		
Total Estimate Value (INR)					
Percentage over estimate					
Final Estimate Value (INR)					
Bhopal Municipal Corporation					