

**Name of Work : Constructing Box Type Culvert For Canal Crossing On Tejlav Distry Ex. Valsad Branch Canal at Ch.10790.00 Mt.**

**SCHEDULE - B**

**Memorandum showing items of work to be carried out**

Item No.	Quantities Estimated but may be	Item of work	Tendered Rates		Unit	Total Amount according to Estimated
			In figure Rs. Ps.	In words		
1	2	3	4	5	6	7
1	36	ITEM NO : 01 Excavation for foundation in all sorts of soil including yellow, sandy, gravelly soil, soft & hard murrum, etc. dry condition including depositing the excavated stuff in uniform layers in banks or as directed etc. complete for lead up to 1.0 Km and all lifts. (By machinery) (a) Above water table.	81.5	Rupees Eighty One and Fifty Paise Only	CM	2934.00
2	11	ITEM NO : 02 Providing and laying plain/reinforced cement concrete of cement, sand and Metal (20mm to 25 mm Size) in following proportion laid in situ including centering, shuttering, temping, smooth finishing, curing etc. complete as directed for all leads and lifts.(Manually with conventional Mixer) (iv) 1:2:4	4943.9	Rupees Four Thousand Nine Hundred Forty Three and Ninety Paise Only	CM	54382.90
3	17	ITEM NO : 03 Providing and laying plain/reinforced Design Mix cement concrete of various grade with cement, sand and coarse aggregates including centering, shuttering, batching, mixing, transporting, placing, vibrating, smooth finishing, curing etc. complete for all lead and lift. (Baching Plant Based, Including dewatering) (B) Raft, Bottom slab of barel, footing of columns, piers, abutment and bottom slab of sump etc. (iii) M - 25 Grade	4844.7	Rupees Four Thousand Eight Hundred Forty Four and Seventy Paise Only	CM	82359.90
4	38	ITEM NO : 04 Providing and laying plain/reinforced Design Mix cement concrete of various grade with cement, sand and coarse aggregates including centering, shuttering, batching, mixing, transporting, placing, vibrating, smooth finishing, curing etc. complete for all lead and lift. (Baching Plant Based, Including dewatering) (D) Walls of barrel, brest wall, staunching rings, pedastal of bearings, stoplog piers, well staining, transition wall etc. (iii) M - 25 Grade	5753.6	Rupees Five Thousand Seven Hundred Fifty Three and Sixty Paise Only	CM	218636.80
5	26	ITEM NO : 05 Providing and laying plain/reinforced Design Mix cement concrete of various grade with cement, sand and coarse aggregates including centering, shuttering, batching, mixing, transporting, placing, vibrating, smooth finishing, curing etc. complete for all lead and lift. (Baching Plant Based, Including dewatering) (E) Roadway slab, approach slab, chut floor slab, kerb pier cap, abutment cap, hoisting platform, top slab of barrel etc. (iii) M - 25 Grade	5206.3	Rupees Five Thousand Two Hundred Six and Thirty Paise Only		135363.80

Item No.	Quantities Estimated but may be	Item of work	Tendered Rates		Unit	Total Amount according to Estimated
			In figure Rs. Ps.	In words		
1	2	3	4	5	6	7
6	69	ITEM NO : 06 Providing and laying 75mm wearing coat of ordinary portland cement concrete M-15 grade including laying on proper camber, tamping, screening, finishing, broomung or grooving etc. complete for all leds and lifts.	282.3	Rupees Two Hundred Eighty Two and Thirty Paise Only		19478.70
7	57.18	ITEM NO : 07 Providing & Placing in position reinforcement bars including cutting,bending welding joints where necessary,hooking etc, complete as per drawing for all leads and lifts.(b) TMT	7194	Rupees Seven Thousand One Hundred Ninety Four Only		411352.92
8	129	ITEM NO : 08 White Or colour wash in following coats including scrapping, scaffolding etc. complete.12(A) For two coats.	14.8	Rupees Fourteen and Eighty Paise Only		1909.20
9	28	ITEM NO : 09 Providing and fixing in position 110 mm dia PVC pipe weep holes in abutment,wingwalls and laying, training etc. comp.	263.7	Rupees Two Hundred Sixty Three and Seventy Paise Only		7383.60
10	1	ITEM NO : 10 Taking Photography of work at site before starting of work, ongoing & after completion of work etc. Complete.	1000	Rupees One Thousand Only		1000.00
						<b>934801.82</b>
<b>Rupees Nine lakh Thirty Four Thousand Eight Hundred One and Eighty Two Paise Only</b>						
I/We am/are Willing to carry out the work at.....% above/below Percent(should be written in figures and words) of the estimated rates mentioned above. Amount of my/our tender works out as under.						
#REF!			* Estimated amount Put to tender	Rs.		<b>9,34,801.82</b>
Deduct.....%below			Rs.	Add.....% above	Rs.	
Net			Rs.	Total	Rs.	
In words.....				In words.....		
*(Please strike out whichever is not applicable)						
Note 1 All works shall be carried out as per Public Works Department Handbook and other specifications of Division or as directed.						
નોંધ-૧ બધું જ કામ બાંધકામ વિભાગની પુસ્તિકા અને ડિવિઝનની ખાસ વિગત મુજબ અથવા સુચના પ્રમાણે કરવાનું રહેશે.						
Note-2 All the columns is Schedule should be filled in ink and the total of the entries in the last column should be struck by the contractor under his signature.						
નોંધ-૨ અનુસૂચીમાં બધા ખાનાની વિગતો સહીથી ભરવી અને છેલ્લા ખાનાની નોંધોનો સરવાળો કરી કોંટ્રાક્ટરે સહી કરવી.						
Note-3 Rates quotes include clearance of site (prior commencement of work and at its close) in all respects and hold good for work under all conditions, site, moisture,						
નોંધ-૩ ટાંકેલા દરમાં, સ્થળની (કામના આરંભે અને પૂરૂ થાય તે વખતે) દરેક રીતે સાફસુફી કરવાનો સમાવેશ થાય છે.અને તે દર તમામ પરિસ્થિતિ ,સ્થળ,ભેજ,હવામાન						
Note-4 To be continued on additional sheets, if found necessary.						
નોંધ-૪ જરૂર જણાય વધારાના કાગળો જોડી ચાલુ રાખવું.						
Executive Engineer Ambica Division Navsari						