

DCF & DFD (Ist) Tiger Project Sawai Madhopur

G-Schedule

Name of work : Tourism Road Maintnace

Name of site : RTR 1st SWM

Amount : 2.75 Cr.

Year : 2026-27

S.N.	PARTICULARS	Unit	Rate	Amount
1	Bush clearing work	P.100 Sqm	402.60	
2	Earth work in cutting with lead upto 50 m and lift of 1.5 m including dagbelling, finishing of formation to required camber and grade disposed soil to be levelled and dressed in : (e) Soil mixed with boulders above 20% & upto 50%	P.Cum	185.31	
3	Collection of graded gravel/ unscrached canker	P.Cum	194.22	
4	Labour charges for spreading rubble murrum quarry rubbish, Canker, Coarse aggregate etc., to required grade and chamber in layers not exceeding 15 cm thickness (loose) as per specifications including dressing etc., complete	P.Cum	69.87	
5	(a) Carriage and rehandling of cement and other heavy materials including loading and unloading and stacking. (ii) add for each extra 50 m or part thereof upto 500 m.	P.Tonne	12.54	
6	Laying single R.R. stone pitching hand paked including filling of voids with small stones	P.Cum	424.00	
7	Earth work in excavation by mechanical means (Hydraulic Excavator)/ manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m, including taking out the excavated soil and depositing and refilling of jhiri with watering & ramming and disposal of surplus excavated soil as directed with in a lead of 50 meter. All kinds of soils	P.Cum	178.00	
8	Providingand laying inposition cement concrete includingcuring,compactionetc.completeinspecifiedgradeexcluding thecostofcenteringandshuttering- Allworkuptoplinth level. 1:5:10(1cement :5coarsesand:10gradedstoneaggregate 40mm nominal size).	P.Cum	2956.00	
9	M15 grade Nominal Mix 1:2:4(1cement :2coarsesand:4gradedstone aggregate 20mm nominal size).	P.Cum	4624.00	
10	RandomRubble stone masonry for with hard stone in foundationandplinth inCementSandmortar above30CM thick wall in: Cement Mortar 1:6 (1-Cement : 6-Sand).	P.Cum	2838.00	
Total				2.75 Cr.