

**Name of Work :M&R work for Premonsoon Work Of various Roads Under R & B
Sub Division, Kadi, Dist. Mehsana.**

SCHEDULE – B

QUANTITY STATEMENT

It. No.	Description of item	Quantity	Unit	Rate		Total Amount
				In Figures	In words	
1	2	3	4	5	6	7
1	Clearing and grubbing road land including uprooting rank vegetation grass bushes, shrubs, sapling and trees girth up to 300 mm removal of stumps of trees cut earlier and disposal of unserviceable materials (C) By mechanical means in area of light jungle	51.27	Hact	28455.09	Rupees Twenty Eight Thousand Four Hundred Fifty Five And Paise Nine Only	14,58,892.46
2	Earthwork for embankment including breaking clods, dressing with all lead and lift (excluding watering and consolidation)(A) From Borrow pits within land width	1420.00	Cmt	109.05	Rupees One Hundred Nine And Paise Five Only	1,54,851.00
3	Earthwork for embankment including breaking clods, dressing with all lead and lift (excluding watering and consolidation)(D) From Borrow area within 1.0 Km. lead	870.00	Cmt	157.91	Rupees One Hundred Fifty Seven And Paise Ninety One Only	1,37,381.70
4	Collecting, Carting, stacking and Spreading of Quarry Spall approved quality and gradation on road site etc. comp. including all kind of taxes and royalties and filling measure boxes etc. comp.(A) in Cmt Basis.	870.00	Cmt	1303.91	Rupees One Thousand Three Hundred Three And Paise Ninety One Only	11,34,401.70
5	Providing and fixing ordinary Kilometer stone of precast C.C. 1:2:4 including necessary reinforcement as per I.R.C. type design in C.C. 1:4:8 including letter and paints etc. complete (For N.H., S.H. and M.D.R.)	37.00	No	1293.39	Rupees One Thousand Two Hundred Ninety Three And Paise Thirty Nine Only	47,855.43
6	Providing and fixing 5th Kilometer stone of precast C.C. 1:2:4 including necessary reinforcement as per I.R.C. type design in C.C. 1:4:8 including painting, lettering etc. complete (For N.H., S.H. and M.D.R.)	16.00	No	1935.15	Rupees One Thousand Nine Hundred Thirty Five And Paise Fifteen Only	30,962.40
7	Providing and fixing Pre Cast hectometer stone as per I.R.C. type design including painting, lettering etc. com plate. (II) Fixing in C.C.1:5:10	400.00	No	356.50	Rupees Three Hundred Fifty Six And Paise Fifty Only	1,42,600.00
8	Providing and fixing Guard stone as per I.R.C. type design including White washing etc. complete. (a) Fixing in earth.	400.00	No	100.97	Rupees One Hundred And Paise Ninety Seven Only	40,388.00
9	Cleaning of Road Surface including engaging Labour/ Tractor/Trolley/Pavada as required and throwing the stuff within all lead and lift as directed by engineer in charge	360000.00	Smt	3.54	Rupees Three And Paise Fifty Four Only	12,74,400.00
10	Applying White Wash and Geru to trees in three coats as and where directed incl. all cost of materials and labour charges in the work etc.complete as directed.	176.00	Km	6253.92	Rupees Six Thousand Two Hundred Fifty Three And Paise Ninety Two Only	11,00,689.92
TOTAL						₹ 55,22,422.61

It. No.	Description of item	Quantity	Unit	Rate		Total Amount		
				In Figures	In words			
1	2	3	4	5	6	7		
	Total Bid Price (in Figure)	₹ 55,22,422.61						
	(in words)	Rupees Fifty Five Lakh(s) Twenty Two Thousand Four Hundred Twenty Two And Paise Sixty One Only						
<p>I/We am/are willing to carry out the work at _____% above/below the (percentage should be written in figure and words only) Estimated rates as mentioned above, amount of my/our tender works out as under.</p> <table style="width: 100%; border: none;"> <tr> <td style="width: 50%; vertical-align: top;"> <p>Estimated Amount</p> <p>Put to Tender: RS.</p> <p>Deduct:</p> <p>Net : RS.</p> <p>In Words RS.</p> <p>(Please Strike out whichever is not applicable)</p> </td> <td style="width: 50%; vertical-align: top;"> <p>Estimated Amount</p> <p>Put to Tender: RS.</p> <p>Add:</p> <p>Total : RS.</p> <p>In Words RS.</p> </td> </tr> </table>							<p>Estimated Amount</p> <p>Put to Tender: RS.</p> <p>Deduct:</p> <p>Net : RS.</p> <p>In Words RS.</p> <p>(Please Strike out whichever is not applicable)</p>	<p>Estimated Amount</p> <p>Put to Tender: RS.</p> <p>Add:</p> <p>Total : RS.</p> <p>In Words RS.</p>
<p>Estimated Amount</p> <p>Put to Tender: RS.</p> <p>Deduct:</p> <p>Net : RS.</p> <p>In Words RS.</p> <p>(Please Strike out whichever is not applicable)</p>	<p>Estimated Amount</p> <p>Put to Tender: RS.</p> <p>Add:</p> <p>Total : RS.</p> <p>In Words RS.</p>							
<p>Note:</p> <ol style="list-style-type: none"> 1 All work shall be carried out as per public works Department Handbook and other specification of Division or as directed. 2 All the column is schedule should be filled in ink and the total of the entries in the last column should be struck by the contractor under his signature. 3 Rates quoted include clearance of site (Prior Commencement of work and as its close) in all respects and hold good for work under all conditions, site, Moisture, weather etc. 4 To be continued on additional sheets, if found necessary. 								
<p>Signature of contractor</p>		<p>Dy. Executive Engineer R & B Sub Division Kadi</p>		<p>Executive Engineer R & B Division Mehsana</p>				