

GENERAL TECHNICAL SPECIFICATIONS

1.0 General :

All measurements shall be made in the metric system. Different items of work shall be measured in accordance with the procedures set forth in the relevant sections read in conjunction with General Conditions of Contract. The same shall not however apply in the case of lump-sum items. All measurements and computations unless otherwise indicated shall be carried nearest to the following limits :

- (i) length and breadth..... 10 mm
 - (ii) height, depth or thickness of earthwork, sub-base, bases, surfacing, and structural members5 mm
 - (iii) areas,0.01 Sq. Metre
 - (iv) cubic contents..... 0.01 cubic metre
- in recording dimensions of work the sequence of length, width and height or depth or thickness shall be followed.

2.0 Measurement of lead for Materials :

Where lead is specified in the contract for construction materials, the same shall be measured as described hereunder.

Lead shall be measured over the shortest practicable route and not the one actually taken and the decision of the Engineer-in-charge in this regard shall be taken as final. Distance upto and including 100 meters shall be measured in units of 50 metres, exceeding 100 metres but not exceeding 1 KM. in units of 100 metres and exceeding 1 km. in units of 500 metres. The half and greater than half of the units shall be reckoned as one and less than half of the units ignored. In this regard, the source of the material shall be divided into suitable blocks and for each block the distance from the centre of the block to the centre of placing pertaining to that block shall be taken as the lead distance.

3. Surface Regularity of Sub grade & Pavement Courses :

The surface regularity of completed sub-base courses and wearing surfaces in the longitudinal and transverse directions shall be within the tolerances indicated in Table below. The longitudinal profile shall be checked with a 3 metre long straight edge, at the middle of each traffic lane along a line parallel to the centre line of the road. The transverse profile shall be checked with a set of three camber boards at intervals of 10 metres.

PERMITTED TOLERANCES OF SURFACE REGULARITY FOR PAVEMENT COURSES

Sr. No.	Type of Construction	Longitudinal Profile with 3 metre straight edge					Cross Profile
		Maximum Permissible undulation in mm	Maximum number of undulation permitted in any 300m. length exceeding in mm.				
			18	12	10	6	
1	2	3	4	5	6	7	8
1	Earth Sub grade	36	30	-	-	-	15
2	Granular / lime / Cement Stabilised Sub – base.	23	-	30	-	-	12
3	Water Bound Macadam with nominal size metal (20-50) mm	18	-	-	30	-	8
4	Semi – Dense Carpet @	15	-	-	-	20	6

Notes:-

- 1 . These are for machine laid surfaces. If laid manually, due to unavoidable reason, tolerance upto 50 percent above these values in this column may be permitted. However, this relaxation does not apply to the values of maximum undulation for longitudinal and cross profiles mentioned in columns 3 and 8 in the table.
2. Surface evenness requirements in respect of both the longitudinal and cross profiles should be simultaneously satisfied.

3. **Rectification** : Where the surface irregularity of subgrade and the various pavement courses fall outside the specified tolerances, the contractor shall be liable to rectify these in the manner described below and to the satisfaction of the Engineer-in-charge at his own cost.

(i) **Subgrade** : Where the surface is high, it shall be trimmed and suitably compacted. Where the same is low, the deficiency shall be corrected by adding fresh material. The degree of compaction and the type of material to be used shall conform to the specified requirements.

(ii) **Granular/Sub-base** : Same as at (i) above except that the degree of compaction and the type of material to be used shall conform to the specified requirements.

(iii) **Lime/Cement stabilized soil sub-base** : For Lime/Cement treated materials where the surface is high, the same shall be suitably trimmed while taking care that the material below is not disturbed due to this operation. However, where the surface is low, the same shall be corrected as described herein below.

For cement treated material, when the time elapsed between detection of irregularity and the time of mixing of the material is less than 2 hours, the surface shall be scarified to a depth of 50 mm, supplemented with freshly mixed material as necessary and recomposed to the relevant specification. When this time is more than 2 hours, the full depth of the layer shall be removed from the pavement and replaced with fresh material to specification. In either case, the area treated shall not be less than 5 metres long by 2 metres wide. This shall also apply to lime treated material except that the time criterion shall be 3 hours instead of 2 hours.

(iv) **Water Bound Macadam Base** : Where the surface is high or low, the top 75mm shall be scarified, reshaped with added material as necessary and recompacted. The area treated at a place shall not be less than 5 metres long and 2 metres wide.

(v) **Bituminous Constructions** : For bituminous constructions, other than wearing course, where the surface is low, the deficiency shall be corrected by adding fresh material and recompaction to specifications.

Where this surface is high, the full depth of the layer shall be removed and replaced with fresh material and compacted to specifications. For wearing course, where the surface is high or low; the full depth of the layer shall be removed and replaced with fresh material and compacted to specifications in all cases where the removal and replacement of a bituminous layer is involved, the area treated shall not be less than 5 metre long and not less than 1 lane wide.

4. **Quality Control Tests During Construction :**

The materials supplied and the works carried out by the Contractor shall conform to the enclosed relevant specifications. For ensuring the requisite quality of construction, the materials and works shall be subjected to quality control test as described hereinafter, by the Engineer-in-charge. The testing frequencies set forth are the desirable minimum and the Engineer-in-charge shall have the full authority to carry out test as frequently as he may deem necessary to satisfy that the materials at work comply with the appropriate specifications. Test procedures for the various quality control tests are indicated in the respective sections of the specifications or for certain tests within this section. Where no specific testing procedure is mentioned, the test shall be carried out as per prevalent accepted engineering practice to the directions of the Engineer-in-charge.

5. **Tests on Earthwork for Embankment Construction :**

5.1 **Borrow Material :**

- (a) Sand Content (IS : 2720 Part IV)
Two test per 8000 Cubic Metres of soil.
- (b) Plasticity Test (IS : 2720 Part-V)
Each type to be tested. Two tests per 8000 Cubic Metres of soil.
- (c) Density test (IS : 2720 Part VII)
Each soil type to be tested. Two tests per 8000 Cubic Metres of soil.
- (d) Moisture Content Test (IS : 2720 Part-II)
One test for every 250 Cubic Metres of soil.

5.2 **Compaction Control :**

Control shall be exercised by taking at least one measurement of density for each 1000 square metres of compacted area, or closer as required to yield the minimum number of test results for evaluating day's work on statistical basis. The determination of density shall be in accordance with IS. : 2720 (Part XXVMI). Test locations shall be chosen only through random sampling techniques. Control shall not be based on the result of any one test but on the mean value of a set of 5-10 density determinations. The number of tests in one set of measurements shall be 5 as long as it is felt that sufficient control over borrow material and the method of compactions is being exercised. If considerable variations are observed between individual density results, the minimum number of tests in one set of measurement shall be increase to 10. The acceptance of work shall be subject to the condition that the mean dry density equals or exceeds the specified density and the standard deviation for any set of results is below 0.08 gm/cc. However for earthwork in shoulders and in top 500 mm portion of the embankment below the

sub grade, at least one density measurement shall be taken for every 500 square meters of the compacted area provided further that the number of the tests in each set-of measurement shall be at least 10. In other respects, the control shall be similar to that described earlier.

6. Following materials shall conform to the Indian Standards shown against them :

- (1)Cement.....
- (2)Sand for masonry.
- (3).....Sand for concrete.
- (4).....Coarse aggregate.
- (5).....Mild Steel...
- (6)High yield strength deformed bars
 - (a) Hot Rolled..... IS : 1139
 - (b) Cold Twisted..... IS : 1786

7. Barrel thickness of pipes of different class shall be as under :

Sr. No.	Internal Diameter of pipe in mm	Barrel thickness (in mm).		
		NP1	NP2	NP2
1	80	25	25	-
2	100	25	25	-
3	150	25	25	-
4	250	25	25	-
5	300	30	30	-
6	350	32	32	75
7	400	32	32	75
8	450	35	35	75
9	500	-	35	75
10	600	-	40	80
11	700	-	40	80
12	800	-	45	90
13	900	-	50	100
14	1000	-	55	100
15	1100	-	60	115
16	1200	-	65	115

Item No. 1 :- Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed within all lead and lift.

The sub grade / sub base / base to receive the water bound macadam course shall be prepared to the specified grade and camber and made of dust and other extraneous materials. Any nets of soft places shall be corrected in on approved manner and rolled until firm.

Cutting shall be paid on cross section area as established by the longitudinal level and cross sections for this purpose. The work shall be started after the initial longitudinal section of the ground and cross sections are taken and recorded.

The final surface shall confirm to proper profile, camber and super elevation etc. as directed by the Engineer. The earthwork shall be paid on sectional measurements, cross sectional etc. taken.

No allowance or payments shall be made for materials excavated prior to the taking of level by the Engineer.

The rate is inclusive of cutting in all soil and murrum including removal of all shrubs, jungle cutting, cutting stuff in slopes, side drain bank etc. complete.

This item also includes the clearing the sides and demarking the line as per requirement and cutting out the existing tress on the road side, not extra payment will be paid for.

At the time of preparing final bill, the road formation in embankment and cutting shall have be perfect condition true to grade, camber and side slope duly dressed and damages due to rain cuts etc. during entire working period shall have to be done by the contractor.

The work taken in length shall be completed in all respects viz. width, grades, camber, side drains, side slopes etc. and measurements for incomplete work shall not be taken otherwise.

1.0 Mode of Measurement & Payment :

The unit rate box cutting shall include the cost of all materials, tools and plant required for excavation in all type of soils in grade and camber, line and levels and finishing as per direction of the Engineer-in-charge, excavation and all other incidental expenses for producing item of box cutting of specified breadth and depth and grade to complete the item or its components as shown on the drawings and according to these specifications.

The box cutting shall be measured for its cross section area and compacting volumes in cubic metres by the method of average areas.

The rate will be made on **Cubic Meter** basis of the finished work.

Item No. 2 :- Providing, laying and spreading Granular sub base (Grade-I) by providing close graded MCBT material in single layer with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC and compacted with vibratory roller 80 to 110 KN static weight to achieve desired density etc. completed.

401 GRANULAR SUB-BASE

401.1 Scope

This work shall consist of laying and compacting close graded material on prepared subgrade in accordance with the requirements of these Specifications. The material shall be laid in one or more layers as sub-base or lower sub-base and upper sub-base (termed as sub-base hereinafter) as necessary according to lines, grades and cross-sections shown on the drawings or as directed by the Engineer.

402 Materials

401.2.1 The material to be used for the work shall be natural sand, crushed gravel, crushed stone, crushed slag, or combination thereof depending upon the grading required. Use of materials like brick metal, Kankar and crushed concrete shall be permitted in the lower sub-base. The material shall be free from organic or other deleterious constituents and shall conform to the gradings given in Table 400-1 and physical requirements given in Table 400-2. Gradings III and IV shall preferably be used in lower sub-base. Gradings V and VI shall be used as a sub-base-cum-drainage layer. The grading to be adopted for a project shall be as specified in the Contract. Where the sub-base is laid in two layers as upper sub-base and lower sub-base, the thickness of each layer shall not be less than 150 mm.

401.2.2 If the water absorption of the aggregates determined as per IS:2386 (Part 3) is greater than 2 percent, the aggregates shall be tested for Wet Aggregate Impact Value (AIV) (IS:5640). Soft aggregates like Kankar, brick ballast and laterite shall also be tested for Wet AIV (IS:5640).

Table 400-1: Grading for Granular Sub-Base Materials

IS Sieve	Percent by Weight Passing the IS Sieve					
Designation	Grading I	Grading II	Grading III	Grading IV	Grading V	Grading VI
75.0 mm	100	-	-	-	1100	-
53.0 mm	80-100	100	100	100	80-100	100
26.5 mm	55-90	70-100	55-75	50-80	55-90	75-100
9.50 mm	35-65	50-80	-	-	35-65	55-75
4.75 mm	25-55	40-65	10-30	15-35	25-50	30-55
2.36 mm	20-40	30-50	-	-	10-20	10-25
0.85 mm	-	. -	-	-	2-10	-
0.425 mm	10-15	10-15	-	-	. 0-5	0-8
0.075 mm	<5	<5	<5	<5	-	0-3

Table 400-2: Physical Requirements for Materials for Granular Sub-base

Aggregate Impact Value (AIV)	IS:2386 (Part 4) or IS:5640	40 maximum
Liquid Limit	IS:2720 (Part 5)	Maximum 25
Plasticity Index	IS:2720 (Part 5)	Maximum 6
CBR at 98% dry density (at IS:2720-Part 8)	IS:2720 (Part 5)	Minimum 30 unless otherwise specified in the Contract

401.2 Construction Operations**401.2.1 Preparation of Sub-grade**

Immediately prior to the laying of sub-base, the subgrade already finished to Clause 301 or 305 as applicable shall be prepared by removing all vegetation and other extraneous matter, lightly sprinkled with water, if necessary and rolled with two passes of 80-100 kN smooth wheeled roller.

401.3.2 Spreading and Compacting

The sub-base material of the grading specified in the Contract and water shall be mixed mechanically by a suitable mixer equipped with provision for controlled addition of water and mechanical mixing. So as to ensure homogenous and uniform mix. The required water content shall be determined in accordance with IS:2720 (Part 8). The mix shall be spread on the prepared subgrade with the help of a motor grader of adequate capacity, its blade having hydraulic controls suitable for initial adjustment and for maintaining the required slope and grade during the operation, or other means as approved by the Engineer.

Moisture content of the mix shall be checked in accordance with IS:2720 (Part 2) and suitably adjusted so that, at the time of compaction, it is from 1 to 2 percent below the optimum moisture content.

Immediately after spreading the mix, rolling shall be done by an approved roller. If the thickness of the compacted layer does not exceed 100 mm, a smooth wheeled roller of 80 to 100 kN weight may be used. For a compacted single layer, up to 200 mm the compaction shall be done with the help of a vibratory roller of minimum 80 to 100 kN static weight capable of achieving the required compaction. Rolling shall commence at the lower edge and proceed towards the upper edge longitudinally for portions having unidirectional cross fall or on super-elevation. For carriageway having cross fall on both sides, rolling shall commence at the edges and progress towards the crown.

Each pass of the roller shall uniformly overlap not less than one-third of the track made in the preceding pass. During rolling, the grade and cross fall (camber) shall be checked and any high spots or depressions which become apparent, corrected by removing or adding fresh material. The speed of the roller shall not exceed 5 km per hour.

Rolling shall be continued till the density achieved is at least 98 percent of the maximum dry density for the material determined as per IS:2720 (Part 8). The surface of any layer of material on completion of compaction shall be well closed, free from movement under compaction equipment and

from compaction planes, ridges, cracks, or loose material. All loose, segregated or otherwise defective areas shall be made good to the full thickness of layer and re-compacted.

401.4 Surface Finish and Quality Control of Work

The surface finish of construction shall conform to the requirements of Clause 902. Control on the quality of materials and works shall be exercised by the Engineer in accordance with Section 900.

401.5 Arrangements for Traffic

During the period of construction, arrangements for the traffic shall be provided and maintained in accordance with Clause 112.

401.6 Measurements for Payment

Granular sub-base shall be measured as finished work in position in cubic metres.

The protection of edges of granular sub-base extended over the full formation as shown in the drawing shall be considered incidental to the work of providing granular sub-base and as such no extra payment shall be made for the same.

401.7 Rate

The Contract unit rate for granular sub-base shall be payment in full for carrying out the required operations including full compensation for:

- i. making arrangements for traffic to Clause 112 except for initial treatment to verges, shoulders and construction of diversions;
- ii. supplying all materials to be incorporated in the work including all royalties, fees, rents where applicable with all leads and lifts;
- iii. all labour, tools, equipment, and incidentals to complete the work to the Specifications;
- iv. carrying out the work in part widths of road where directed; and
- v. carrying out the required tests for quality control.

Item No. 3 :- Providing & laying compacted WBM Grading-II using MCBT metal of size 53mm to 22.4mm in required layers including using 24% stone screening, 11.2mm size and 8% stone dust as filler including spreading, watering and consolidation by vibratory roller as per MORTH specification etc complete as directed by engineer in charge.

404.1 SCOPE

This work shall consist of clean, machine crushed B.T. stone aggregates mechanically interlocked by rolling and bonding together with screening, binding material where necessary and water laid on a properly prepared sub grade/ sub bases base or existing pavement, as the case may be and finished in accordance with the requirements of these specifications and in close conformity with the lines, grades, cross-sections and thickness as per approved plans or as directed by the Engineer.

404-2. Materials

404.2.1 Coarse aggregates

Coarse aggregates shall be either crushed or broken stone, crushed slag, overburnt (Jhama) brick aggregates or any other naturally occurring aggregates such as kankar and laterite of suitable quality. Materials other than crushed gravel / shingle is used, not less than 90 percent by weight of the gravel / shingle pieces retained on 4.75mm sieve shall have at least two fractured faces. The aggregates shall conform to the physical requirements set forth in Table 400-8. The type and size range of the aggregate shall be specified in the contract or shall be as specified by the Engineer. If the water absorption value of the coarse aggregate is greater than 2 percent, the soundness test shall be carried out on the material delivered to site as per IS:2386 (Part-5).

TABLE 400-8. PHYSICAL REQUIREMENTS OF COARSE AGGREGATES FOR WATER BOUND MACADAM FOR SUB-BASE / BASE COURSES

S.No. Test	Test Method	Requirement
1. *** Los Angeles Abrasion value or Aggregate Impact value	IS:2386 (Part-4) IS: 2386 (Part-4) or IS:5640*	40 percent (Max) 30 percent (Max)
2. Combined Flakiness and Elongation - Indices (Total)**	IS:2386 (Part- 1)	30 percent (Max)

* Aggregate which get softened in presence of water shall be tested for impact value under wet conditions in accordance with IS:5640.

** The requirement of flakiness index and elongation index shall be enforced only in the case of Crushed broken stone and crushed slag.

*** In case water bound macadam is used for sub-base, the requirements in respect of Los Angeles Value and Aggregate impact value shall be relaxed to 50 percent and 40 percent maximum respectively.

404.2.2 Crushed or broken stone

The crushed or broken stone shall be hard, durable and free from excess flat, elongated, soft and disintegrated particles, dirt and other deleterious material.

404.2.3. Crushed slag :

Crushed slag shall be made from air-cooled blast furnace slag. It shall be of angular shape, reasonably uniform in quality and density and generally free from thin, elongated and soft pieces, dirt or other deleterious materials. The weight of crushed slag shall not be less than 11.2 kN per m³ and the percentage of glossy material shall not be more than 20. It should also comply with the following requirements:

- (i) Chemical stability : To comply with requirement of appendix of BS : 1047
- (ii) Sulphur content : Maximum 2 per cent
- (iii) Water absorption : Maximum 10 per cent

404.2.4. Overburnt (Jhama) Brick aggregates :

Jhama brick aggregates shall be made from overburnt bricks or brick bats and be free from dust and other objectionable and deleterious materials. This shall be used only for road stretch when traffic is low.

404.2.5. Grading requirement of Coarse aggregates :

The coarse aggregates shall conform to one of the Gradings given in Table 400-9 as specified.

404.2.6. Screenings:

Screenings to fill voids in the coarse aggregate shall generally consist of the same material as the coarse aggregate. However, where permitted, predominantly non-plastic material such as murrum or gravel (other than rounded river borne material) may be used for this purpose provided liquid limit and plasticity index of such material are below 20 and 6 respectively and fraction passing 75 micron sieve does not exceed 10 per cent.

TABLE 400-9 : GRADING REQUIREMENTS OF COARSE AGGREGATES

Grading No.	Size Range	IS Sieve Designation	Per cent by weight passing
1.	63 mm to 45 mm	75 mm	100
		63 mm	90-100
		53 mm	25-75
		45 mm	0-15
		22.4 mm	0-5
2.	53 mm to 22.4 mm	63 mm	100
		53 mm	95-100
		45 mm	65-90
		22.4 mm	0-10
		11.2 mm	0-5

Note : The compacted thickness for a layer shall be 75mm.

Screenings shall conform to the grading set forth in Table 400–10. The quantity of screenings required for various grades of stone aggregates are given in Table 400–11. The table also gives the quantities of materials (loose) required for 10 m² for sub-base / base compacted thickness of 75 mm. The use of screenings shall be omitted in the case of soft aggregates such as brick metal, kankar, laterites etc. as they are likely to get crushed to a certain extent under rollers.

404.2.7 Binding Material :

Binding material to be used for water bound macadam as a filler material meant for preventing ravelling, shall comprise of a suitable material approved by the Engineer having a Plasticity Index (PI) value of less than 6 as determined in accordance with IS:2720 (Part 5).

The quantity of binding material where it is to be used will depend on the type of screening. Generally, the quantity required for 75 mm compacted thickness of water bound macadam will be 0.06 – 0.09 m³ / 10 m².

TABLE 400 – 10. GRADING FOR SCREENINGS

Grading Classification	Size of Screenings	IS Sieve Designation	Per cent by weight passing the IS sieve
A	13.2 mm	13.2 mm	100
		11.2 mm	95-100
		5.6 mm	15-35
		180 micron	0-10
B	11.2 mm	11.2 mm	100
		9.5 mm	80-100
		5.6 mm	50-70
		180 micron	5-25

TABLE 400 – 11. APPROXIMATE QUANTITIES OF COARSE AGGREGATES AND SCREENINGS REQUIRED FOR 75 MM COMPACTED THICKNESS OF WATER BOUND MACADAM (WBM) SUB-BASE / BASE COURSE FOR 10 M² AREA

Classification	Size Range	Compact thickness	Loose Qty.	Screenings			
				Stone screening		Crushable type such as murrum or gravel	
				Grading classification and size	For WBM sub-base / base course (loose Qty)	Grading classification and size	Loose Qty.
Grading 1	63mm to 45 mm	75 mm	0.91 to 1.07m ³	Type A 13.2 mm	0.12 to 0.15 m ³	No uniform	0.22 to 0.24 m ³
- do -	- do -	- do -	- do -	Type B 11.2 mm	0.20 to 0.22 m ³	- do -	- do -
Grading 2	53mm to 22.4 mm	75 mm	- do -	- do -	0.18 to 0.21 m ³	- do -	- do -

The above mentioned quantities should be taken as a guide only, for estimation of quantities for construction etc.

Application of binding materials may not be necessary when the screenings used are of crushable type such as murrum or gravel.

404.3 Construction Operations

404.3.1 Preparation of base :

The surface of the sub grade sub-base/base to receive the water bound macadam course shall be prepared to the specified grade and camber and cleaned of dust, dirt and other extraneous material. Any ruts or soft yielding places shall be corrected in an approved manner and rolled until firm surface is obtained.

Where the WBM is to be laid on an existing metalled road, damaged area including depressions and potholes shall be repaired and made good with the suitable material. The existing surface shall be scarified and re-shaped to the required grade and camber before spreading the coarse aggregate for WBM.

As far as possible, laying water bound macadam course over an existing bituminous layer may be avoided since it will cause problems of internal drainage of the pavement at the interface of two courses. It is desirable to completely pick out the existing thin bituminous wearing course where water bound macadam is proposed to be laid over it.

404.3.2 Inverted Choke / Sub surface Drainage layer

If water bound macadam is to be laid directly over the subgrade, without any other intervening pavement course, a 25 mm course of screenings (Grading B) or coarse sand shall be spread on the prepared subgrade before application of the aggregates is taken up. In case of a fine sand or silty or clayey subgrade, it is advisable to lay 100 mm insulating layer of screening or coarse sand on top of Fine grained soil, the gradation of which will depend upon whether it is intended to act as a drainage layer as well. As a preferred alternative to inverted choke, appropriate geosynthetics performing functions of separation and drainage may be used over the prepared subgrade as directed by the Engineer. Section 700 shall be applicable for use of geosynthetics.

404.3.3 Lateral Confinement of Aggregates

For construction of WBM, arrangement shall be made for the lateral confinement of aggregates. This shall be done by building adjoining shoulders along with WBM layers. The practice of constructing WBM in a trench section excavated in the finished formation must be completely avoided.

Where the WBM course is to be constructed in narrow widths for widening of an existing pavement, the existing shoulders should be excavated to their full depth and width upto the sub grade level except where widening specifications envisages laying of a stabilised sub base using in situ operations in which case the same should be removed only upto the sub base level.

404.3.4 Spreading coarse aggregates:

The coarse aggregates shall be spread uniformly and evenly upon the prepared sub grade/sub-base/ in the required quantities from the stock piles to proper profile by using templates placed across the road about. 6 m apart, in such quantities that the thickness of each compacted layer is not more than 75 mm. In no case shall these be dumped in heaps directly on the area where there are to be laid nor shall their hauling over a partly completed base be permitted. Wherever possible approved mechanical devices such as aggregate spreader shall be used to spread the aggregates uniformly so as to minimize the need for manual rectification afterwards.

No segregation of coarse aggregate shall be allowed and the coarse aggregates, as spread shall be of uniform gradation with no pockets of fine material.

The surface of the aggregate spread shall be carefully checked with templates and all high or low spots remedied by removing or adding aggregates as may be required. The surface shall be checked frequently with a straight edge while spreading and rolling so as to ensure a finished surface as per approved drawings.

The coarse aggregate shall not normally be spread more than 3 days in advance of the subsequent construction operations.

404.3.5 Rolling:

Immediately following the spreading of the coarse aggregate, rolling shall be started with three wheeled power rollers of 80 to 100 kN capacity or tandem or vibratory rollers of 80 to 100 kN static weight. The type of roller to be used shall be approved by the Engineer based on trial run.

Except on super elevated portions and carriageway with unidirectional cross-fall, where the rolling shall proceed from inner edge to the outer, rolling shall begin from the edges gradually progressing towards the centre. First the edge/edges shall be compacted with roller running forward and backward. The roller shall then move inward parallel to the centre line of the road, in successive passes uniformly overlapping preceding tracks by at least one half width.

Rolling shall be carried out on courses where coarse aggregates of crushed / broken stone are used, till the road metal is partially compacted. This will be followed by application of screening and binding material where required in Clauses 404.3.6 and 404.3.7.

However, where screenings are not to be applied as in the case of aggregates like brick metal laterite and kankar for the sub base construction, the compaction shall be continued until the aggregates are thoroughly keyed. Rolling shall be continued and light sprinkling of water shall be done till the surface is well compacted. Rolling shall not be done when the sub grade is soft or yielding or when it causes a wave-like motion in the sub grade or sub base course.

The rolled surface shall be checked transversely with templates and longitudinally with 3 m. straight edge. Any irregularities exceeding 12mm shall be corrected by loosening the surface, adding or removing necessary amount of aggregates and re-rolling until the entire surface conforms to desired camber and grade. In no case shall the use of screenings be permitted to make up depressions.

Material which gets crushed excessively during compaction or becomes segregated shall be removed and replaced with suitable aggregates.

404.3.6 Application of screenings:

After the coarse aggregate have been rolled to Clause 404.3.5, screenings to completely fill the interstices shall be applied gradually over the surface. These shall not be damp or wet at the time of application. Dry rolling shall be done while the screenings are being spread so that vibrations of the roller cause them to settle into the voids of the coarse Aggregate. The screenings shall not be dumped in piles but be spread uniformly in successive thin layers either by the spreading motion & of hand shovels or by mechanical spreaders or directly from tipper with suitable grit spreading arrangement Tipper operating for spreading the screenings shall be equipped with pneumatic tyres and operated so as not to disturb to coarse aggregates.

The screenings shall be applied at a slow and uniform rate (in three or more applications) so as to ensure filling of all voids. This shall be accompanied by dry rolling and brooming with mechanical brooms, hand brooms or both. In no case shall the screenings be applied so fast and thick as to form cakes or ridges on the surface in such a manner as would prevent filling of voids or prevent the direct bearing of the roller on the coarse aggregate. These operations shall continue until no more screenings can be forced into the voids of the coarse aggregate.

The spreading, rolling and brooming of screenings shall be carried out in only such lengths of the road which could be completed within one day's operation.

404.3.7 Sprinkling of water and grouting :

After application of screenings, the surface shall be copiously sprinkled with water, swept and rolled. Hand brooms shall be used to sweep the wet screenings into voids and to distribute them evenly. The sprinkling, sweeping and rolling operation shall be continued, with additional screenings applied as necessary until the coarse aggregate have been thoroughly keyed, well-bonded and firmly set in its full depth and a grout has been formed of screenings. Care shall be taken to see that the sub base or sub grade does not get damaged due to the addition of excessive quantities of water during construction.

In case of lime treated soil sub-base, construction of water bound macadam on top of it shall be taken up after curing as per Clause 402.3.9 and as directed by the Engineer.

Application of binding material : After the application of screenings in accordance with Clauses 404.3.6 and 404.3.7, the binding material where it is required to be used (Clause 404.2.7) shall be applied successively in two or more thin layers at a slow and uniform rate. After each application, the surface shall be copiously sprinkled with water, the resulting slurry swept in with hand brooms or mechanical brooms to fill the voids properly and rolled during which water shall be applied to the wheels of the rollers if necessary to wash down the binding material sticking to them. These operations shall continue until the resulting slurry after filling of voids, form a wave ahead of the wheels of the moving roller .

404.3.8 Setting and drying :

After the final compaction of water bound macadam course, the pavement shall be allowed to dry overnight. Next morning hungry spots shall be filled with screenings or binding material as directed, lightly sprinkled with water if necessary and rolled. No Traffic shall be allowed on the road until the macadam has set. The Engineer shall have the discretion to stop hauling traffic from using the completed water bound macadam course, if in his opinion it would cause excessive damage to the surface.

The compacted water bound macadam course should be allowed to completely dry and set before the next pavement course is laid over it.

404.4 Surface Finish and Quality Control of Work

404.4.1 The surface finish of construction shall conform to the requirements of Clause 902.

404.4.2 Control on the quality of materials and works shall be exercised by the Engineer in accordance with Section 900.

404.4.3 The water bound macadam work shall not be carried out when the atmospheric temperature is less than 10° C in the shade.

404.4.4 Reconstruction of defective macadam :

The finished surface of water bound macadam shall conform to the tolerance of surface regularity as prescribed in Clause 902. However, where the surface irregularity of the course exceeds the tolerances or where the course is otherwise defective due to sub grade soil mixing, with the aggregates, the course to its full thickness shall be scarified over the affected area, reshaped with added material or removed and replaced with fresh material as applicable and re-compacted. The area treated shall not be less than 10 sq.m. In no case shall depressions be filled up with screenings or binding material.

404.5 Arrangement for Traffic

During the period of construction, the arrangement for traffic shall be done as per Clause 112.

404.6 Mode of Measurement & payment

Water bound macadam shall be measured as finished work in position in **cubic meters**.

404.7 RATE

The Contract unit rate for water bound macadam sub-base/base course shall be payable in full for carrying out the required operations including full compensation for all components listed below including arrangement of water used in the work as approved by the Engineer.

- (i) Making arrangements for traffic to Clause 112 except for initial treatment to verges, shoulders and construction of diversions;
- (ii) Supplying all materials to be incorporated in the work including all royalties, fees, rents where applicable with all leads and lifts,
- (iii) All labour, tools, equipment and incidental to complete the work to the Specifications
- (iv) Carrying out the work in part widths of the road where required and
- (v) Carrying out the required tests for quality control.

Item No. 4 : Earthwork for embankment including breaking clods, dressing with all lead and lift including rolling with power roller, watering and consolidation from borrow pits within land width.

1. The land width on which the earth work is to be done shall be cleared of all trees having a girth of 30 cm and less, loose stones, vegetation, bushes, stumps and all other objectionable materials. All the materials cleared will be the property of Government. Useful material shall be arranged in convenient stacks along the roads boundary or as directed at places within 50 metres lead, and handed over to the department in convenient sections. Unsuitable material shall be burnt or otherwise disposed off by the contractor at his own cost without causing any nuisance. inconvenience or damage to the works, property or people in the neighborhood. In all cases, the materials shall be disposed off in a neat manner.
2. After clearing the site, the alignment of the road shall be properly set out true to line, curves, slopes, grades and sections as shown on then plan or directed by the Engineer-in-charge. 'The contractor shall provide all labours and materials such as lime, string, pegs, nails, bamboos, stones, mortar, concrete etc. required for setting out, establishing Bench Marks and giving profiles. The contractor shall be responsible for maintaining the B.M.S. profiles alignments and other marks as long as they are required for the work in the opinion of the Engineer-in-charge. If the contractor defaults in this respect they may be restored by the department at the cost of the contractor.
3. When an existing embankment is to be widened, continuous, horizontal benches, each at least 0.3 metre wide, shall be cut into existing slope for ensuring adequate bond with the fresh embankment material to be added. The material obtained from the cutting of benches can be utilised in the widening of the embankment. Where the width of the widened portions is insufficient to permit the use of usual rollers, compactions shall be carried out with the help of tandem/sheepfoot rollers, mechanical tampers or other approved plant. The dumping of material from trucks for widening operations shall be avoided except in difficult circumstances when the extra width is too narrow to permit the movement of any other type of hauling equipment.
4. The soil to be used for embankment shall be free from trees, stumps, roots, rubbish or any other objectionable materials. Only materials considered suitable by the Engineer-in-charge shall be used for the construction and that considered unsuitable shall be disposed off as directed by him. The selection of materials to be used in the construction of embankment shall be made after soil survey and investigations are carried out by the Department. The embankment shall consist of earth available from road-side borrow pits on either side with all lead and lifts.
5. The materials satisfying the density requirements given the table shall be employed for embankment construction.

S.No.	Type of work	Laboratory dry density when tested as per IS:2720(Pt. VII)
1.	Embankments upto 3 metres height, not	Not less than 1.44 gm/cc
2.	Embankments exceeding 3 metres height or embankments of any height subject to long periods of inundation.	Not less than 1.52 gm/cc
3.	Top 0.5 metre of embankment below the sub grade level and shoulder [Where earth shoulder are specified]	Not less than 1.65 gm/cc

Field density shall be a percentage of laboratory density as recommended by the Gujarat Engineering research institute. Location, shape and size of borrow pits shall be as indicated by the Engineer-in-charge. Pits shall not be dug continuously. Ridges of not less than 8 metres width should be left at intervals not exceeding 300 metre. Small drain shall be cut through the ridges of facilities drainage. The outer edge of borrow pits shall be so regulated that the bottom does not cut an imaginary line having a slope of 1 vertical to 4 horizontal projected from the edge of final section of the bank, the maximum depth in any case being limited to 1.5 metres. Also no pits shall be dug within 5 metres of the tow of the final section of the road embankment.

- 5.1 No borrow pits shall be allowed at the following sites along the road.
- (i) upto 30 metres on either side of C.D. Works;
 - (ii) upto 15 metres on either side of cart rack crossing for which approaches are to be constructed
 - (iii) in the length in which earth obtained from cutting is specified to be used in the embankment.
- 5.2 If there is top layer of black cotton or other objectionable soils, the same shall be removed and disposed off elsewhere and usable material found at lower level will only be used in earthen embankment.
6. The embankment shall be constructed in uniform layers not exceeding 250 mm in loose thickness. The soil shall be spread uniformly over the entire width of the embankment. Unless otherwise directed by the Engineer-in-charge. The consolidation including watering and rolling of earthwork shall be carried out by the Department, The operation of laying the successive layer of earth shall have to be suitably synchronized with the consolidation work. If the soil as delivered to the road is too wet, it shall be dried by exposure to the sun till the moisture content is acceptable for compaction. All clods of hard lumps of earth shall be broken to have maximum size of 15 cm. when being placed in the embankment and a maximum size of 5 cm. when being placed in the top 45 cm. of the embankment. The work of next layers shall be allowed only after the first layer below it has been thoroughly compacted to the density specified.

7. Where an embankment is to be placed on sloping ground, the surface of the ground shall be benched in the step of trenches or broken up in such a manner that the new material shall have perfect bond with the existing surface. Where the embankment is to be placed over an existing surface, the new material. However when the embankment is to be placed over an old concrete, pavement shall be broken up in pieces not to exceed 0.1 m and may be left under the new-embankment. If the existing road surface is of granular or bituminous type and lies within 1 mt. of the new subgrade level, the same shall be scarified to a depth of minimum 50 mm. so as to provide ample bond between the old and the new material.
8. To avoid interference with construction of abutments, wing walls or return walls of culverts/bridge structures, the contractor shall, at point to be determined by the Engineer-in-charge, suspend work on embankments forming approaches to such structures, until such time as the construction of the latter is sufficiently advanced to permit the completion of approaches without the risk of interference of damage to the bridge work. Unless directed otherwise the filling around culverts, bridge and other structures up to a distance of twice the height of the embankment from the back of the embankment shall be carried out independent of the work on the main embankment. The fill materials shall not be placed against any abutment or wing wall unless permission has been given by the Engineer-in-charge but in any case not until the concrete or masonry has been in position for 14 days. The embankment shall be brought up simultaneously in equal layers on each side of the structure to avoid displacement and unequal pressure. The sequence of work in this regard shall be got approved from the Engineer-in-charge. Where the provision of any filter medium is specified behind the abutment, the same shall be laid in layers simultaneously with the laying of fill material the material used for the filler shall conform to the requirement rollers or other heavy equipment, the compaction shall be carried out by mechanical tampers or other methods approved by the Engineer-in-charge. Care shall be taken to see that the compaction plant does not hit or come too close to any structural members so as to cause any damage to them.
9. The embankment shall be finished in conformity with the alignment, level, cross sections and dimensions shown on the plans or as directed by the Engineer-in-charge. Where the alignment of the road is in a curve, the top of the embankment shall be formed with the super elevation and the increased width shown on the drawings or as the Engineer-in-charge may direct. Finishing operations shall include the work of shaping and dressing the shoulder, road bed and the slopes to conform to the cross section.
10. The consolidation of earth work including rolling and watering at O.M.C. as per laboratory requirement shall be carried out by the Department, the field and laboratory investigations and testing of samples shall be carried out by the department. However, the contractor shall give full co-operation and shall bear the charges for layout and collection of samples for testing at authorized Government laboratory. The work of laying of earthwork in layers shall be synchronized with the work of compaction and consolidation of the earth work and the

operations shall also be synchronized with the field and laboratory testing. When density measurements reveal any soft areas in the embankment, the Engineer-in-charge shall direct that these areas shall be compacted further. In spite of that, specified compactions is not achieved, the materials in the soft area shall be removed as directed and replaced by the approved materials. Deduction of 15% shall be made for the shrinkage from the sectional measurements to be paid to the contractor, if measured before first monsoon and 10% measured after one or more monsoon have passed over the earth embankment.

11. The earth work measurements shall be paid on cross sectional measurements and computing the volumes of earth-work in cubic metres by average area method. The contractor shall sign day to day leveling work and also original cross sections in token of his acceptance etc. The working sections both longitudinal and cross of the ground shall be taken by the Engineer-in-charge before the actual earth work is started. The contractor or his authorised representative shall attend day to day leveling work and sign with date the field book daily, in token of this acceptance. If there is any disagreement the contractor shall inform of it in writing to the officer concerned of any complaint shall be taken. Merely not signing of the level book shall not be deemed as disagreement. The Executive Engineer shall also verify leveling work to the extent of 5% before commencement of earth work and on finalisation. The contractor shall maintain the embankment by filling in ruts, rain cuts depression due to shrinkage etc. to proper formation and grade till this item is finally measured and accepted by the Department. The measurement shall be taken on compacted earth work, no deduction for shrinkage shall be made from gross measured quantity of compacted earth work. However the contractor shall have to bear loss of quantity due to all settlement as well as other types of deformations etc. if any that might have taken place at the time of taking the final measurement of this item. If the Compaction as stipulated in para-10 is not done by the department in that case shrinkage from such earthwork quantity shall be deducted as per norms, i.e. 10% after monsoon and 15% before monsoon.
12. The rate of earthwork includes clearing jungles, dogbelling, fixing profiles, erecting necessary pillars or stones for bench mark for leveling purpose, excavating earth from borrow pits, breaking clods, conveying and spreading earth in layers with all lead and lift, finishing the entire embankment to the proper profile camber, grade and slopes. The rate also includes all labour, materials, tools, equipment and incidentals necessary to complete the work according to the specifications. Cutting stuff of cutting in ordinary soil, soft murrum, soft rock, hard murrum and hard rock shall be utilised in embankment construction under this item within the lead specified in that particular item. No payment shall be made under this item for the cutting stuff used in the embankment but labour for cutting will be paid as per specifications in the particular item and only balance quantity brought from borrow pits will be paid in this item.
12. If usable approved materials is available within the land width of road, the same shall be permitted for use in the road embankment subject to the following conditions :-

- (i) The borrow pits will be so excavated as to form a road side longitudinal gutter to drain the water interrupted by such gutter,
 - (ii) The width of the drain shall be restricted to 1.5 mts, only. The depth will be restricted to such grade so as to drain the water efficiently. All balance quantity of earth shall be brought from distant borrow areas only.
 - (iii) If there is top layer of black cotton or other objectionable soils, the same be removed and disposed off elsewhere and usable material found at the lower level will only be used in the earthen embankment, if the contractor chooses to utilize this material.
 - (iv) The drain should be aligned along the boundary of the land width of the road. No pit, other than this drain, shall be dug within 5 metres of the toe to the final section of the road embankment,
 - (v) No borrow pits shall be allowed in the length in which earth obtained from cutting is specified to be used in embankments.
13. The rate of earthwork includes clearing jungles, dogbelling. fixing profiles, erecting necessary pillars for stones for bench marks for leveling purpose, excavating earth from borrow areas, breaking clods, conveying and spreading earth in layers with all lead and Lift, finishing the entire embankment and incidentals necessary to complete the work to the specifications. The cutting stuff of cutting in ordinary soil, soft murrum, soft rock, hard murrum and hard rock shall be utilised in embankment construction under this item within the lead specified in that particular item. No payment shall be made under this item for the cutting stuff used in the embankment but labour for cutting will be paid as per specifications in that particular item, and only balance quantity of earthwork brought from borrow areas will be paid in this item.
14. Payment shall be made in **Cubic meter** basis.

Item No. 5 : Providing and laying compacted of specified quarry spaul in side shoulder including carriage of material and spreading on prepared base including compacting as per MORTH specification etc. complete.

1. The quarry spauls shall be approved quarry as approved by the Ex. Engineer prior to collection. Filling of boxes, shall not be allowed till the metal is broken to the specified site.
2. The quarry spaul shall be as uniform in size as possible. The quarry spaul shall be hard, tough, solid durable of black trap quarry of close texture, free from decay and weathering. The stone shall be angular and roughly cubical in shape and round elongated or flaky materials shall be rejected. No sound or long rubble or angular chips smaller than specified size shall be allowed.

Grading for quarry spauls

IS:Sieve	Grading - I	Grading - II	Grading - III
75mm	100	-	-
53mm	-	100	-
26.5mm	55-75	50-80	100
9.50 mm	-	-	-
4.75mm	10-30	15-35	25-45
2.36mm	-	-	-
0.425mm	-	-	-
0.075mm	< 10	< 10	< 10

Material passing through 425 micro sieve for all the three gradings when tested according to I.S. 2720 (Part-5) shall have liquid limit and plastic index not more than 25 and 6 respectively.

3. All unsound, weathered or disintegrated stone obtained from the under surface layer of the quarry or other layers of boulders shall be rejected.
4. Wherever any doubt as to whether above requirement are satisfied in whole or part of the collection it shall be got screened by the Contractor if so ordered by the Executive Engineer, and for which no extra payment shall be claimed by the contractor
5. Any collection which does not fully satisfy the above requirements is liable to be rejected all together.
6. Regular stacks shall be made by the contractor on a fairly level ground. All the stack shall be marked by white wash immediately on being measured and recorded by the Engineer-in-charge.
7. The rate includes blasting the rock, if any, breaking the quarry spauls, stacking measuring in pharas etc. complete.
8. Stacks shall as per actual requirements and any materials in excess shall have to be transported by the contractor at the places directed by the Executive Engineer at the risk and cost of the contractor.
9. While stacking materials the depositing should commence at one end of the K.M. and carried continuously towards the other end unless the Executive Engineer shall direct otherwise and as a rule measurements shall be taken after metal for halt kilometer or Km. has been fully collected. Any fraction of these distance shall not be measured up.

10. The measurements shall be recorded in on Cum. basis on level computing method after rolling and consolidation and shall be paid accordingly.
- **Spreading quarry spauls in grade & camber complete.**
1. The quarry spauls shall be only be allowed to be spread after the written permission of the Executive Engineer is obtained.
2. The permission for spreading the metal shall *be* given by the Executive Engineer if
 - (i) The full quantity of a particular mile(kilometer)is completely collected.
 - (ii) The collection of metal-is also completed in the adjoining two miles (Kilometers)
 - (iii) The measurements are recorded in the Measurement book.
3. Q. S. shall if required, be screened, if containing rubbish dust, grass etc. it shall than be filled in basket & conveyed where required and spread evenly on the prepared surface be given twisting motion to the basket at the time of spreading. The surface shall then (15 m) by means of templates and strings as well as with camber boards and spirit level.
4. Between the straight length and curves and at the meeting points of the convex and concave portions of the reverse curves, the change in camber of the road, due to super elevations shall be made as well as with camber boards and spirit level.
5. At the time of spreading Q. S. a small quantity (about 4 to 5 percent) of metal as directed, shall be retained at the first instance. It shall be spread later 0:1 after partial consolidated as required to rectify the camber and to fill up the hollows if any. No extra amount shall be paid for this.
6. Measurements shall be paid as per the measurements of collection less the quantity remained to be spread and on cubic metre basis.
7. The rate includes the cost of screening the Q.S. if any spreading, sectioning, with template and adding reserved quota of metal, while/oiling is in progress for making good hollows and camber.
8. The surface shall be brought to the required camber which shall be checked at every 50 ft.(15 M) by means off templates of while the necessary of the in between shall tested by strings and corrected as required.
9. The centre line shall first be marked in the subgrade which is properly consolidated and has uniform carnber and grade as required
10. The Q. S. shall be laid for a small length on 25 ft. (8 M.) and then the edge stones shall be laid.
11. Pegs shall be driven on either side of the road and joined with strings true and parallel with a distance between they equal to the width be laid with over metal Similarly.
12. The Q. S. shall be laid as close as possible so as too leave minimum possible interstices and voids.
13. Before roiling is allowed on soling the side berms shall be filled upto the top of the soling and at least 3'-0" (1 m.) on either side so as to prevent metal layer getting disturbed at times during rolling. The rate is inclusive of all the operations as stated above.
14. Immediately following the spreading of the coarse aggregates rolling shall be started with

three wheeled power roller of 8 - to - 10 tone capacity or tendum roller or equivalent vibratory roller. The weight of the roller shall depend upon the type of the aggregate and be indicated by Engineer-in-charge.

15. Except on super elevated portions where the roiling shall proceed from inner edge to outer, rolling shall from the edges gradually progressing towards the centre. First the edge / edges shall be compacted with roller running forward and backward. The roller shall then move inward parallel to centre line of the road, in successive passes uniformly lapping preceding tracks by at least one half the width.
16. Rolling shall continue until the aggregate is thoroughly keyed and the creeping of the aggregate a head of the roller is no longer visible. During rolling, slight sprinkling of water may be done, if necessary. Rolling shall no be done when the sub grade is soft or yielding or when it causes a wave like motion in the sub grade or sub base course.
17. The rolled surface shall be checked transversely and longitudinally with templates and any irregularities corrected by loosening the surface, adding or removing necessary amounts of aggregate and re - rolling until the entire surface conform to desired camber and grade. In no case shall the base of screening be permitted to make up depression.
18. The blindage material where it is required to be used shall be applied successively in two or more thin layer at a slow and uniform rate. After each application, the surface shall be copiously sprinkled with water, the resulting, slurry swept in with hand brooms or mechanical brooms to fill the voids properly and rolled during which water shall be applied the wheels of the rollers, if necessary to wash down the binding material sticking to them. These operations shall continue until the resulting slurry after filling of voids forms a wave ahead of the wheels of the moving roller.
19. After the final compaction of water bound macadam course, the road shall be allowed to any over night Next morning hungry spots shall be filled with screenings of binding materials as directed lightly sprinkled with water, if necessary and rolled. No traffic shall be allowed on the road until the macadam has set. The Engineer - in - charge shall have the discretion to stop hauling traffic from using the completed water bound macadam course, if in his opinion, it would cause excessive damage to the surface.

➤ **Mode of Measurement & Payment**

1. Measurements shall be paid as per the measurements of collection less the quantity remained to be spread and on **cubic meter** basis.
2. The rate includes the cost of screening the Q.S. if any spreading, sectioning, with template and adding reserved quota of metal, while/oiling is in progress for making good hollows and camber.

Item No. 6 Providing and filling in foundation with ordinary cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 crushed stone aggregate 20mm nominal size) mix and providing necessary vertical pin headers including formwork, vibrating, ramming and curing complete.

1. In case of ordinary concrete, mix is not required to be designed by preliminary tests and proportions of cement fine aggregate and coarse aggregates are specified by volume as given in table below for different four grades designated as ordinary M-100, M-150, M-200 and M-250.
2. In the designation of a concrete mix letter M refers to the mix and the number to the specified 28 days works cube compressive strength of that mix on 100 mm cubes expressed in kg./cm.
3. The ordinary concrete mix shall generally be specified by volume for cement which normally comes in bags and is used by weight, volume shall be worked out taking 50 kg. of cement as 0.035 cubic metre in volume. While measuring aggregate by volume, shaking ramming or hammering shall not be done proportioning of sand be as per its dry volume. In case it is dam, allowance for bulking shall be made as per IS : 2386 (Part-III).
4. In gradients required for ordinary / concrete containing one 50 kg. bag of cement for different proportions of mix shall be as given in Table below.

TABLE

Grade of concrete	Mix by volume	Total quantity of dry aggregates by volume per 50 kg. cement to be taken as sum aggregate of the individual volumes of fine & coarse aggregates, maximum	Proportion of fine aggregate to coarse aggregate	Quantity of water per 50 kg. of cement max.
(1 cubic metre : 1000 Litres)				
1	2	3	4	5
Ordinary	Litres			Litres
M-100	1:3:6	300	General 1:2 for fine aggregate to Coarse aggregate by volume but subject to a upper limit of 1:1.1/2 & a lower limit of 1:3.	34
M-150	1:2:4	220		32
M-200	1:1.1/2:3	160		30
M-250	1:1:2	100		27

Note :- The proportion of the aggregates shall be adjusted from upper limit to lower limit progress grading of the final aggregate becomes finer and the maximum size of coarse aggregate becomes larger.

Example : For an average grading of fine aggregate (that is zone II of IS : 383 - 1963) the proportions 1:1 1/2, 1:2 and 1:3 for maximum size of aggregates 10mm, 20 mm and 40mm respectively (after carrying out sieve analysis).

Note:- A mix leaner than M-100 (1:3:6) may be used for non structural part, if provided in the contract. In such cases grading of aggregates shall be by volume. Other requirements for mixing, placing and curing shall the same.

5. Following shall be the maximum nominal size of coarse aggregate for the different items of work.

Sr. No.	Item of construction	Maximum nominal size of coarse aggregate
i	R.C.C. well curb, R.C.C. well steining and R.C.C. Piles	40 mm
ii.	R.C.C. well steining	63 mm
ii	Well cap or pile cap, solid type piers, abutments and wing walls and their pier caps	40 mm
iii	R.C.C. works in cross girders, deck slab, wearing coat, kerb, light post, blast walls, approach slab etc. and hollow type piers, abutments, wing walls and their pier caps	20mm
iv	R.C.C. bearings	20 mm
v	For any other item of construction not covered by items (i) to (v)	As specified on the drawing or as desired by the Engineer in charge in case it is not specified on drawing.

For heavily reinforced concrete members as in the case of ribs of main beams, nominal maximum size of aggregate shall usually be restricted to 5 mm. less than the minimum lateral clear distance between the main bars or 5 mm. less than the minimum cover to the reinforcement whichever is the smaller.

6. Fine aggregate shall be clean, hard, coarse sand. It shall be free from dust and such other substances. The sand shall be got approved by the Engineer-in-charge.
7. All materials shall be stored as to prevent their deterioration or intrusion of their quality and fitness for the work. Any material which has deteriorated or has been damaged or is otherwise considered defective by the Engineer-in-charge shall not be used in the work
8. Cement shall be store above the ground level in perfectly dry and watertight sheds and shall be stocked not more than eight bags high. Wherever bulk storage containers are used. their capacity should be sufficient to cater to the requirements at site and should be cleaned at least once every 3 to 4 months. Cement more than 3 to 4 months old shall invariably be tested to ascertain that R satisfies the ascertain requirements. The aggregates shall be stored in such a way as to prevent admixture of foreign materials. Different sizes of the fine or coarse aggregate shall be stored in separate stock piles sufficiently removed from each other to prevent intermixing the materials.
9. The water for mixing shall be portable water to the satisfaction of the Engineer-in-charge. The quantity of water shall be just sufficient to produce a dense concrete of required workability for the job.
10. For all work concrete shall be mixed in a mechanical mixer which along with other accessories shall be kept in first class working condition and so maintained throughout the construction. Mixing shall be continued till materials are uniformly distributed and uniform colour of the entire mass is obtained and each individual particle of the coarse aggregate shows complete coating of mortar containing its proportionate amount of cement. In no case shall the mixing be done for less than 2 minutes after all ingredients have been put into the mixer.
11. When hand mixing is permitted by the Engineer-in-charge for small jobs or for certain other reasons, it shall be done on a smooth watertight platform large enough to allow efficient. Turning over of the ingredients of concrete before and after adding water. Mixing platform shall be so arranged that no foreign material shall get mixed with concrete nor does the mixing water flow out. Cement in required number of bags shall be placed in a uniform layer on top of the measured quantity of fine and coarse aggregate. Which shall also be spread in a layer of uniform thickness on the mixing platform ? Dry coarse and fine aggregate and cement then shall be mixed thoroughly by turning over to get a mixture of uniform color. Enough water shall then be added gradually through a nose and the mass turned over till a

mix of required consistency is obtained. In hand mixing quantity of cement shall be increased by 10 percent above that specified.

12. Mixers which have been out of use for more than 30 minutes shall be thoroughly cleaned before putting in a new batch. Unless otherwise agreed to by the Engineer-in-charge the first batch of concrete from the mixer shall contain only two third of normal quantity of coarse aggregate. Mixing plants shall be thoroughly cleaned before changing from one type of cement to another.
13. The method of transporting and placing concrete shall be approved by the Engineer-in-charge. Concrete shall be so transported and placed that no contamination, segregation or loss of its constituent material takes place. All form work and reinforcement contained in it shall be cleaned and made free from standing water, dust, snow or ice immediately before placing of concrete. No concrete shall be placed in any part of the structure until the approval of the Engineer-in-charge has been obtained.
14. If concreting is not started within 24 hours of the approval being given, it shall have to be obtained again from the Engineer-in-charge. Concreting then shall proceed continuously over the area between construction joints. Fresh concrete shall not be placed against concrete which has been in position for more than 30 minutes unless a proper construction joint is formed. Concrete shall be compacted in its final position within 30 minutes of its discharge from the mixer unless carried in properly designed agitators, operating continuously, when this time shall be within 2 hours of the addition of cement to the mix and within 30 minutes of its discharge from the agitator. Except where otherwise agreed to by the Engineer-in-charge, concrete shall be disposed in horizontal layer to a compacted depth of not more than 0.45 metre when internal vibrators are used and not exceeding 0.30 metre in all other cases.
15. Unless otherwise agreed to by the Engineer-in-charge concrete shall not be dropped into place from a height exceeding 2 metres. When trucking or chutes are used they shall be kept clean and used in such way as to avoid segregation. When concreting has to be resumed on a surface which has hardened, it shall be roughened swept clean, thoroughly wetted, and cleaned with a 13 mm. thick -layer of mortar composed of cement and sand in the same ratio as in the concrete mix itself. This 13 mm. layer of mortar shall be freshly mixed and placed immediately before placing of new concrete. Where concrete has not fully hardened, all laitance shall be removed by scrubbing the wet surface with wire or bristle brush, care being taken to avoid dislodgement of particulars of coarse aggregate. The surface shall then be thoroughly wetted. All free water removed and then coated with neat cement grout. The first layer of concrete to be placed on this, surface shall not exceed 150 mm. in thickness and shall be well rammed against old work particular attention being given to corner and close spots.
16. All concrete shall be compacted to produce a dense homogenous mass with the assistance of Vibrators, unless otherwise permitted by the Engineer-in-charge for exceptional cases, such as concreting Under water, where vibrators cannot be used Sufficient vibrators in serviceable condition shall be kept at site so that spare equipment is always available in the event, of break downs.
17. Immediately after compaction concrete shall be protected against harmful effects of weather including rain, running water shocks, vibrations due to traffic, rapid temperature changes. Fast drying put process, it shall be covered with wet sacking Hessian or other similar absorbent material approved by the Engineer-in-charge soon after the initial set. It shall be kept continuously wet for a period of not less than 14 days from the date of placement. Masonry work over the foundation concrete may be started after 48 hours of it's laying but the curing of concrete shall be continued for a minimum period of 14 days.
18. Form work shall include all temporary or permanent forms required for forming the concrete, together with all temporary construction required for their support. Formwork shall however be delivered into following two district categories :-
 - (1) Shuttering i.e. formwork required for forming the concrete
 - (2) Scaffolding i.e. formwork required for supporting shuttering.

Forms for shuttering shall be constructed only, in metal suitably lined. Forms for scaffolding shall be constructed of metal or timber. Both shuttering and scaffolding shall be of substantial rigid construction and shuttering shall be true to shape and dimensions shown on the drawings. All bolts and reverts shall be counter-sunk and well ground to provide a smooth, plane surface.

- 19.** Forms shall be mortar tight and shall be made sufficiently rigid by the use of ties and bracings to prevent any displacement or sagging between supports. They shall be strong enough to withstand all pressure, ramming and vibration, without deflection from the prescribed lines occurring during and after placing the concrete. Screw jacks or hardwood wedges where required shall be provided to make up any settlement in the form work either before or during the placing of concrete. Suitable camber shall be provided in horizontal members of structure especially in long spans to counteract the effects of any deflection. The framework shall be so fixed as to provide for such camber. Forms shall be as constructed as too removable in sections in the desired sequence, without damaging the surface of concrete or disturbing other sections. Unless otherwise specified or directed. Chamfers or fillets of size 25 mm x 25 mm shall be provided at all angles of framework to avoid sharp corners.
- 20.** The inside surface of forms shall except in the case of permanent form work or where otherwise agreed to by the engineer-in-charge be coated with an approved material to prevent adhesion of concrete to the form work. Release agents shall be applied strictly in accordance with the manufacturer's instruction and shall not be allowed to come into contact with any reinforcement of prestressing tendons and anchorage shall be applied strictly in accordance with the manufacturer's instruction and shall not be allowed to come into contact with any reinforcement of prestressing tendons and anchorage. Different release agents shall not be used in form work of concrete which will be visible in the finished works.
- 21.** Special measures shall be taken to ensure that the framework does not hinder the shrinkage of concrete because without these cracking could occur before the form work is removed. Wherever applicable arrangement must be made to ensure that the form does not restrain the shortening and hogging of the beams or slabs during tensioning of the tendons. The formwork should take due account of the calculated amount of positive or negative camber so as to ensure the correct final shape of the structures having regard to the deformation of false work, scaffolding or propping and the instantaneous deformation due to various causes affecting prestressed structures. Where there are re-entrant angles in the concrete section, the formwork should be removed at these sections as soon as possible after the concrete has set in order to avoid cracking due to shrinking of concrete. Formwork shall be tight enough to prevent any appreciable loss of cement during vibrations. Suitable tolerances should be provided in the formwork, immediately before concreting all forms shall be thoroughly cleaned. Contractor shall give the Engineer-in-charge due notice before placing any concrete in the forms to permit him to inspect and accept the false work and forms as to their strength alignment and general fitness, but such inspection shall not relieve the contractor of his responsibility for safety of machinery materials and for results obtained.
- 22.** The Engineer-in-charge shall be informed in advance by the contractor of his intention to strike any form work. While fixing the time for removal of formworks. Due consideration shall be given to local condition, Character of the structure, the weather and other condition that influence the setting of concrete the removal of the load supporting of soffit forms may commence when concrete has attained strength and of the materials used in the mix. Where field operations are controlled by the strength test of concrete, the removal of the load supporting of soffit forms may commence when concrete has attained strength equal to at least twice the stress to which the concrete will be subject at the time of striking props including the effect of any further addition of loads. When field operations are not controlled by strength test of concrete the vertical forms of beams, columns and walls may be removed after 2 days. The props of slabs and beams may be removed after 14 and 21 days respectively. All form work shall be removed without causing any damage to the concrete. Centering shall be gradually and uniformly lowered in such a manner as to avoid any shock or vibrations. Supports shall be removed in such a manner as to permit the concrete to take stresses due to its own weight uniformly and gradually. Where internal metal ties are permitted they or their removable parts shall be extracted without causing any damage to the

concrete and remaining holes filled with mortars. No permanently embedded metal part shall have less than 25 mm. cover to the finished concrete surface. Where it is intended to reuse the framework R shall be cleaned and made good to the satisfaction of the Engineer-in-charge.

- 23** Immediately after the removal of forms, all exposed bars or bolts passing through the Cement concrete member and used for shuttering or any other purpose shall be cut inside the Cement Concrete member to a depth of at least 25 mm. below the surface of the concrete and the resulting holes filled by cement mortar. All fins cause by from joints, all cavities produced by the removal of from ties and all other holes and depressions, honeycomb spots, broken edges or corner and other defects shall be thoroughly cleaned, saturated with water and carefully pointed and rendered true with mortar of cement and fine aggregate mixed in the proportions used in the grade of concrete with mortar or cement and fine aggregate mixed in the proportions used in the grade of concrete that is being finished and of as dry a consistency as is possible to use. Considerable pressure shall be applied in filling and pointing to ensure thorough filling in all voids. Surface which has been pointed shall be kept moist for a period of 24 hours. If rock, pockets/honeycombs, in the opinion of the Engineer-in-charge are of such extent of and character as to affect materially or to endanger the life of the strength or the steel reinforcement he may declare the concrete defective and require the removal and replacement of the portions of the structure affected.
24. In the case of reinforced concrete work, workability shall be such that the concrete surrounds and properly grips all reinforcement. The degree of consistency, which shall depend upon the nature of work and. methods of vibration of concrete shall be determined regular slump test. Following slump shall be adopted for different types of works.

	Type of Work	Slump where vibrator is used	Slump where vibrator is not used
1	Mass conc. In RCC, foundation footing and retaining walls	10 to 25 mm	80 mm
2	Beam slab and column with simply reinforced	25 to 40 mm	100 to 120 mm
3	Thin RCC section or congested steel	40 to 50 mm	125 to 150 mm

25. Works strength tests shall be made in accordance with IS : 516. Each test shall be conducted on ten specimens five of which shall be tested at seven days and the remaining five at 28 days. The samples of concrete shall be taken on each day of concreting and, cubes shall be made at the rate of one for every 5 cubic meter of concrete or a part thereof. However if concreting done in a day is than 15 cubic meter, the minimum number of cubes can be reduced to 6 with the specific permission of the Engineer-in-charge. Similar works tests shall be carried out when ever the quality and grading of materials is changed irrespective of the quantity of concrete poured, The number of specimens may be suitable increased as deemed necessary by the Engineer-in-charge when procedure to tests given above reveals a poor quality of concrete and in other special cases.
26. The average strength of the group of cubes cast for each day shall not be less than the specified works cube strength. 20 percent of the cubes cast each day may have values less than the specified strength provided the lowest value is not less than 85 percent of the specified strength.
27. R.C.C. work shall have exposed concrete surface. Centering design and its erection shall be approved by the Engineer-in- charge. One carpenter with helper will invariably be kept throughout the period of concreting. Movement of labour and other persons shall be totally prohibited over reinforcement laid in position. For access to different parts, suitable mobile platforms shall be provided so that steel reinforcement in position as not disturbed. For ensuring proper cover, mortar blocks of suitable size shall be cast and tied to the reinforcement. Timber, kapachi or metal pieces shall not be used for this purpose. Concreting of important structural members shall always be done in the presence and under the supervision of departmental person not below the rank of Asstt. Engineer / Addl. Asstt. Engineer / Overseer or as instructed by the Engineer-in-charge. After removal of 'form work

and suturing, the executive Engineer shall inspect the work and satisfy by random checks that concrete produced is of good quality. Plastering shall not be allowed to the exposed faces of concrete.

28. In reinforced concrete the volume occupied by reinforcement shall not be deducted. The slab shall be measured as running continuously through and the beam as the portion below the slab.
29. All necessary labour, materials, equipment etc. for sampling, preparing test cubes, curing etc. shall be provided by the Contractor. Testing of the materials and concrete may be arranged by the Engineer-in-charge in an approved laboratory at the cost of the contractor.
30. The unit rate for concrete shall include the cost of all materials, labour, tools and plant required for mixing, placing in position, vibrating and compacting finishing as per directions of the Engineer-in-charge, curing and all other incidental expenses for producing concrete of specified strength to complete the structure or its components as shown on the drawings and according to these specifications. The rate shall also include the cost of making fixing and removing of all centers and forms required for the work.
31. **The payment will be made on cumt. basis of the finished work.**

Item No. 7 :- Providing and casting in situ ordinary cement concrete M-250 mix with Trimix C.C. Road laid as directed including vibrating, curing and filling in joints with bitumen complete.

This work shall consist of furnishing and laying **trimix C.C. Road ordinary cement concrete M-250** of the shape and dimensions shown on the drawings and conforming to these Specifications or as approved by the Engineer in charge.

Prior to the start construction the contractor shall design the mix in case of design mix concrete or propose nominal mix in case of nominal mix concrete and submit to the Engineer in charge for approval the proportions of materials including admixtures to be used water reducing admixtures (including plasticizers or super plasticizers) may be used at the contractors option subject to the approval of Engineer in charge. Other types of admixtures shall be prohibited unless specifically permitted by the Engineer in charge.

Weigh Batch Machine of appropriate capacity shall be used continuously during the entire process of execution of this item.

The ordinary concrete mix shall generally be specified by volume. For cement which normally comes in bags and is used by weight, volume shall be worked out taking 50 kg of cement as 0.035 cubic meter in volume. While measuring aggregate by volume, ramming or hammering shall not be done. Proportioning of sand shall be as per its dry volume In case it is dump allowance for "bulking" shall be made as per IS:2386(Part-III).

In the designation of a concrete mix, letter "M" refers to the mix and the number the specified 28 days works cube compressive strength of that mix on 250 mm. cubes expressed in kg./cm²

Ingredients required for ordinary concrete containing one 50 Kg. bag of cement of different proportions of mix shall be as given in Table below

Grade of Concrete	Mix By volume	Total quantity of dry aggregate by volume per 50 kg of cement	Proportion of fine aggregate to coarse aggregate	Quantity of water per 50 kg of cement (liter)
M-100	1:3:6	220	General 1:2 for fine aggregate to coarse aggregate by volume but subject to a upper limit of 1:1.5 and lower limit 1:3	34
M-150	1:2:4	290		32
M-200	1:1.1/2:3	360		30
M-250	1:1:2	380		27

MATERIALS

1.0 WATER

1.1 Water shall not be salty brackish and shall be clean reasonably clear and free objectionable quantities of silt and traces of oil injurious alkalis salts organic matter and other deleterious material which will either weaken the mortar of concrete or cause efflorescence or attack the steel in R C C container for transport storage and huddling of water shall be clean, Water shall conform to the standard specified in I S 455 -1978.

1.2 If required by the Engineer in charge it shall be tested by comparison with distilled water compression shall be made by means of standard cement tests for soundness time of setting and mortar strength as specified in I S 269-1976 Any indication of unsoundness change in time of setting by 30 minutes or more or decrease of more than 10 percent strength of mortar prepared with distilled water sample when compared with the result obtained with mortar prepared with distilled water shall be sufficient cause for rejection of water under test.

1.3 Water for curing mortar concrete or masonry should not be too acidic or too alkaline.

1.4 It shall be free of elements which significantly affect the hydration reaction or otherwise interface with the hardening of mortar or concrete during curing or those which produce objectionable stains or other unsightly deposits on concrete or mortar surfaces.

1.5 Hard and bitter water shall not be used for curing.

1.6 Potable water will generally found suitable for curing mortar or concrete.

2.0 CEMENT

2.1 Cement shall be ordinary Portland slag cement as per IS 1624 -1974 or Portland slag cement as per IS 455-1976.

2.2 Cement shall be stored above the ground level in perfectly dry and water tight sheds. Wherever bulk storage containers are used, their capacity should be sufficient to cater to the requirements at site and should be cleaned at least once every 3 to 4 months. The aggregate shall be stored in such a way as to prevent admixture of foreign materials. Different size of fine or coarse aggregate shall be stored in separate stock-piles sufficiently away from the each other to prevent intermixing the materials.

3.0 SAND

3.1 Sand shall be natural sand, clean well graded, hard strong durable and gritty particular free from immures amounts of dust, clay, kankar modules, soft: or flaky particles shall alkali salts, organic matter, learn mica or other deleterious substance and shall be got approved from the Engineer-in-charge. The sand shall not contain more than 8 percent of slit as determined by field test, if necessary the sand.

Coarse Sand: The fineness modules of coarse sand shall not be less than 2.5 and shall not exceed 3.0. The sieve analysis of coarse sand be as under:

I. S. Sieve Designation	% by wt. passing
4.75 mm	100
2.36mm	90 to 100
1.18 mm	70 to 100
600 MC	30 to 100
300 MC	85 to 70
150 MC	00 to 50

3.2 Fine Sand: The fineness module shall not exceed 1.0 the sieve analysis of fine sand be as under:

IS. Sieve Designation	% by wt. passing
4.75 mm	100
2.3 6mm	100
1.18 mm	75 to 100
600 MC	40 to 85
300 MC	05 to 50
150 MC	00 to 10

4.0 STONE COARSE AGGREGATE FOR NOMINAL MIX CONCRETE

4.1 Coarse aggregate shall be machine crushed stone of black trap and hard, strong, dense, durable, clean and free from disintegrated pieces, organic and other deleterious matter. .

4.2 The aggregate shall be generally be cubical in shape unless special stones of particular quarries are mentioned. Aggregate shall be machine crushed from the best black trap. Aggregate shall have no deleterious reaction with cement. The size of the coarse aggregate for plain cement concrete and ordinary reinforced cement shall generally as per the table given below

IS Sieve designation	% passing for single sized aggregate of nominal size		
80mm			
63 mm	100	-	-
40mm	85-100	100	0

20mm	0-20	85-100.	100
16mm	-	-	85-100

IS Sieve designation	% passing for single sized aggregate of nominal size		
12.5 mm			
10mm	0.5	0.20	0.30
4.75 mm	-	0.5	0.5
2.35 mm	-	-	-

Note: This percentage may be varied some what by the Engineer-in-charge when considered necessary containing better and strength of concrete.

4.3 The grading test shall be taken in the beginning and at the change of source of material as indicated in I.S. 383-1970 and I.S. 456-1978. Aggregate shall be stored separately and handled in such a manner so as to prevent the intermixing diff aggregate if the aggregate are covered with dust, they shall be washed with water to make them clean.

4.4 All materials shall be stored as to prevent their deterioration of their quality and fitness for the work. Any material which has deteriorated or has been damaged or is otherwise considered defective by the Engineer-in-charge shall not be used in the work. The aggregate shall be stored in such a way as to prevent admixture of foreign materials. Different size of fine or coarse aggregate shall be stored in separate stock-piles sufficiently away from the each other to prevent intermixing the materials.

5.0 WORKMANSHIP

General

5.1 Prior to the start construction the contractor shall design the mix in case of design mix concrete or propose nominal mix in case of nominal mix concrete and submit to the Engineer in charge for approval the proportions of materials including admixtures to be used water reducing admixtures Before stating concrete the bed of foundation trenches shall be cleared of all loose materials leveled watered and rammed as directed.

5.2 Complete including mixing plasticizer Conplast P - 211 @ 100 ML / bag including mixing shall be used including making c channel size required to level and slope and thickness of the concrete road leveling of placed concrete with surface vibrator and finishing with power floater shall be done. Floater and trowel light booming the surface shall be done **expansions joints** shall be cut as directed.

5.3 For sub base shall be leveled up prior to start the Trimix concrete.

The channel shall be placed on both side and shall be check by plumb & to spirit level in true level and longitudinal slope and gradient and camber.

6.0 MIXING:

FOR MASS CONCRETE WORK. :

6.1 Dry coarse and fine aggregate and cement shall then be mixed thoroughly by turning over to get a mixture of uniform colour.

6.2 Enough water shall then be added gradually and the mass turned over till a mix of required consistency is obtained. In case of hand mixing quantity of cement shall be increased by 10 per cent above that specified. The quantity of water shall be just sufficient to produce a dense concrete of required workability for the purpose

6.3 The concrete shall be mixed in a mechanical mixer. At the site of work Hand mixing may however be allowed for smaller quantity of work if approved by the Engineer-in-charge. When hand mixing is permitted by the Engineer-in-charge in case of break-down of machineries and in the interest of the work. Mixers which have been out of use for more than 30 minutes shall be thoroughly cleaned before putting in a new batch. Unless otherwise agreed to be the Engineer in-charge, the first batch of concrete from the mixer shall contain only two thirds of normal quantity of coarse aggregate. Mixing plant shall be thoroughly cleaned before changing from one type of cement to another.

6.4 The method of transporting and placing concrete shall be approved by the Engineer-in charge. Concrete shall be so transported and placed so that no contamination, segregations or loss of its constituent material takes place. All form work and reinforcement contained in it shall be cleaned and made free from standing water, dust, snow or ice immediately before placing of concrete. No concrete shall be placed in any part of the structure until the approval of the Engineer-in-charge has been obtained.

6.5 Mixing shall be done on a smooth watertight platform large enough to allow efficient turning over the ingredients of concrete before and after adding water, Mixing platform shall be so arranged so that no foreign material shall get mixed with concrete nor does the mixing water flow out.

6.6 Cement in required number of bags shall be placed in a uniform layer on top of the measured quantity of fine and coarse aggregate, which shall also be spread in a layer of uniform thickness on the mixing platform,

6.7 Unless otherwise agreed to by the Engineer-in-charge, concrete shall not be dropped into place from a height exceeding 2 meters. When chutes are used they shall be kept clean and used in such a way as to avoid segregation. When concreting has to be resumed on a surface which has hardened, it shall be roughened, kept clean, thoroughly wetted, and covered with a 13 mm. thick layer of mortar composed of cement and sand in the same ratio as in the concrete mix itself. This 13 mm. layer of mortar shall be freshly mixed and placed immediately before placing of new concrete. Where concrete has not fully hardened, all laitance shall be removed by scrubbing the wet surface with wire or bristle brushes, care being taken to avoid dislodgement of any particles of coarse aggregate. The Surface shall then be thoroughly wetted, all free water removed, and the coated with neat cement grout. The first layer of concrete to be placed on this surface shall not exceed 150 mm. in thickness, and shall be well rammed against old work particular attention being given to corners and Close spots.

6.8 If concreting is not started within 24 hours of the approval being given, it shall have to be obtained again from the Engineer-in-charge. Concreting being given, it shall proceed continuously over the Area between construction joints. Fresh concrete shall not be placed against concrete which has been in position for more than 30 minutes unless a proper construction joint is formed. Concrete shall be compacted in its final position within 30 minutes of its discharge from the mixer unless carried in properly design agitators, operating continuously, when this time shall be within 2 hours of the addition of cement to the mix and within 30 minutes of its discharge from the agitator. Except where otherwise agreed to be the Engineer-in-charge, concrete shall be deposited in horizontal layers to a compacted depth of not more than 0.4-metre when internal vibrators are used and not exceeding 0.30 meter in all other cases

6.9 In the case of reinforced concrete work workability shall be such that the concrete surrounds and properly grips all reinforcement. The degree of consistency which shall depend upon the nature of work and methods of vibration of concrete shall be determined by regular slump, tests. Following slump shall be adopted for different types of works.

type of work vibrators used.	Slumps	
	Where vibrators Are used	Where are not
Mass concrete in R.C.C. foundations footings and retaining walls.	10 - 25 mm	80 mm
(ii) Beams, slabs and columns simply reinforced	25 – 40 mm	100-120 mm

(iii) Thin R.C.C. section or section with mm. congested steel	40 – 50 mm	125 -150 mm
---	------------	-------------

8.0 Segregation

8.1 When concreting has to be resumed on a surface which has hardened, it shall be roughened, swept, clean, thoroughly wetted and covered with a 13 mm. thick layer of mortar shall be freshly mixed and placed immediately before placing of new concrete. Where concrete has not fully hardened, allegiance shall be removed by scrubbing the well surface with wire or bristle brushes, care : being taken to avoid dislodgement of any particles of coarse aggregate. The surface shall then be thoroughly wetted, with neat cement grout. The first layer of concrete to be placed on the Is surface shall not exceed 150mm.in thickness, and shall be well rammed against old work particular attention being given to corners and close spots.

9.0 Transporting & Placing the Concrete:

9.1 The concrete shall be handed from the place of mixing to the final position in not more than 15 minutes by the method as directed and shall be placed into its final position compacted and finished within 30 minutes of mixing with water i.e. before the setting commences.

9.2 The concrete shall be laid in layers of 15 cms to 20 cms.

9.3 All concrete shall be compacted to produce a dense homogeneous mass with the assistance of vibrators, unless otherwise permitted by the Engineer-in-charge for exceptional cases, such as concreting under water, where vibrators can not be used sufficient vibrators in serviceable condition shall be kept at site so that spare equipment is always available in the event of break downs.

9.4 After Placing

The mechanical vibrator shall be installed on channel and it shall be run in forwarded direction of concrete placing. The vibrator shall be start and shall be use as per instruction of Engineer-in-charge.

The water shall be suck by dewaterization equipment by spreading vaccum sheet on concrete after sufficient vibrator the floating water shall be sufficiently suck from concrete so that the sufficient strength of concrete shall be achieved.

The mechanical trowel shall be start after dewatering from concrete. The trowel shall be run in such a way that the required finish top surface of concrete shall be achieved mat finish or glossy finish.

10.0 Curing :

10.1 Immediately after compaction, concrete shall. be protected against harmful effects of weather, including rain, running water, shocks, vibration, traffic, rapid temperature charges, frost and driving out process shall be covered with wet jute bags or the similar absorbent material approved by the Engineer-in-charge soon after the initial set, and shall be kept continuously wet for a period of not less than 14 days from the date of placement. Masonry work over the foundation concrete may be started after 48 hours of its laying but the curing of concrete shall be continued for a minimum period of 14 days.

10.2 After the final set, the concrete shall be kept continuously wet if required by pounding for a period of not less then 7 days form the date of placement. Hard and bitter water shall not be used for curing

11.0 Mode of Measurement & Payment :

11.1 The payment will be made on Cum. basis of the finished work.

- 11.2** In reinforced concrete the volume occupied by reinforcement shall not be deducted. The slab shall be measured as running continuously through and the beam as the portion below the slab.
- 11.3** All necessary labour, materials equipment, etc for sampling, preparing test cubes, curing etc. shall be provided by the Contractor. Testing of the materials and concrete may be arranged by the Engineer in charge in an approved laboratory at the cost of the contractor
- 11.4** The unit rate concrete shall include the cost of all materials, tools and plant required for mixing, placing in position, compacting, and cost Water recuding concrete ad mixture at 100 ml per bag of cement and making channel 75 mm x 75 mm required to level and slope and thickness of the concrete road leveling of placed concrete with surface vibrator and finishing with power floater and trowel light booming the surface and cutting Expansions joints by machine as directed by The Engineer in charge and finishing as per direction of the Engineer-in-charge, curing and all other incidental expenses for producing concrete of specified strength to complete the structure or its components as shown on the drawings and according to these specifications. They shall also include the cost of making, fixing and removing of all centering and forms required for the work.
- 11.5** The concrete shall be measured for its length breadth limiting dimensions to those specified on plan or as directed.
- 11.6** The rate shall be for a unit of one **Cum**.

Item No. 8 :- Providing and fixing I.S.I. mark T.M.T. bar Fe-550D reinforcement for R.C.C. work including binding, bending and placing in position complete upto floor two level.

1.0. GENERAL

This work shall consist of furnishing and placing coated, or uncoated or high strength deformed reinforcement, bars (intentioned) of the shape and dimensions shown on the drawings and conforming to these Specifications or as approved by the Engineer in charge.

2.0. MATERIAL

2.1. TMT Bars

Reinforcements may be either T.M.T. tensile steel, confirms to IS 1786-2008 bars. They may be uncoated or coated with epoxy or with approved protective coatings.

2.2. T.M.T. bars reinforcement for R C C work shall conform IS 432 (Part II) 1982 (Reaffirmed 1995) and shall be of tested quality. It shall also comply with relevant part of IS 456-2000.

2.3. All reinforcement shall be clean and free from dirt, paint, grease or oil, all scale or loose or thick rust at the time of placing.

2.4. All steel shall be procured form original producers no re-rolled steel shall be incorporated in the work.

2.5. Only new steel shall be delivered to the site every bar shall be inspected before placing to its position and defective brittle or burnt bar shall be discarded cracked ends of bars shall be discarded.

3.0. Pitch

3.1. Distance between bars shall be as specified in drawings and as directed by the Engineer in Charge all bars shall be placed at an accurate distance from each other and shall be bind tightly to maintain the desired pitch Suitable means shall be provided for holding bars securely in position

4.0. Binding wire

4.1. Mild steel binding wire shall be of 1.63 mm or 1.22 mm (16 to 18 gauge diameter and shall conform IS 280-2006.

4.2. The use of black wire will be permitted for binding reinforcement bars. It shall be free form free from dirt, paint, grease or oil, oil scale or loose or thick rust and any other undesirable coating which may prevent adhesion of cement mortar at the time of binding

4.3. Only new binding wire shall be delivered to the site all binding wire shall be inspected before binding to its position and defective brittle, rusted, used wire, shall be discarded

5.0. PROTECTION OF REINFORCEMENT

5.1. Uncoated reinforcing steel shall be protected from rusting or chloride contamination. Reinforcements shall be free from rust, mortar, loose mill scale, grease, oil or paints. This may be ensured either by using reinforcement fresh from the factory or thoroughly cleaning all reinforcement to remove rust using any suitable method such as sand blasting, mechanical wire brushing, etc. as directed by the Engineer. Reinforcements shall be stored on bricks, racks or platforms and above the ground in a clean and dry condition and shall be suitably marked to facilitate inspection and identification.

5.2. Portions of uncoated reinforcing steel and dowels projecting from concrete shall be protected within one week after initial placing of concrete with a brush coat of neat cement mixed with water to a consistency, of thick paint. This coating shall be removed by lightly tapping with a hammer or other tool not more than one week before placing of the adjacent pour of concrete. Coated reinforcing steel shall be protected against damage to the coating. If the coating on the bars is damaged during transportation or handling and cannot be repaired, the same shall be rejected.

6.0. Workmanship

6.1. The work shall consist of furnishing and placing reinforcement to the shape and dimensions shown as on the drawings or as directed by The Engineer in charge.

6.2. Reinforcing steel shall conform accurate to the dimensions given in the bar bending schedules shown on relevant drawing

7.0. BENDING OF REINFORCEMENT

7.1. Bar bend g schedule shall be furnished by the Contractor and got approved by the Engineer before start of work.

7.2. Reinforcing steel shall conform to the dimensions and shapes given in the approved bar bending Schedules.

7.3. Bars shall be bent cold to the specified shape and dimensions or directed by the Engineer using a proper bar bender operated by hand power to obtain the correct radius of bends and shape.

Bars shall not be bent or straightened in a manner that will damage parent material or the coating bars bent during transport or handling shall, be straightened before being used on work and shall not be heated to facilitate straightening.

8.0. PLACING OF REINFORCEMENT

8.1. The reinforcement cage should generally be fabricated in the yard at ground level, and then shifted and placed in position. The reinforcement shall be placed strictly, in accordance with the drawings and shall be assembled in position, only when structure is otherwise ready for placing of concrete. Prolonged time gap, between assembling of reinforcements and casting of concrete, which may result in rust formation on the surface, shall not be permitted.

8.2. Reinforcement bars shall be placed accurately in position as shown on the drawings. The bars, crossing one another shall be tied together at every intersection with binding wire (annealed), conforming to IS:280 to make the skeleton of the reinforcement rigid such that the reinforcement does not get displaced during placing of concrete, or any other operation. The diameter of binding wire shall not be less than 1 mm.

8.3. Bars shall be kept in position usually by the following methods:

In case of beam an slab construction, industrially produced polymer cover blocks of thickness equal to the specified cover shall be placed between the bars and formwork subject to Satisfactory evidence that the polymer composition is not harmful to concrete and reinforcement. Cover blocks made of concrete may be permitted by the Engineer, provided they have the same strength and specification as those of the member.

8.4. In case of dowels for Columns and walls the vertical reinforcement shall be kept in position by means of timber templates with slots in them accurately, or with cover blocks tied to the reinforcement timber templates shall be removed after the concreting has progressed up to a level just below their location.

8.5. Layers of reinforcements shall be separated by spacer bars at approximately One meter intervals. The minimum diameter of spacer bars shall be 12 mm or: equal to maximum size of main reinforcement or maximum size of coarse aggregate, whichever is greater. Horizontal reinforcement shall not be, allowed to sag between supports.

8.6. Necessary stays, blocks, metal chairs, spacers, metal hangers supporting wires etc, or other subsidiary, reinforcement shall be provided to fix the reinforcements firmly in its correct position.

8.7. Use of pebbles, broken stone, metal pipe, brick, mortar or wooden blocks etc as devices for positioning reinforcement shall not be permitted.

8.8. Bars coated with epoxy or any other approved protective coating shall be placed on supports that do not damage the coating. Supports shall be installed in a manner such that planes of weakness are not created in hardened concrete. The coated reinforcing steel shall be held in place by use of plastic or plastic coated binding wires especially manufactured for the purpose.

8.9. Placing and fixing of reinforcement shall be inspected and approved by the Engineer before concrete is deposited.

9.0. Lapping

9.1. All reinforcement shall be furnished in full lengths as indicated on the drawing. No splicing of bars, except where shown on the drawing; will be permitted without approval of the Engineer. The lengths of the splice shall be as indicated on drawing or as approved by the Engineer. Where practicable, overlapping bars shall not touch each other, and shall be kept apart by 25 mm or 1 1/4 times the maximum size of coarse aggregate, whichever is greater, If this is not feasible, overlapping bars shall be bound with annealed steel binding wire, not less than 1 mm diameter and twisted tight in such a manner as to maintain minimum clear cover to the reinforcement from the concrete surface. Lapped splices shall be staggered or located at points, along the span where stresses are low.

10.0. Welding

10.1 Splicing by welding of reinforcement will be permitted only if detailed on the drawing or approved by the Engineer. Weld shall develop an ultimate strength equal to or greater than that of the bars connected.

10.2. While welding may be permitted for T.M.T. reinforcing bars conforming to IS:432, welding of deformed bars conforming to IS: 1786 shall in general be prohibited. Welding may be permitted in case of bars of other than S 240 grade including special. Welding grade of S 415 grade bars conforming to IS:1786, for which necessary chemical analysis has been secured and the carbon equivalent (CE) calculated from the chemical composition using the formula:

$$CE = C + \frac{Mn}{6} + \frac{Cr + Mg + V}{5} + \frac{Ni + Cu}{15}$$

is 0.4 or less.

10.3. The method of welding shall conform to IS:2751 and IS:9417 and to any supplemental specifications to the satisfaction of the Engineer

10.4. Bars shall be bent cold to the specified shape and dimensions or as directed by Engineer in charge using the proper bender tool, operated by hand or power to attain proper radius of bends. Bars shall not be bend or straightened in a manner that will injure the material. Bars bent during transport or handling shall be straightened before being used in the work. Bars shall not be heated to facilitate bending

10.5. Unless otherwise specified a 'U' type hook at the end of each bar shall invariably be provided to main reinforcement. The radius of the bane shall not be less then twice the diameter of the round bar and the length of the straight part of the bar beyond the end of the curve shall be at least four times of the diameter of the round bar. In case of bars which are not round and in case of deformed bars, the diameter shall be taken as the diameter of circle having an equivalent effective area. The hooks shall be suitably encased to prevent any spiting of the concrete

10.6. All reinforcement bars shall be accurately placed in exact position shown on the drawings and shall be securely held in position during placing of concrete by annealed binding wire not less than 1 mm in size and by using say blocks or metal chairs spacers, metal hangers, supporting wires or other approved devices at sufficiently close intervals, Bars shall not be allowed to sag between supports not displaced during concreting or any other operations of the work All devices used for positioning shall be of not corrodible material wooden and metal supports shall not extended to the surface of the concrete, except where shown in drawings. Placing bars on layers of freshly laid concrete as the work progresses for adjusting bar spacing shall not be allowed. Pieces of broken stone or brick and wooden blocs shall not be used Layers of bars shall be separated by spacer bars pre-cast mortar blocks or other approved devices. Reinforcement after bending placed in position shall be maintained in a clean condition until completely embedded in concrete, Special care shall be exercised to prevent any displacement of reinforcement in concrete already placed. To prevent reinforcement form corrosion, concrete cover shall be provided as indicated on drawings. All bars protruding from concrete and to which other bars are to be sliced and which are likely to be exposed for a period exceeding 10 days shall be protected by a thick coat of neat cement grout

10.7. Bars crossing each other where required shall be secured by binding wire (annealed) of size not less than 1 mm in such a manner that they do not slip over at the time of fixing and concreting

As far possible bars of full length shall be used in case this is not possible, overlapping of bars shall be done as directed by the Engineer in charge When practicable overlapping bars shall not touch each other, but be kept apart by 25 mm Where no feasible overlapping bars shall be bound with

annealed wires not less than 1 mm thick twisted tight The overlaps shall be staggered for different bars and located at points along the span where neither sheer not bending moments is maximum.

10.8. Whenever indicated on drawing or desired the Engineer in charge bars shall be jointed by coupling which shall have a cross section sufficient to transmit the full stresses of bars The end of the bars that are jointed by coupling shall be upset for sufficient length so that the effective cross section at the base of threads is not less than the normal cross section of the bar. Threads shall be standards threads Steel for coupling shall conform to IS 226.

10.9. When permitted or specified on the drawings joints of reinforcement bars shall butt-welded so as to transmit their full stresses Welded joints shall preferably be located at points when steel will not be subject to more than 75 percent of the maximum permissible stresses and welds so staggered that at any one section not more than 20 percent of the rods are welded Only electric are welding using a process which excludes air form the molten metal and conforms to any or other special provisions for the work shall be accepted Suitable means shall be provided for holding bars securely in position during welding It shall be ensured that no voids are left in welding and when welding is done in two or three stages previous surface shall be cleaned properly Ends of bars shall be cleaned of all loose scale rust stages paint and other foreign matter before welding Only competent welders shall be employed on the work. The M S electrodes used for welding shall conform IS 814 Welded pieces of reinforcement shall be tested. Specimen shall be taken form the actual site and their number shall frequency to test shall be as directed by the Engineer in charge

11.0 MODE OF MEASUREMENTS & PAYMENT

11.1. For the purpose of payment the bar shall be measured correct up to 10 mm length and weight payable works out at the rate specified below :

Sr. No	Diameter of steel	weight of steel per running meter	Sr. No	Diameter of steel	weight of steel per running meter
1	6 mm	0.22 Kg / Rmt	8	20 mm	2.47 Kg / Rmt
2	8 mm	0.39 Kg / Rmt	9	22 mm	2.98 Kg / Rmt
3	10 mm	0.62 Kg / Rmt	10	25 mm	3.85 Kg / Rmt
4	12 mm	0.89 Kg / Rmt	11	28 mm	4.83 Kg / Rmt
5	14 mm	1.21 Kg / Rmt	12	32 mm	6.31 Kg / Rmt
6	16 mm	1.58 Kg / Rmt	13	36 mm	7.99 Kg / Rmt
7	18 mm	2.00 Kg / Rmt	14	40mm	9.86 Kg / Rmt

11.1. Excess consumption over 5% will be charged at penal rate.

11.2. Reinforcement shall be measured in length including hooks, if any, separately for different diameters as actually used in work, excluding overlaps. From the length so measured, the weight of reinforcement shall be calculated in tonnes on the basis of IS: 1732. Wastage, overlaps, couplings, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire or other methods for binding and placing shall not be measured and cost of these items shall be deemed to be included in the rates for reinforcement.

11.3. The contract unit rate for coated/uncoated reinforcement shall cover the cost of material, fabricating, transporting, storing, bending, placing, binding and fixing in position as shown on the drawings as per these specifications and as directed by the Engineer, including all labour, equipment, supplies, incidentals, sampling, testing and supervision.

The unit Rate for coated reinforcement shall be deemed to also include cost of all material, labour, tools and plant, royalty, transportation and expertise required to carry out the work. The rate shall also cover sampling, testing and supervision required for the work.

11.4. The rate shall be for a unit of **One Kg.**

Item No. 9 :- Supplying, fixing and joining reinforced concrete heavy duty non-pressure pipes carrying Indian Railway standard with collars for culverts carrying heavy traffic as per Indian Railway standard specification including setting and joining the pipes in C.M. 1:2 watering and laying (to level or slopes) of I.S. class NP-4 of 300mm internal diameter.

1. This shall consist of furnishing and installing reinforced cement concrete pipe of the type diameter and length required at the location shown on the drawings or as ordered by the Engineer-in-charge.
2. Reinforced concrete pipe shall be of NP4 type conforming to the requirements of IS : 458 and shall be of dia. as specified in the item. Pipes shall be durable & its durability shall be achieved as a result of low water cement ratio & high compaction with the use of latest "Vertical Casting Technology" with precisely controlled socket & spigot joints & quality of pipes and its inner surface shall be smooth and strictly as per I.S. 458/1971. Each consignment of cement concrete pipes shall be inspected, if necessary and approved by the Engineer-in-charge either at the place of manufacture or at the site before their incorporation in the works.

NP4, NP3, NP2 and NP1 pipes are used for R.C.C. Pipes. Where the testing of pipes will not be feasible the contractors will have to produce a certificate from the manufacturer on company's letter head in the given hereinafter from.

Production of such certificate will not however relieve the Contractor from his responsibility of supplying pipes of required standard and will have to bear the loss or damage caused to the work on account of defects found subsequently during execution. It will also be necessary to purchase these pipes from manufacturer having standard equipments for carrying out various tests as per IS : 458 at his factory.

Form of Certificate for NP4, NP-3, NP-2, NP-1 Pipes

We _____

Manufacturer or R.C.C. Pipes produce R.C.C. pipes as per the requirement of IS : 458 and also carry out the required test at out place, We have acquired equipments for carrying out test and are prepared to carry out tests at our factory sites. We have experience of manufacturing of pipes of years. The pipes supplied by us to M/S. _____.

Satisfy the requirement of IS:458.

Date: _____

Place: _____

Manufacturer's Sign _____

3. No pipes shall be placed in position until the foundations have been approved by the Engineer-in charge. Where two or more pipes are to be laid adjacent to each other, they shall be separated by a distance equal to at least half the diameter of the pipe subject to minimum of **300 mm**. The laying of pipes on the prepared foundation shall start from the outlet and proceed towards the inlet and be completed to the specified lines and grades. The pipes shall be fitted and matched so that when laid in works they form a culvert with a smooth uniform invert. Any pipe found defective or damaged during laying shall be removed at the cost of Contractor.
4. The pipes shall be jointed either by collar joint or by flush joint in the former case the collars shall be of R.C.C. 150 to 200 mm. wide and having the same strength as the pipes to be jointed. Caulking space shall be between 13 and 20 mm. according to the diameter of the pipes caulking material shall be slightly wet mix of cement and sand in the ratio of 1:2 rammed with caulking irons. Before caulking the collar shall be so placed that its centre coincides with that of pipes and an even annular space is left between the collar and the pipes. Flush joint may be shaped to form a self centering joint with a joining space 13 cm wide. The joining space shall be filled with cement mortar 1:2 (1 cement : 2 sand) mixed sufficiently dry to remain in position when forced with a trowel or rammer. Care shall be taken to fill all voids and excess mortar shall be removed. All joints shall be made with care so that their interior surface is smooth and consistent with the interior surface of the pipes. After finishing, the joint shall be kept covered and damp for at least four days.
5. R. C. C. pipes shall be measured along their centre between their inlet and outlet ends in linear metres.
6. The rate for the pipes shall include the cost of pipe including loading, unloading, handling, storing laying in position and joining complete.
7. The rate shall be for a unit of one **running meter**.

Item No. 10 : Hazard Marker Sign :- Providing and fixing sign board made out of 2mm aluminium sheet size 90 x 30 cms. rectangle as per the design / drawing attached (IRC) pretreated with phosphating & acid etching, coated with one coat of epoxy primer and two coats of best quality epoxy paint reflectorised with retro reflective sheeting as per latest M.O.R.T.H. specification, 3.1m long (2 nos.) stand post and frame fabricated from suitable size iron angle of 35 x 35 x 3mm & 50 x 50 x 5mm painted with best quality epoxy coatings in black and white bends. The details of symbol or inscription / numerals for each board shall be as per instruction of Engineer in charge. The fixing at site shall be in 1:2:4 C.C. block of size 45 x 45 x 60cms for each leg including excavation curing etc. complete under the supervision of Engineer in charge (A) Engineer Grade (VR).

The sign board shall conform to IRC-67-1977 and ninth schedule of the motor vehicle Act. It shall be providing and fixed as directed by the Engineer in charge.

1.2 Traffic Signs having retro-reflective sheeting :

1.2.1 General Requirements :

The retro-reflective sheetings used on the sign shall consist of white or coloured sheeting having a smooth outer surface which has the property of retro reflective over its entire surface. It shall be weather resistance and show colour fastness. It shall be new and unused and shall shown no evidence of cracking scaling pitting, blistering, edge lifting or curling and shall have negligible shrinkage or expansion. A certificate of having tested the sheeting for these properties in an unprotected outdoor exposure facing the sun for two years and its having passed these tests shall be obtained from a reputed laboratory by the manufacture of the sheeting. The reflective sheeting shall be either or Engineering Grade material with enclosed lens or of high intensity grade with encapsulated lens/ micro prismatic type. The type of sheeting to be used would depend upon the type functional hierarchy and importance of the road.

1.2.2 High Intensity Grade Sheeting :

1.2.2.1 Encapsulated Lens Type :

This sheeting shall be of encapsulated lens type consisting of spherical glass lens elements, adhered to a synthetic resin and encapsulated by a flexible, transparent water proof plastic having a smooth surface. The retro reflective surface after cleaning with soap and water and in dry condition shall have the minimum co-efficient of retro-reflection (determined in accordance with ASTM Standard E:810) as indicated in Table 800-1.

TABLE 800-1

ACCEPTABLE MINIMUM CO-EFFICIENT OF RETRO REFLECTIVE FOR HIGH INTENSITY GRADE SHEETING (CANDELAS PER LUX SQUARE METRE).

Observation angle (in degrees)	Entrance Angle (in degrees)	White	Yellow	Orange	Green/ Red	Blue
0.2	-4	250	170	100	45	20
0.2	+ 30	150	100	60	25	11
0.5	-4	95	62	30	15	7.5
0.5	+30	65	45	25	10	5.0

When totally wet, the sheeting shall not show less than 90% of the values of retro reflectance indicated in Table 800-1. At the end of 10 years, the sheeting shall retain at least 75% of its original retro-reflectance.

1.3.2 Engineering Grade Sheeting :

This sheeting shall be of enclosed lens type consisting of microscopic lens elements embedded beneath the surface of a smooth, flexible, transparent, water-proof plastic, resulting in a non-exposed lens optical, resulting in a non-exposed lens optical reflecting systems. The retro-reflective surface after cleaning with soap and water and in dry condition shall have the minimum coefficient of retro-reflection (determined in accordance with ASTM Standard E-810) as indicated in Table 800-2.

TABLE 800-2

ACCEPTABLE MINIMUM CO-EFFICIENT OF RETRO REFLECTIVE FOR ENGINEERING GRADE SHEETING (CANDELAS PER LUX SQUARE METRE).

Observation angle (in degrees)	Entrance Angle (in degrees)	White	Yellow	Orange	Green	Red	Blue
0.2	-4	70	50	25	9.0	14.5	4.0
0.2	+ 30	30	22	7.0	3.5	6.0	1.7
0.5	-4	30	25	13.5	14.5	7.5	2.0
0.5	+30	15	13	4.0	2.2	3.0	0.8

1.1.2.3 When totally wet, the sheeting shall not show less than 90% of the values of retro-reflectance indicated in Table 800-2. At the end of 5 years, the sheeting shall retain at least 50% of its original retro reflective.

1.1.3 **Messages / Borders :** The messages (legends, letters, numerals etc.) and borders shall either be screen-printed or of cut-outs. Screen-printing shall be processed and finished with materials and in a manner specified by the sheeting manufacturer. Cut outs shall

be of materials as specified by the sheeting manufacturer and shall be bonded with the sheeting in the manner specified by the manufacturer.

1.1.4 For screen-printed transparent coloured areas on white sheeting, the co-efficient of retro-reflection shall not be less than 50% of the values of corresponding colour in Tables 800-1(a), 800-1(b) and 800-2 as applicable.

1.1.5 Cut out messages and borders, wherever used, shall be made out of retro-reflective sheeting (as per Clause 801.3.2 of 801.3.3 as applicable) except those in black which shall be of non-reflective sheeting.

1.1.6 **Colour** : Unless otherwise specified, the general colour scheme shall be as stipulated in IS:5 "Colour for Ready Mixed Paints".

Blue	IS	Colour No.166 : French Blue
Red	IS	Colour No.537 : Signal Red
Green	IS	Colour No.284 : India Green
Orange	IS	Colour No.591 : Deep Orange

The colours shall be durable and uniform in acceptable but when viewed in day light or under normal headlights at night.

1.1.7 **Adhesives** : The sheeting shall either have a pressure sensitive adhesive of the aggressive-tack type requiring no heat, solvent or other preparation for adhesion to a smooth clean surface, or a tack adhesive activated by heat, applied in a heat-vacuum applicator, in a manner recommended by the sheeting manufacturer. The sheeting shall be protected by an easily removable liner (removable by peeling without soaking in water or other solvent) and shall be suitable for the type of material of the base plate used for the sign. The adhesive shall form a durable bond to smooth, corrosion and weather resistant surface of the base plate such that it shall not be possible to remove the sheeting from the sign base in one piece by use of sharp instrument. In case of pressure-sensitive adhesive sheeting, the sheeting shall be applied in accordance with the manufacturer's specifications. Sheeting with adhesives requiring use of solvents or other preparation for adhesive shall be applied strictly in accordance with the manufacturer's instructions.

1.1.8 **Refurbishment**: Where existing signs are specified for refurbishment, the sheeting shall have a semi-rigid aluminium backing pre-coated with aggressive-tack type pressure sensitive adhesive. The adhesive shall be suitable for type of material used for the sign and should thoroughly bond with that material.

Alternatively, the aluminium blank shall be recycled to a finished condition and new sheeting's put on in an approved manner.

1.1.9 **Fabrication** :

1.1.9.1 Surface to be reflectorised shall be prepared to receive the retro-reflective sheeting. The smooth plain surface before the application of retro-reflective sheeting. If the surface is rough, approved surface primer may be used. After cleaning, metal shall not be handled, except by suitable device or clean canvas gloves between all cleaning and preparation operation and application of reflective sheeting/primer. There shall be no opportunity for metal to come in contact with grease, oil or other contaminants prior to the application of retro-reflective sheeting.

1.1.9.2 Complete sheets of the material shall be used on the signs except where it is unavoidable. At splices, sheeting with pressure sensitive adhesive shall be overlapped not less than 5 mm. Sheeting with heat-activated adhesives may be spliced with an overlap not less than 5 mm or butted with a gap not exceeding 0.75 mm. Where screen printing with transparent colours is proposed, only but jointing shall be used. The material shall cover the sign surface evenly and shall be free from twists, cracks and folds. Cut outs to produce legends and borders shall be bonded with the sheeting in the manner specified by the manufacturer.

1.1.10 **Warranty Durability** : For each lot of sheetings procured, the contractor shall obtain from the manufacturer a 10 years warranty for satisfactory field performance including stipulated retro-reflectance of the sheetings of high intensity grade and a 5 years warranty for the engineering grade and submit the same to the Engineer. In addition, a 10 years and a five years warranty for satisfactory in-field performance of the finished sign with retro-reflective sheeting of high intensity grade and engineering grade respectively, inclusive of the screen printed or cut-out letters/legends and their bonding to the retro-reflective sheeting shall be obtained from the contractor/supplier and passed on to the Engineer. The contractor / supplier shall also furnish a certification that the signs and materials supplied against the assigned work meet all the stipulated requirements and carry the stipulated warranty.

Processed and applied in accordance with recommended procedures, the reflective material shall be weather resistant and following cleaning shall show no appreciable discolouration, cracking, blistering or dimensional change and shall not have less than 50 percent of the specified minimum reflective intensity values Tables 800-1 and 800-2) when subjected to accelerated weathering for 1000 hours, using type E or EH weatherometer AASHTO Designation M 268).

1.2 **Installation :**

1.2.1 Sign posts, their foundations and sign mountings shall be so constructed as to hold these in a proper and permanent position against the normal storm wind loads or displacement by vandalism. Normally signs with an area upto 0.9 sq.m. shall be mounted on a single post,

and for greater area two or more supports shall be provided. Sign supports may be of mild steel, reinforced concrete or galvanised iron (G.I.). Post-end(s) shall be firmly fixed to the ground by means of properly designed foundation. The work of foundation shall conform to relevant specifications as specified.

1.2.2 All components of signs and supports, other than the reflective portion and G.I. Posts shall be thoroughly descaled, cleaned, primed and painted with two coats of epoxy paint. Any part of mild steel (M.S.) post below ground shall be painted with three coats of red lead paint.

1.2.3 The signs shall be fixed to the posts by welding in the case of steel posts and by bolts and washers of suitable size in the case of reinforced concrete or G.I. Posts. After the nuts have been tightened, the tails of the bolts shall be furred over with a hammer to prevent removal.

1.3 **Measurements for Payment :**

The measurement for standard cautionary, mandatory and information sign shall be in number of different types of signs supplied and fixed as per above details and specifications. Direction and place identification signs, also shall be measured in numbers of different type of sign supplied and fixed.

1.4 **Rate :**

The contract unit rate shall be payment in full for the cost of making the road sign, including all materials, installing it at the site and incidentals to complete the work in accordance with the specifications.

➤ **SPECIAL TERMS AND CONDITIONS OF CONTRACT FOR SIGN BOARDS**

- 1 Warranty certificate for 5 years for respective grades of signs from the sheeting manufacturer should be attached with the bid.
- 2 A certificate of authorization from the sheeting manufacturer shall be submitted with the bid.
- 3 The responsibility for handling, upkeep and safety of the boards lies with the contractor until the completion of work and final payment are released.
- 4 The contract is valid for three months from the date of work order. The required quantity has to be supplied and fixed as and when intimated by the Division.
- 5 The measurement for payment will be done only after fulfilling condition up to the satisfaction of Executive Engineer. The 100% quantity of supply and fixing will be checked by Deputy Executive Engineer and at least 10% quantity of supply and fixing will be checked by the Executive Engineer to ensure quality and workmanship, before passing for payments.
- 6 The contractor will have to ensure how he is going to arrange repair or replacement of defective boards after intimation from the Division.

Item No. 11 :- Direction sign (Junction board) :- Providing and fixing sign boards made out of 2mm aluminium sheet size 244 x 122cms. rectangle as per the design of IRC-67-1977 pre treated with phosphating process & acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint reflectorised with retro reflective sheeting as per latest M.O.S.T. specifications, Letters and numerals should be as per IRC-30-1968, 3.1m long (2 Nos.) stand post and frame fabricated from suitable size iron angle of 50 x 50 x 5mm, 75 x 75 x 6mm as required, painted with best quality epoxy coatings in black and white bends. The details of symbol or inscription / numerals for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60cms. for each leg including excavation curing etc. complete under the supervision of engineer in charge. (A) Engineer grade. (VR)

The work shall be executed as per specification of **Item No. 10** except the work is for **Direction sign (Junction board) :- Providing and fixing sign boards made out of 2mm aluminium sheet size 244 x 122cms. rectangle as per the design of IRC-67-1977 pre treated with phosphating process & acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint reflectorised with retro reflective sheeting as per latest M.O.S.T. specifications, Letters and numerals should be as per IRC-30-1968, 3.1m long (2 Nos.) stand post and frame fabricated from suitable size iron angle of 50 x 50 x 5mm, 75 x 75 x 6mm as required, painted with best quality epoxy coatings in black and white bends. The details of symbol or inscription / numerals for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60cms. for each leg including excavation curing etc. complete under the supervision of engineer in charge. (A) Engineer grade. (VR)**

Measurement shall be taken and paid on No. basis.

Item No. 12 :- Citizen's Information Board : Providing and fixing of typical information board as per instruction. Two M.S. plate of 1.6mm thick of 900mm x 750mm size fixed at top and bottom duly welded with M.S. angle with angles of 25 x 25 x 5mm thick M.S. plate shall be welded by two vertical M.S. flat and four horizontal M.S. flats 5mm thick to 75mm x 75mm of 12 SWG square tube posts duly embedded in cement concrete M-15 grade C.C. blocks of 600 mm x 600mm x 750mm below ground level. Painting new letters and figures of any shade with ready mixed synthetic enamel paint of superior quality in required shade and coloured, all sections of frame joints and steel tube will be painted with primer and two coats of epoxy paint as per drawing clause 1701 & Annexure 1700.1 (10.16).

The work shall be executed as per specification of **Item No. 10** except the work is for **Citizen's Information Board : Providing and fixing of typical information board as per instruction. Two M.S. plate of 1.6mm thick of 900mm x 750mm size fixed at top and bottom duly welded with M.S. angle with angles of 25 x 25 x 5mm thick M.S. plate shall be welded by two vertical M.S. flat and four horizontal M.S. flats 5mm thick to 75mm x 75mm of 12 SWG square tube posts duly embedded in cement concrete M-15 grade C.C. blocks of 600 mm x 600mm x 750mm below ground level. Painting new letters and figures of any shade with ready mixed synthetic enamel paint of superior quality in required shade and coloured, all sections of frame joints and steel tube will be painted with primer and two coats of epoxy paint as per drawing clause 1701 & Annexure 1700.1 (10.16).**

Measurement shall be taken and paid on No. basis.

Item No. 13 : Road marking with hot applied thermoplast compound with reflectorising glass beads on bituminous surface and laying of hot applied thermoplastic compound 2.5mm thick including reflectorising glass beads @250 gms/sqmt area, thickness of surface applied glass beads as per IRC 35. The finish surface to be level uniform free from streaks and holes.

803.4 Hot Applied Thermoplastic Road Marking

803.4.1 Thermoplastic Material

803.4.1.1 General

The thermoplastic material shall be homogeneously composed of aggregate, pigment, resins and glass reflectorizing beads. The colour of the compound shall be white or yellow (IS colour No. 356) as specified in the drawings or as directed by the Engineer.

803.4.1.2 Requirements :

- I. Composition: The pigment, beads, and aggregate shall be uniformly dispersed in the resin. The material shall be free from all skins, dirt and foreign objects and shall comply with requirements indicated in Table 800-9.

Table 800-9 : Proportions of Constituents of Marking Material (Percentage by Weight)

Component	White	Yellow
Binder	18.0 min.	18.0 min.
Glass Beads	30 - 40	30 - 40
Titanium dioxide	10.0 min.	-
Calcium Carbonate and Inert Fillers	42.0max.	See Note Below
Yellow pigments	-	See Note Below

Note: Amount of yellow pigment, calcium carbonate and inert fillers shall be at the option of the manufacturer, provided all other requirements of this Specification are met.

- II. Properties: The properties of thermoplastic material, when tested in accordance with ASTM 036/BS-3262-(Part I), shall be as below:
 - a. Luminance:
 - White: Daylight luminance at 45°-65 percent min. as per AASHTO M249
 - Yellow: Daylight luminance at 45°-45 percent min. as per AASHTO M249
 - b. Drying time: When applied at a temperature specified by the manufacturer and to the required thickness, the material shall set to bear traffic in not more than 15 minutes.
 - c. Skid resistance: not less than 45 as per BS:6044.
 - d. Cracking resistance at low temperature: The material shall show no cracks on application to concrete blocks.
 - e. Softening point: 102.5°C ± 9.5°C as per ASTM D 36.
 - f. Yellowness index (for white thermoplastic paint): not more than 0.12 as per AASHTO M 249
- III. Storage life : The material shall meet the requirements of these Specifications for a period of one year. The thermoplastic material must also melt uniformly with no evidence of skins or

unmelted particles for the one year storage period. Any material not meeting the above requirements shall be replaced by the manufacturer/supplier/ Contractor.

- IV. Reflectorisation : Shall be achieved by incorporation of beads, the grading and other properties of the beads shall be as specified i~ Clause 803.4.2.
- V. Marking: Each container of the thermoplastic material shall be clearly and indelibly marked with the following information:
 - 1) The name, trade mark or other means of identification of manufacturer
 - 2) Batch number
 - 3) Date of manufacture
 - 4) Colour (white or yellow)
 - 5) Maximum application temperature and maximum safe heating temperature.
- VI. Sampling and Testing : The thermoplastic material shall be sampled and tested in accordance with the appropriate ASTM/BS method. The Contractor shall furnish to the Engineer a copy of certified test reports from the manufacturers of the thermoplastic material showing results of all tests specified herein and shall certify that the material meets all requirements of this Specification.

803.4.2 Reflectoring Glass Beads

803.4.2.1 General

This Specification covers two types of glass beads to be used for the production of reflectorised pavement markings.

Type 1 beads are those which are a constituent of the basic thermoplastic compound vide Table 800-9 and Type 2 beads are those which are to be sprayed on the surface vide Clause 803.6.4.

803.4.2.2 The glass beads shall be transparent, colourless and free from milkiness, dark particles and excessive air inclusions.

These shall conform to the requirements spelt out in Clause 803.4.2.3.

803.4.2.3 Specific Requirements

- a) Gradation: The glass beads shall meet the gradation requirements for the two types as given in Table 800-10.

TABLE 800-10: GRADATION REQUIREMENTFOR GLASS BEADS

Sieve size	Percent Retained	
	Type 1	Type 2
1.18 mm	0 to 3	-
850 micron	5 to 20	0 to 5
600 micron	-	5 to 20
425 micron	65 to 95	-
300 micron	-	30 to 75
180 micron	0 to 10	10 to 30
Below 180 Micron		00 to 15

- b) **Roundness** : The glass beads shall have a minimum of 70 percent true spires.
- c) **Refractive index** : The glass beads shall have a minimum refractive index of 1.50.

- d) **Free flowing properties** : The glass beads shall be free of hard lumps and clusters and shall dispense readily under any conditions suitable for paints striping. They shall pass the free flow test.

803.4.2.4 Test Methods

The specific requirements shall be tested with the following methods:

- i. Free-flow test: Spread 100 grams of beads evenly in a 100 mm diameter glass dish. Place the dish in a 250 mm inside diameter dessicator which is filled within 25 mm of the top of a dessicator plate with sulphuric acid water solution (specific gravity 1.10). Cover the dessicator and let it stand for 4 hours at 20°C to 29°C. Remove sample from dessicator, transfer beads to a pan and inspect for lumps or clusters. Then pour beads into a clean, dry glass funnel having a 100 mm stem and 6 mm orifice. If necessary, initiate flow by lightly tapping the funnel. The glass spheres shall be free of lumps and clusters and shall flow freely through the funnel.
- ii. The requirements of gradation, roundness and refractive index of glass beads and the amount of glass beads in the compound shall be tested as per BS:6088 and BS:3262 (Part I).
- iii. The Contractor shall furnish to the Engineer a copy of certified test reports from the manufacturer of glass beads obtained from a reputed laboratory showing results of all tests specified herein and shall certify that the material meets all requirements of these Specifications However, if so required, these tests may be carried out as directed by the Engineer.

803.4.3 Application Properties of Thermoplastic Material

803.4.3.1 The thermoplastic material shall readily get screeded/extruded at temperatures specified by the manufacturers for respective method of application to produce a line of specified thickness which shall be continuous and uniform in shape having clear and sharp edges.

803.4.3.2 The material upon heating to application temperatures shall not exude fumes which are toxic, obnoxious or injurious to persons or property.

803.4.4 Preparation

- i. The material shall be melted in accordance with the manufacturer's instructions in a heater with a mechanical stirrer to give a smooth consistency to the thermoplastic material to avoid local overheating. The temperature of the mass shall be within the range specified by the manufacturer, and shall on no account be allowed to exceed the maximum temperature stated by the manufacturer. The molten material should be used as expeditiously as possible and for thermoplastic material which has natural binders or is otherwise sensitive to prolonged heating, the material shall not be maintained in a molten condition for more than 4 hours.
- ii. After transfer to the laying equipment, the material shall be maintained within the temperature range specified by the manufacturer for achieving the desired consistency for laying.

803.5 Reflectorised Paint

Reflectorised paint, if used, shall conform to the Specification by the manufacturers and approved by the Engineer. Reflectorising glass beads for reflectorising paints where used shall conform to the requirements of Clause 803.4.2.

803.6 Application

803.6.1 Marking shall be done by machine. For locations where painting cannot be done by machine, approved manual methods shall be used with prior approval of the Engineer. The

Contractor shall maintain control over traffic while painting operations are in progress so as to cause minimum inconvenience to traffic compatible with protecting the workmen.

803.6.2 Where the compound is to be applied to cement concrete pavement, a sealing primer as recommended by the manufacturer, shall be applied to the pavement in advance of placing of the stripes to ensure proper bonding of the compound. On new concrete surface any laitance and/or curing compound shall be removed before the markings are applied.

803.6.3 The thermoplastic material shall be applied hot either by screeding or extrusion process. After transfer to the laying apparatus, the material shall be laid at a temperature within the range specified by the manufacturer for the particular method of laying being used. The paint shall be applied using a screed or extrusion machine.

803.6.4 The pavement temperature shall not be less than 10°C during application. All surfaces to be marked shall be thoroughly cleaned of all dust, dirt, grease, oil and all other foreign matter before application of the paint.

The material, when formed into traffic stripes, must be readily renewable by placing an overlay of new material directly over an old line. Such new material shall so bond itself to the old line that no splitting or separation takes place.

Thermoplastic paint shall be applied in intermittent or continuous lines of uniform thickness of at least 2.5 mm unless specified otherwise. Where arrows or letters are to be provided, thermoplastic compound may be hand-sprayed. In addition to the beads included in the material, a further quantity of glass beads of Type 2, conforming to the above noted Specification shall be sprayed uniformly into a mono-layer on to the hot paint line in quick succession of the paint spraying operation. The glass beads shall be applied at the rate of 250 grams per square metre area.

803.6.5 The minimum thickness specified is exclusive of surface applied glass beads. The method of thickness measurement shall be in accordance with Appendices B and C of BS:3262 (Part 3).

803.6.6 The markings shall be done to accuracy within the tolerances given below:

- i. Width of lines and other markings shall not deviate from the specified width by more than 5 percent.
- ii. The position of lines, letters, figures, arrows and other markings shall not deviate from the position specified by more than 20 mm
- iii. The alignment of any edge of a longitudinal line shall not deviate from the specified alignment by more than 10 mm in 15 m.
- iv. The length of segment of broken longitudinal lines shall not deviate from the specified length by more than 150 mm.

In broken lines, the length of segment and the gap between segments shall be as indicated on the drawings; if these lengths are altered by the Engineer, the ratio of the lengths of the Painted sections shall remain the same.

803.6.7 Properties of Finished Road Markings

The finished lines shall be free from ruggedness on sides and ends and be parallel to the general alignment of the carriageway. The upper surface of the lines shall be level, uniform and free from streaks.

- a. The stripe shall not be slippery when wet.

- b. The marking shall not lift from the pavement in freezing weather.
- c. After application and proper drying, the stripe shall show no appreciable deformation or discoloration under traffic and under road temperatures upto 60°C.
- d. The marking shall not deteriorate by contact with sodium chloride calcium chloride or oil dripping from traffic.
- e. The stripe or marking shall maintain its original dimensions and position. Cold ductility of the material shall be such as to permit normal movement with the road surface without chopping or cracking.
- f. The colour of yellow marking shall conform to IS Colour No. 356 as given in IS:164

803.6.8 Measurements for Payment

803.6.8.1 The painted markings shall be measured in sq. metres of actual area marked (excluding the gaps, if any).

803.6.8.2 In respect of markings like directional arrows and lettering, etc., the measurement shall be by numbers.

803.6.9 Rate

The Contract unit rate for road markings shall be payment in full compensation for furnishing all labour, materials, tools, equipment, including all incidental costs necessary for carrying out the work at the site conforming to these Specifications complete as per the approved drawing(s) or as directed by the Engineer and all other incidental costs necessary to complete the work.

1.7 SPECIAL TERMS AND CONDITIONS FOR THERMOPLAST PAINT WORK:

- (1) Agency should carry out the such type of work by only of thermoplastic paint laying machine (power driven only) with temperature controller and automatic mixing arrangement of glass beads in required proportion.
- (2) After completion of the laying of thermoplastic paint work, four years guarantee for durability and reflectivity as per M.O.R.T.H. specification for road and bridge works clause 803 should be given by the bidder in the writing.
- (3) Guarantee security deposit shall be retained @ 10% of the cost of the item of thermoplast paint from the R.A. bills, which will be released after expiry of guarantee period.
- (4) Agency who carry out the such type of work shall have an experience of carrying out similar type of work.
- (5) Test certificates as per M.O.R.T.H. specification for road and bridge works clause 803.3.2.2 (vi) should be furnished of reputed laboratory before.

Item No. 14 :- Supply & fixing logo board of MMGSY diamond size (600mm x 600mm) 16 gauge & board plate size (900mm x 250mm) 16 gauge thick M.S plate and 2.40 mt. deep length single angle 75 x 75 x 6 mm size including fitting and painting lettering with luminous color as per drawing etc. complete.

The board will be a composite unit consisting of three M.S. plates of 1.6mm thickness (16 SWG). The top most plate will be in diamond shape of 600mm x 600mm size, welded over welded M.S. flat iron frame of 75mm x 6mm size on back on edges. The middle plate will be 900mm x 250mm size welded over welded M.S. flat iron frame of 25mm x 5mm size on back on edges. The main lower most M.S. plate will be 900mm x 250mm size, welded over welded M.S. angle iron frame of 75mm x 75mm x 6mm size. Welding of all the sheets over angle and flat iron frame will be done neatly to have plain surface on one side. The angle iron frame of the lower most plate and flat iron frame of the middle plate will be welded to two nos. 75mm x 75mm (12 SWG) sheet tubes posts placed at 1125mm apart centre to centre. The top of the middle plate will be flushed with the top of 75mm dia. medium steel tube posts and these posts will be embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm below ground level. The height of bottom to the lower most plate will be 900mm from normal ground level and the bottom of middle plate will be 100mm above the top level of the lower most plate. The diamond shaped plate mounted over flat iron frame will be connected to middle plate by square steel section of 47mm x 47mm thickness 12 SWG having a spacing of 100mm between the diamond shaped plate and middle plate and this square section will be welded to the bottom point of the diamond shaped plate.

All M.S. plates will be stove enameled on both sides in furnace at required temperature. The lettering and borders etc. of middle and bottom place. MMGSY logo on top plate and back of all steel plates will be painted with ready mixed synthetic enamel paints of superior quality in required shade and colour as specified. All the sections for frame and posts will be painted with primer and two coats of epoxy paint. The steel tube below ground level will be painted with three coats of epoxy paint. The design painting and lettering will be done as per approved drawing.

The work shall be carried out as per design as per the instructions of the Engineer-in-charge. The measurements shall be recorded and paid on **number** basis for board fixed in position.

Item No. 15 : Cautionary Warning Sign :- Providing and fixing sign board made out of 2mm aluminium sheet size 90 x 90 x 90 cms equilateral triangle as per the design of IRC-67-1977. Pre treated with phosphating process and acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint, reflectorized with retro reflective sheeting as per the latest M.O.R.T.H. specification, 3.1 Mt. long stand post and frame fabricated from suitable size iron angle of 35 x 35 x 3 mm, 75 x 75 x 6 mm; painted with best quality epoxy coating in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 cms for each leg, including excavation curing etc. complete under the supervision of Engineer-in-charge. (A) Engineer grade (VR).

The relevant specification of **Item No. 10** shall be followed for the execution for the work is **Cautionary Warning Sign :- Providing and fixing sign board made out of 2mm aluminium sheet size 90 x 90 x 90 cms equilateral triangle as per the design of IRC-67-1977. Pre treated with phosphating process and acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint, reflectorized with retro reflective sheeting as per the latest M.O.R.T.H. specification, 3.1 Mt. long stand post and frame fabricated from suitable size iron angle of 35 x 35 x 3 mm, 75 x 75 x 6 mm; painted with best quality epoxy coating in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 cms for each leg, including excavation curing etc. complete under the supervision of Engineer-in-charge. (A) Engineer grade (VR).**

Measurement shall be taken and paid on No. basis.

Item No. 16 : Informatory Warning Sign :- Providing & fixing sign boards made out of 2mm aluminium sheet size 80 x 60 cms as per design of IRC 67-1977. Pre treated with phosphating process and acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint, reflectorized with retro reflective sheeting as per the latest M.O.R.T.H. specification, 3.1 mt. long stand post and frame fabricated from suitable size iron angle of 35 x 35 x 3 mm, 75 x 75 x 6 mm; painted with best quality epoxy coating in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 cms for each leg, including excavation curing etc. complete under the supervision of Engineer-in-charge. (A) Engineer grade (VR).

The relevant specification of **Item No. 10** shall be followed for the execution for the work is **Informatory Warning Sign :- Providing & fixing sign boards made out of 2mm aluminium sheet size 80 x 60 cms as per design of IRC 67-1977. Pre treated with phosphating process and acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint, reflectorized with retro reflective sheeting as per the latest M.O.R.T.H. specification, 3.1 mt. long stand post and frame fabricated from suitable size iron angle of 35 x 35 x 3 mm, 75 x 75 x 6 mm; painted with best quality epoxy coating in black and white bends. The details of symbol for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60 cms for each leg, including excavation curing etc. complete under the supervision of Engineer-in-charge. (A) Engineer grade (VR).**

Measurement shall be taken and paid on No. basis.

Item No. 17 :- Type - A, "W" : Metal Beam Crash Barrier (Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per clause 810)

810. METAL BEAM CRASH BARRIERS

810.1. General

810.1.1. This work shall consist of furnishing and erection of metal beam crash barrier of dimensions and at locations as shown on the drawing (s) or as directed by the Engineer.

810.1.2. Metal beam crash barrier shall generally be located on approaches to bridge structures, at locations where the embankment height is more than 3 metres and at horizontal curves and location as specified by Engineer in charge.

810.2. Materials

810.2.1. Metal beam rail shall be corrugated sheet steel beams of the class, type, section and thickness indicated on the plans. Railing posts shall be made of steel of the section, weight and length as shown on the plans. All complete steel rail elements, terminal sections, posts, bolts, nuts, hardware and other steel fittings shall be galvanized. All elements of the railing shall be free from abrasions, rough or sharp edges and shall not be kinked, twisted or bent.

810.2.2. Steel beam elements and terminal sections shall be galvanized (zinc coated, 0.55 kg per square metre, minimum single spot) unless otherwise specified. The galvanizing on all other steel parts shall conform to the relevant IS Specifications. All fittings (bolts, nuts, washers) shall conform to the IS : 1367 and IS : 1364. All galvanizing shall be done after fabrication.

810.2.3. Concrete for bedding and anchor assembly shall conform to section 1700 of these Specifications.

810.3. Construction Operations

810.3.1. The line and grade of railing shall be true to that shown on the plans. The railing shall be carefully adjusted prior to fixing in place, to ensure proper matching at abutting joints and correct alignment and camber throughout their length. Holes for field connections shall be drilled with the railing in place in the structure at proper grade and alignment.

810.3.2. Unless otherwise a specified on the drawing, railing steel posts shall be given one shop coat of paint (primer) and three coats of paint on structural steel after erection, if the sections are not galvanised. Any part of assembly below ground shall be painted with three coats of red lead paint.

810.3.3. Splices and end connections shall be of the type and designs or shown on the plans and shall be of such strength as to develop full design strength of the rail elements.

810.4 Installation of Posts

- 810.4.1. Holes shall be dug or drilled to the depth indicated on the plans or posts may be driven by approved methods and equipment, provided these are erected in proper position and are free from distortion and burring or any other damage.
- 810.4.2. All post holes that are dug or drilled shall be of such size as will permit proper setting of the posts and allow sufficient room for back filling and tapping.
- 810.4.3. Holes shall be back filled with selected earth or stable materials in layers not exceeding 100 mm thickness and each layer shall be thoroughly tamped and rammed. When back filling and tamping are completed, the posts or anchors shall be held securely in place.
- 810.4.4. Post holes that are drilled in rock and holes for anchor posts shall be back filled with concrete.
- 810.4.5. Posts for metal beam guardrails on bridges shall be bolted to the structure as detailed on the plans. The anchor bolts shall be set to proper location and elevation with templates and carefully checked.

810.5 Erection

- 810.5.1. All guardrail anchors shall be set and attachments made and placed as indicated on the plans or as directed by the Engineer.
- 810.5.2. All bolts or clips used for fastening the guardrail or fittings to the posts shall be drawn up tightly. Each bolt shall have sufficient length to extend at least 6 mm through and beyond the full nut, except where such extensions might interfere with or endanger traffic in which case the bolts shall be cut off flush with the nut.
- 810.5.3. All railings shall be erected, drawn and adjusted so that a length of 3 metre. The railing barrier shall be erected true to line and grade.

810.6. Tolerance

The posts shall be vertical with a tolerance not exceeding 6 mm in a length of 3 metre. The railing barrier shall be erected true to line and grade.

810.7. Measurements for Payment

- 810.7.1. Metal beam railing barriers will be measured by **linear metre** of completed length as per plans and accepted in place. Terminals/anchors of various types shall be paid for by numbers.
- 810.7.2. No measurement for payment shall be made for projections or anchors beyond the end posts except as noted above. Furnishing and placing anchor bolts and/or devices for guard rail posts on bridges shall be considered incidental to the construction and the costs thereof shall be included in the price for other items of construction.
- 810.7.3. No measurement for payment will be made for excavation or back filling performed in connection with this construction.

810.8. Rate

The Contract unit rate shall include full compensation for furnishing of labour, materials, tools, equipments and incidental costs necessary for doing all work involved in constructing the metal beam railing barrier complete in place in all respects as per these Specifications.

Payment shall be made on **Running Meter** basis of the finished work.

Item No. 18 : Cat Eye/ Road Stud/ RPM :- Supplying of moulded Twin shanks Raised pavement markers made of Polycarbonate and ABS moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the distance and shall support a load of 13635 Kgs. tested in accordance to ASTM-D 4380 Type H and complying to specifications of Category - A of MORTH circular No. RW/NH/33023/10-97-DO in Dt. 11.06.1997. The height, width and length shall not exceed 20mm, 130mm and 130mm and width minimum reflective area of 13 Sq.cm on each side and slope to the base shall be 35 +/- 5 degrees. The strength of detachment of the integrated cylindrical shanks (of diameter not less than 19 +/- 2 mm) and height not less than 30+/-2mm) from the body is to be a minimum value of 500 kgf fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacture's recommendations and the colour of the marker should be as per the IRC 35-2005 and as directed by engineer in charge.

1.0 General

The colour, configuration, size and location of Molded Twin Shanks Raised Pavement Markers for highways other than Expressways shall be in accordance with the Code of Practice for Road Signs, IRC:35-2015 or as shown on the drawings or as directed by the Engineer.

The Molded Twin Shanks Raised Pavement Markers shall be reflectorised as shown on the drawings or as directed by the Engineer. It shall be of retro-reflectorised type and made of polycarbonate and ABS moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 13635 kgs. tested in accordance to ASTM D 4280 Type H and complying to Specifications of Category A of MORTH Circular No RW/NH/33023/10-97 – DO III Dt. 11.06.1997.

In general, cautionary and mandatory signs shall be fabricated through process of screen printing. In regard to informatory signs with inscriptions, either the message could be printed over the reflective sheeting, or cut letters of non-reflective black sheeting used for the purpose which must be bonded well on the base sheeting as directed by the Engineer.

1.2 Materials :

The various materials and fabrication of the Molded Twin Shanks Raised Pavement Markers shall conform to the following requirements.

The adhesive materials shall be of standard quality and it shall be high resistance quality against heavy moving vehicles.

The materials shall be used for the body of the Molded Twin Shanks Raised Pavement Markers is of high density PVC materials.

The dimensions and size of the Molded Twin Shanks Raised Pavement Markers shall be as per IS standard. The retro-reflective sheeting used on the Molded Twin Shanks Raised Pavement Markers shall consist of the white or coloured sheeting having a smooth outer surface which has the

property of retro reflection over its entire surface. It shall be weather resistant and show colour fastness. It shall be new and unused and shall show no evidence of cracking, scaling, pitting, blistering, edge lifting or curling and shall have negligible shrinkage or expansion. A certificate of having tested the sheeting for these properties in an unprotected outdoor exposure facing the sun for two years and its having passed these tests shall be obtained from a reputed laboratory, by the manufacturer of the sheeting. The reflective sheeting shall be either of Engineering Grade material with enclosed lens or of High Intensity Grade with encapsulated lens. The type of the sheeting to be used would depend upon the type, functional hierarchy and importance of the road.

High intensity grade sheetings : This sheeting shall be of encapsulated lens type consisting of spherical glass lens, elements adhered to a synthetic resin and encapsulated by a flexible, transparent water-proof plastic having a smooth surface. The retro-reflective surface after cleaning with soap and water and in dry condition shall have the minimum co-efficient of retro-reflection determined in accordance with ASTM D 4280 Type H).

TABLE 800.1

ACCEPTABLE MINIMUM CO-EFFICIENT OF RETRO-REFLECTION FOR HIGH INTENSITY GRADE SHEETING

[CANDEL AS PER LUX PER SQUARE METRE]

Observation (in degree)	Entrance angle (in degree)	White	Yellow	Orange	Green/ Red	Blue
0.2	-4	250	170	100	45	20
0.2	+ 30	150	100	60	25	1.1
0.5	- 4	95	62	30	15	7.5
0.5	+ 30	65	45	25	10	5.0

When totally wet, the sheeting shall not show less than 90 percent of the values of retro reflective indicated in Table 800-1. At the end of 7 years, the sheeting shall retain at least 75 percent of its original retro-reflectance.

Engineer grade sheetings : This sheeting shall be of enclosed lens type consisting of micro prismatic lens elements embedded beneath the surface of a smooth, flexible, transparent, water proof plastic, resulting in a non-exposed lens optical reflecting system. The retro-reflective surface after cleaning with soap and water and in dry condition shall have the minimum co-efficient of retro-reflection determined in accordance with ASTM D 4280 Type H) as indicated in Table 800.2.

TABLE 800.2
ACCEPTABLE MINIMUM CO-EFFICIENT OF
RETRO-REFLECTION FOR HIGH INTENSITY GRADE SHEETING
[CANDEL AS PER LUX PER SQUARE METRE]

Observation (in degree)	Entrance angle (in degree)	White	Yellow	Orange	Green	Red	Blue
0.2	-4	70	50	25	9.0	14.5	4.0
0.2	+ 30	30	22	7.0	3.5	6.0	1.7
0.5	-4	30	25	13.5	4.5	7.5	2.0
0.5	+ 30	15	13	4.0	2.2	3.0	0.8

When totally wet, the sheeting shall not show less than 90 percent of the values of retro reflective indicated in Table 800-2. At the end of 5 years, the sheeting shall retain at least 50 percent of its original retro-reflectance.

1.3 Processed and applied in accordance with recommended procedures, the reflective material shall be weather resistant and, following cleaning, show no appreciable discolouration, cracking, blistering or dimensional change and shall not have less than 50 percent of the specified minimum reflective intensity values (Table 800-1 and 800-2) when subjected to accelerated weathering for 1000 hours, using type E or EH Weatherometer (AASHTO Designation M 268).

1.4 INSTALLATION:

The Molded Twin Shanks Raised Pavement Markers shall be installed directly on road surface, after cleaning completely by removing all dust and other foreign materials from the surface of the road.

1.5 MEASUREMENT FOR PAYMENT :

The measurement of Molded Twin Shanks Raised Pavement Markers shall be in numbers, these shall be measured in **No.**

1.6 RATE :

The Contract unit rate shall be payment in full for the cost of making Molded Twin Shanks Raised Pavement Markers including all materials, installing it at the site and incidentals to complete the work in accordance with the specifications.

Item No. 19 : Excavation for foundation up to 1.50 mt. depth including sorting out and stacking of useful material and disposing off the excavated stuff within all lead and lift for all sorts of soil.

304.1 Scope

Excavation for structures shall consist of the removal of material for the construction of other similar structures, in accordance with the requirements of these Specifications and the lines and dimensions shown on the drawings or as indicated by the Engineer. The work shall include construction of the necessary cofferdams and cribs and their subsequent removal; all necessary sheeting, shoring, bracing, draining and pumping; the removal of all logs, stumps, grubs and other deleterious matter and obstruction, necessary for placing the foundations, trimming bottoms of excavations; backfilling and clearing up the site and the disposal of all surplus material.

304.2 Classification of Excavation

301.2.1. Classification : All materials involved in excavation shall be classified by the Engineer in the following manner:

(a) Soil

This shall comprise topsoil, turf, sand, silt, loam, clay, mud, peat, black cotton soil, soft shale or loose murrum, a mixture of these and similar material which yields 10 the ordinary application of pick, spade and/or shovel, rake or other ordinary digging equipment. Removal of gravel or any other modular material having dimension in any one direction not exceeding 75 mm shall be deemed to be covered under this category.

(b) Ordinary Rock (not requiring blasting) this shall include:

- (i) Rock types such as laterites, shales and conglomerates, varieties of limestone and sandstone etc., which may be quarried or split with crow bars, also including any rock which in dry state may be hard, requiring blasting but which, when wet, becomes soft and manageable by means other than blasting;
- (ii) macadam surfaces such as water bound and bitumen bound; soling of roads, cement concrete pavement, coddle stone etc. compacted murrum or stabilized soil requiring use of pick axe or shovel or both.
- (iii) lime concrete, stone masonry and brick work in lime/cement mortar below ground level, reinforced cement concrete which may be broken up with crow bars or picks and stone masonry in cement mortar below ground level; and
- (iv) boulders which do not require blasting found lying loose on the surface or embedded in river bed, soil, talus, slope wash and terrace material of dissimilar origin.

- (c) Hard Rock (requiring blasting)
This shall comprise:
 - (i) any rock or cement concrete for the excavation of which the use of mechanical plant and/or blasting is required;
 - (ii) reinforced cement concrete below ground level and in bridge / ROB / RUB / fly over piers and abutments,
 - (iii) boulders requiring blasting.
- (d) Hard Rock (using controlled blasting)
Hard rock requiring blasting as described under (c) but where controlled blasting is to be carried out in locations where built-up area, huts and are situated at within 200m of the blast site.
- (e) Hard Rock (blasting prohibited)
Hard rock requiring blasting as described under (c) but where blasting is prohibited for any reason like people living within 20m of blast sites etc. and excavation has to be carried out by chiselling, wedging or any other agreed method.
- (f) Marshy Soil
This shall include soils like soft clays and peats excavated below the original ground level of marshes and swamps and soils excavated from other areas requiring continuous pumping or bailing out of water.

304.3 Construction Operations

304.3.1 Setting Out

After the site has been cleared according to Clause 201, the limits of excavation shall be set out true to lines, curves and slopes, curves, slopes, grades and sections as shown on the drawings or as directed by the Engineer. The Contractor shall provide all labour, survey instruments and materials such as strings, pegs, nails, bamboos, stones, lime, mortar, concrete etc. required in connection with the setting out of works and the establishment of bench marks. The Contractor shall be responsible for the maintenance of bench marks and other marks and stakes as long as in the opinion of the Engineer, they are required for the work.

304.3.2 Excavation

Excavation shall be taken to the width of the lowest step of the footing including additional width as required for construction operation. The sides shall be left plumb where the nature of soil allows it. Where the nature of soil or the depth of the trench and season of the year do not permit vertical sides, the Contractor at his own cost shall put up necessary shoring; strutting and planking or cut slopes to a safer angle or both with due regard to the safety of personnel and works and to the satisfaction of the Engineer.

The depth to which the excavation is to be carried out shall be as shown on the drawings, unless the type of material encountered is such as to require changes, in which case the depth shall be as ordered by the Engineer. Propping shall be undertaken when any foundation or stressed zone from an adjoining structure is within a line of 1 vertical to 2 horizontal from the bottom of the excavation.

Where blasting is to be resorted to, the same shall be carried out in accordance with Clause 302 and all precautions indicated therein observed. Where blasting is likely to endanger adjoining foundations or other structures, necessary precautions such as controlled blasting, providing rubber mat cover to prevent flying of debris etc. shall be taken to prevent any damage.

304.3.3 Dewatering and Protection

Normally, open foundations shall be laid dry. Where water is met with in excavation due to stream flow, seepage, springs, rain or other reasons, the Contractor shall take adequate measures such as bailing, pumping, constructing diversion channels, drainage channels, bunds, depression of water level by well-point system, cofferdams and other necessary works to keep the foundation trenches dry when so required and to protect the green concrete/ masonry against damage by erosion or sudden rising of water level. The methods to be adopted in this regard and other details thereof shall be left to the choice of the Contractor but subject to the approval of the Engineer. Approval of the Engineer shall, however, not relieve the Contractor of the responsibility for the adequacy of dewatering and protection arrangements for the quality and safety of the works.

Where cofferdams are required, these shall be carried to adequate depths and heights, be safely designed and constructed and be made as watertight as is necessary for facilitating construction to be carried out inside them. The interior dimensions of the cofferdams shall be such as to give sufficient clearance for the construction and inspection and to permit installation of pumping equipment's etc. inside the enclosed area.

If it is determined beforehand that the foundations cannot be laid dry or the situation is found that the percolation is too heavy for keeping the foundation dry, the foundation concrete shall be laid under water by tremie pipe only. In case of flowing water or artesian springs, the flow shall be stopped or reduced as far as possible at the time of placing the concrete.

Pumping from the interior of any foundation enclosure shall be done in such a manner as to preclude the possibility of the movement of water through any fresh concrete. No pumping shall be permitted during the placing of concrete and for a period of at least 24 hours thereafter, unless it is done from a suitable sump separated from the concrete work by a watertight wall or other similar means.

At the discretion of the Contractor, cement grouting or other approved methods may be used to prevent or reduce seepage and to protect the excavation area.

The Contractor shall take all precautions in diverting channels and in discharging the drained water as not to cause damage to the works, crops or any other property.

304.3.4 Preparation of Foundation

The bottom of the foundation shall be levelled both longitudinally and transversely or

stepped as directed by the Engineer. Before footing is laid, the surface shall be slightly watered and rammed. In the event of excavation having been made deeper than that shown on the drawings or as otherwise ordered by the Engineer, the extra depth shall be made up with concrete as per Clause 2104.1 at the cost of the Contractor. Ordinary filling shall not be permitted to bring the foundation to the design level as shown in the drawing.

When rock or other hard strata is encountered, it shall be freed of all soft and loose material, cleaned and cut to a firm surface either level or stepped as directed by the Engineer. All seams shall be cleaned out and filled with cement mortar or grout to the satisfaction of the Engineer. In the case of excavation in rock, annular space around footing shall be filled with lean concrete M 15 up to the top level of rock.

If the depth of fill required is more than 1.5 m in soft rock or 0.6 m in hard rock above the foundation level, the filling up to this level shall be done with M-15 concrete and portion above shall be filled by concrete or by boulders grouted with cement.

When foundation piles are used, the excavation for pile cap shall be done after driving / casting of all piles forming the group. After pile driving operations in a given pit are completed, all loose and displaced materials therein shall be removed to the level of the bottom of the pile cap.

304.3.5 Slips and Slip-Outs

If there are any slips or slip-outs in the excavation, these shall be removed by the Contractor at his own cost.

304.3.6 Public Safety

Near towns, villages and all frequented places, trenches and foundation pits shall be securely fenced, provided with proper caution signs and marked with red lights at night to avoid accidents. The Contractor shall take adequate protective measures to see that the excavation operations do not affect or damage adjoining structures. For safety precautions, guidance may be taken from IS:3764.

304.3.7 Backfilling

Backfilling shall be done with approved material after concrete or masonry is fully set and carried out in such a way as not to cause undue thrust on any part of the structure. All space between foundation masonry or concrete and the sides of excavation shall be refilled to the original surface in layers not exceeding 150 mm compacted thickness. The compaction shall be done with the help of suitable equipment such as trench compactor, mechanical tamper, rammer, plate vibrator etc. after necessary watering, so as to achieve the maximum dry density.

304.3.8 Disposal of Surplus Excavated Materials

All the excavated materials shall either be reused with the approval of the Engineer or disposed off with all leads and lifts as directed by Engineer in charge.

304.4 Measurements for Payment

Excavation for structures shall be measured in Cu.m for each class of material encountered, limited to the dimensions shown on the drawings or as directed by the Engineer. Excavation over increased width, cutting of slopes, production/support to the existing structures shoring, shuttering and planking shall be deemed as incidental to the main work and shall not be measured and paid separately.

304.5 Rates

304.5.1 The Contract unit rate for the items of excavation for structures shall be payment in full for carrying out the required operations including full compensation for:

- i. setting out;
- ii. transporting the excavated materials for use or disposal with all leads and lifts;
- iii. construction of necessary cofferdams, cribs/sheeting, shoring and bracing and their subsequent removal;
- iv. removal of all logs, stumps, grubs and other deleterious matter and obstructions, for placing the foundations including trimming of bottoms of excavations;
- v. foundation sealing, dewatering including pumping when no separate provision for it is made in the Contract;
- vi. backfilling, clearing up the site and disposal of all surplus material with all leads and lifts or as otherwise specified; and
- vii. all labour, materials, tools, equipment, safety measures, diversion of traffic and incidentals necessary to complete the work to Specifications.

304.5.2 The Contract unit rate for preparation of rock foundation shall be full compensation for cutting, trimming and cleaning the foundation surface and filling/sealing of all seams with cement grout or mortar including all materials, labour and incidentals required for completing the work.

Item No. 20 Providing and filling in foundation with ordinary cement concrete M-100 mix and providing necessary vertical pin headers including formwork, vibrating, ramming and curing complete.

1. In case of ordinary concrete, mix is not required to be designed by preliminary tests and proportions of cement fine aggregate and coarse aggregates are specified by volume as given in table below for different four grades designated as ordinary M-100, M-150, M-200 and M-250.
2. In the designation of a concrete mix letter M refers to the mix and the number to the specified 28 days works cube compressive strength of that mix on 100 mm cubes expressed in kg./cm.
3. The ordinary concrete mix shall generally be specified by volume for cement which normally comes in bags and is used by weight, volume shall be worked out taking 50 kg. of cement as 0.035 cubic metre in volume. While measuring aggregate by volume, shaking ramming or hammering shall not be done proportioning of sand be as per its dry volume. In case it is dam, allowance for bulking shall be made as per IS : 2386 (Part-III).
4. In gradients required for ordinary / concrete containing one 50 kg. bag of cement for different proportions of mix shall be as given in Table below.

TABLE

Grade of concrete	Mix by volume	Total quantity of dry aggregates by volume per 50 kg. cement to be taken as sum aggregate of the individual volumes of fine & coarse aggregates, maximum	Proportion of fine aggregate to coarse aggregate	Quantity of water per 50 kg. of cement max.
(1 cubic metre : 1000 Liters)				
1	2	3	4	5
Ordinary	Litres			Litres
M-100	1:3:6	300	General 1:2 for fine aggregate to Coarse aggregate by volume but subject to a upper limit of 1:1.1/2 & a lower limit of 1:3.	34
M-150	1:2:4	220		32
M-200	1:1.1/2:3	160		30
M-250	1:1:2	100		27

Note :- The proportion of the aggregates shall be adjusted from upper limit to lower limit progress grading of the final aggregate becomes finer and the maximum size of coarse aggregate becomes larger.

Example : For an average grading of fine aggregate (that is zone II of IS : 383 - 1963) the proportions 1:1 1/2,1:2 and 1:3 for maximum size of aggregates 10mm, 20 mm and 40mm respectively (after carrying out sieve analysis).

Note:- A mix leaner than M-100 (1:3:6) may be used for non structural part, if provided in the contract. In such cases grading of aggregates shall be by volume. Other requirements for mixing, placing and curing shall the same.

5. Following shall be the maximum nominal size of coarse aggregate for the different items of work.

Sr. No.	Item of construction	Maximum nominal size of coarse aggregate
i	R.C.C. well curb, R.C.C. well steining and R.C.C. Piles	40 mm
ii.	R.C.C. well steining	63 mm
ii	Well cap or pile cap, solid type piers, abutments and wing walls and their pier caps	40 mm
iii	R.C.C. works in cross girders, deck slab, wearing coat, kerb, light post, blast walls, approach slab etc. and hollow type piers, abutments, wing walls and their pier caps	20mm
iv	R.C.C. bearings	20 mm
v	For any other item of construction not covered by items (i) to (v)	As specified on the drawing or as desired by the Engineer in charge in case it is not specified on drawing.

For heavily reinforced concrete members as in the case of ribs of main beams, nominal maximum size of aggregate shall usually be restricted to 5 mm. less than the minimum lateral clear distance between the main bars or 5 mm. less than the minimum cover to the reinforcement whichever is the smaller.

6. Fine aggregate shall be clean, hard, coarse sand. It shall be free from dust and such other substances. The sand shall be got approved by the Engineer-in-charge.
7. All materials shall be stored as to prevent their deterioration or intrusion of their quality and fitness for the work. Any material which has deteriorated or has been damaged or is otherwise considered defective by the Engineer-in-charge shall not be used in the work
8. Cement shall be store above the ground level in perfectly dry and watertight sheds and shall be stocked not more than eight bags high. Wherever bulk storage containers are used. their capacity should be sufficient to cater to the requirements at site and should be cleaned at least once every 3 to 4 months. Cement more than 3 to 4 months old shall invariably be tested to ascertain that R satisfies the ascertain requirements. The aggregates shall be stored in such a way as to prevent admixture of foreign materials. Different sizes of the fine or coarse aggregate shall be stored in separate stock piles sufficiently removed from each other to prevent intermixing the materials.
9. The water for mixing shall be portable water to the satisfaction of the Engineer-in-charge. The quantity of water shall be just sufficient to produce a dense concrete of required workability for the job.
10. For all work concrete shall be mixed in a mechanical mixer which along with other accessories shall be kept in first class working condition and so maintained throughout the construction. Mixing shall be continued till materials are uniformly distributed and uniform colour of the entire mass is obtained and each individual particle of the coarse aggregate shows complete coating of mortar containing its proportionate amount of cement. In no case shall the mixing be done for less than 2 minutes after all ingredients have been put into the mixer.
11. When hand mixing is permitted by the Engineer-in-charge for small jobs or for certain other reasons, it shall be done on a smooth watertight platform large enough to allow efficient. Turning over of the ingredients of concrete before and after adding water. Mixing platform shall be so arranged that no foreign material shall get mixed with concrete nor does the mixing water flow out. Cement in required number of bags shall be placed in a uniform layer on top of the measured quantity of fine and coarse aggregate. Which shall also be spread in a layer of uniform thickness on the mixing platform ? Dry coarse and fine aggregate and cement then shall be mixed thoroughly by turning over to get a mixture of uniform color. Enough water shall then be added gradually through a nose and the mass turned over till a mix of required consistency is obtained. In hand mixing quantity of cement shall be increased by 10 percent above that specified.

12. Mixers which have been out of use for more than 30 minutes shall be thoroughly cleaned before putting in a new batch. Unless otherwise agreed to by the Engineer-in-charge the first batch of concrete from the mixer shall contain only two third of normal quantity of coarse aggregate. Mixing plants shall be thoroughly cleaned before changing from one type of cement to another.
13. The method of transporting and placing concrete shall be approved by the Engineer-in-charge. Concrete shall be so transported and placed that no contamination, segregation or loss of its constituent material takes place. All form work and reinforcement contained in it shall be cleaned and made free from standing water, dust, snow or ice immediately before placing of concrete. No concrete shall be placed in any part of the structure until the approval of the Engineer-in-charge has been obtained.
14. If concreting is not started within 24 hours of the approval being given, it shall have to be obtained again from the Engineer-in-charge. Concreting then shall proceed continuously over the area between construction joints. Fresh concrete shall not be placed against concrete which has been in position for more than 30 minutes unless a proper construction joint is formed. Concrete shall be compacted in its final position within 30 minutes of its discharge from the mixer unless carried in properly designed agitators, operating continuously, when this time shall be within 2 hours of the addition of cement to the mix and within 30 minutes of its discharge from the agitator. Except where otherwise agreed to by the Engineer-in-charge, concrete shall be disposed in horizontal layer to a compacted depth of not more than 0.45 metre when internal vibrators are used and not exceeding 0.30 metre in all other cases.
15. Unless otherwise agreed to by the Engineer-in-charge concrete shall not be dropped into place from a height exceeding 2 metres. When trucking or chutes are used they shall be kept clean and used in such way as to avoid segregation. When concreting has to be resumed on a surface which has hardened, it shall be roughened swept clean, thoroughly wetted, and cleaned with a 13 mm. thick -layer of mortar composed of cement and sand in the same ratio as in the concrete mix itself. This 13 mm. layer of mortar shall be freshly mixed and placed immediately before placing of new concrete. Where concrete has not fully hardened, all laitance shall be removed by scrubbing the wet surface with wire or bristle brush, care being taken to avoid dislodgement of particulars of coarse aggregate. The surface shall then be thoroughly wetted. All free water removed and then coated with neat cement grout. The first layer of concrete to be placed on this, surface shall not exceed 150 mm. in thickness and shall be well rammed against old work particular attention being given to corner and close spots.
16. All concrete shall be compacted to produce a dense homogenous mass with the assistance of Vibrators, unless otherwise permitted by the Engineer-in-charge for exceptional cases, such as concreting Under water, where vibrators cannot be used Sufficient vibrators in serviceable condition shall be kept at site so that spare equipment is always available in the event, of break downs.
17. Immediately after compaction concrete shall be protected against harmful effects of weather including rain, running water shocks, vibrations due to traffic, rapid temperature changes. Fast drying put process, it shall be covered with wet sacking Hessian or other similar absorbent material approved by the Engineer-in-charge soon after the initial set. It shall be kept continuously wet for a period of not less than 14 days from the date of placement. Masonry work over the foundation concrete may be started after 48 hours of it's laying but the curing of concrete shall be continued for a minimum period of 14 days.
18. Form work shall include all temporary or permanent forms required for forming the concrete, together with all temporary construction required for their support. Formwork shall however be delivered into following two district categories :-
 - (1) Shuttering i.e. from work required for forming the concrete
 - (2) Scaffolding i.e. formwork required for supporting shuttering.

Forms for shuttering shall be constructed only, in metal suitably lined. Forms for scaffolding shall be constructed of metal or timber. Both shuttering and scaffolding shall be of substantial rigid construction and shuttering shall be true to shape and dimensions shown on the drawings. All bolts and reverts shall be counter-sunk and well ground to provide a smooth, plane surface.

- 19.** Forms shall be mortar tight and shall be made sufficiently rigid by the use of ties and bracings to prevent any displacement or sagging between supports. They shall be strong enough to withstand all pressure, ramming and vibration, without deflection from the prescribed lines occurring during and after placing the concrete. Screw jacks or hardwood wedges where required shall be provided to make up any settlement in the form work either before or during the placing of concrete. Suitable camber shall be provided in horizontal members of structure especially in long spans to counteract the effects of any deflection. The framework shall be so fixed as to provide for such camber. Forms shall be as constructed as to be removable in sections in the desired sequence, without damaging the surface of concrete or disturbing other sections. Unless otherwise specified or directed. Chamfers or fillets of size 25 mm x 25 mm shall be provided at all angles of framework to avoid sharp corners.
- 20.** The inside surface of forms shall except in the case of permanent form work or where otherwise agreed to by the engineer-in-charge be coated with an approved material to prevent adhesion of concrete to the form work. Release agents shall be applied strictly in accordance with the manufacturer's instruction and shall not be allowed to come into contact with any reinforcement of prestressing tendons and anchorage shall be applied strictly in accordance with the manufacturer's instruction and shall not be allowed to come into contact with any reinforcement of prestressing tendons and anchorage. Different release agents shall not be used in form work of concrete which will be visible in the finished works.
- 21.** Special measures shall be taken to ensure that the framework does not hinder the shrinkage of concrete because without these cracking could occur before the form work is removed. Wherever applicable arrangement must be made to ensure that the form does not restrain the shortening and hogging of the beams or slabs during tensioning of the tendons. The formwork should take due account of the calculated amount of positive or negative camber so as to ensure the correct final shape of the structures having regard to the deformation of false work, scaffolding or propping and the instantaneous deformation due to various causes affecting prestressed structures. Where there are re-entrant angles in the concrete section, the formwork should be removed at these sections as soon as possible after the concrete has set in order to avoid cracking due to shrinking of concrete. Formwork shall be tight enough to prevent any appreciable loss of cement during vibrations. Suitable tolerances should be provided in the formwork, immediately before concreting all forms shall be thoroughly cleaned. Contractor shall give the Engineer-in-charge due notice before placing any concrete in the forms to permit him to inspect and accept the false work and forms as to their strength alignment and general fitness, but such inspection shall not relieve the contractor of his responsibility for safety of machinery materials and for results obtained.
- 22.** The Engineer-in-charge shall be informed in advance by the contractor of his intention to strike any form for work. While fixing the time for removal of formworks. Due consideration shall be given to local condition, Character of the structure, the weather and other condition that influence the setting of concrete the removal of the load supporting of soffit forms may commence when concrete has attained strength and of the materials used in the mix. Where field operations are controlled by the strength test of concrete, the removal of the load supporting of soffit forms may commence when concrete has attained strength equal to at least twice the stress to which the concrete will be subject at the time of striking props including the effect of any further addition of loads. When field operations are not controlled by strength test of concrete the vertical forms of beams, columns and walls may be removed after 2 days. The props of slabs and beams may be removed after 14 and 21 days respectively. All form work shall be removed without causing any damage to the concrete. Centering shall be gradually and uniformly lowered in such a manner as to avoid any shock or vibrations. Supports shall be removed in such a manner as to permit the concrete to take stresses due to its own weight uniformly and gradually. Where internal metal ties are permitted they or their removable parts shall be extracted without causing any damage to the concrete and remaining holes filled with mortars. No permanently embedded metal part shall

have less than 25 mm. cover to the finished concrete surface. Where it is intended to reuse the framework R shall be cleaned and made good to the satisfaction of the Engineer-in-charge.

23. Immediately after the removal of forms, all exposed bars or bolts passing through the Cement concrete member and used for shuttering or any other purpose shall be cut inside the Cement Concrete member to a depth of at least 25 mm. below the surface of the concrete and the resulting holes filled by cement mortar. All fins cause by from joints, all cavities produced by the removal of from ties and all other holes and depressions, honeycomb spots, broken edges or corner and other defects shall be thoroughly cleaned, saturated with water and carefully pointed and rendered true with mortar of cement and fine aggregate mixed in the proportions used in the grade of concrete with mortar or cement and fine aggregate mixed in the proportions used in the grade of concrete that is being finished and of as dry a consistency as is possible to use. Considerable pressure shall be applied in filling and pointing to ensure thorough filling in all voids. Surface which has been pointed shall be kept moist for a period of 24 hours. If rock, pockets/honeycombs, in the opinion of the Engineer-in-charge are of such extent of and character as to affect materially or to endanger the life of the strength or the steel reinforcement he may declare the concrete defective and require the removal and replacement of the portions of the structure affected.
24. In the case of reinforced concrete work, workability shall be such that the concrete surrounds and properly grips all reinforcement. The degree of consistency, which shall depend upon the nature of work and. methods of vibration of concrete shall be determined regular slump test. Following slump shall be adopted for different types of works.

	Type of Work	Slump where vibrator is used	Slump where vibrator is not used
1	Mass conc. In RCC, foundation footing and retaining walls	10 to 25 mm	80 mm
2	Beam slab and column with simply reinforced	25 to 40 mm	100 to 120 mm
3	Thin RCC section or congested steel	40 to 50 mm	125 to 150 mm

25. Works strength tests shall be made in accordance with IS : 516. Each test shall be conducted on ten specimens five of which shall be tested at seven days and the remaining five at 28 days. The samples of concrete shall be taken on each day of concreting and, cubes shall be made at the rate of one for every 5 cubic meter of concrete or a part thereof. However if concreting done in a day is than 15 cubic meter, the minimum number of cubes can be reduced to 6 with the specific permission of the Engineer-in-charge. Similar works tests shall be carried out when ever the quality and grading of materials is changed irrespective of the quantity of concrete poured, The number of specimens may be suitable increased as deemed necessary by the Engineer-in-charge when procedure to tests given above reveals a poor quality of concrete and in other special cases.
26. The average strength of the group of cubes cast for each day shall not be less than the specified works cube strength. 20 percent of the cubes cast each day may have values less than the specified strength provided the lowest value is not less than 85 percent of the specified strength.
27. R.C.C. work shall have exposed concrete surface. Centering design and its erection shall be approved by the Engineer-in- charge. One carpenter with helper will invariably be kept throughout the period of concreting. Movement of labour and other persons shall be totally prohibited over reinforcement laid in position. For access to different parts, suitable mobile platforms shall be provided so that steel reinforcement in position as not disturbed. For ensuring proper cover, mortar blocks of suitable size shall be cast and tied to the reinforcement. Timber, kapachi or metal pieces shall not be used for this purpose. Concreting of important structural members shall always be done in the presence and under the supervision of departmental person not below the rank of Asstt. Engineer / Addl. Asstt. Engineer / Overseer or as instructed by the Engineer-in-charge. After removal of 'form work and suturing, the executive Engineer shall inspect the work and satisfy by random checks

that concrete produced is of good quality. Plastering shall not be allowed to the exposed faces of concrete.

28. In reinforced concrete the volume occupied by reinforcement shall not be deducted. The slab shall be measured as running continuously through and the beam as the portion below the slab.
29. All necessary labour, materials, equipment etc. for sampling, preparing test cubes, curing etc. shall be provided by the Contractor. Testing of the materials and concrete may be arranged by the Engineer-in-charge in an approved laboratory at the cost of the contractor.
30. The unit rate for concrete shall include the cost of all materials, labour, tools and plant required for mixing, placing in position, vibrating and compacting finishing as per directions of the Engineer-in-charge, curing and all other incidental expenses for producing concrete of specified strength to complete the structure or its components as shown on the drawings and according to these specifications. The rate shall also include the cost of making fixing and removing of all centers and forms required for the work.
31. **The payment will be made on cumt. basis of the finished work.**

Item No. 21 :- Providing and casting in situ ordinary cement concrete M-150 mix and providing necessary pin headers including shuttering, scaffolding, laying, vibrating, curing and finishing complete without V-groove (A) height 0.0 to 5.0 mt.

The work shall be executed as per specification of **Item No. 20** except the work is for **providing and casting in situ ordinary cement concrete M-150 mix and providing necessary pin headers including shuttering, scaffolding, laying, vibrating, curing and finishing complete without V-groove (A) height 0.0 to 5.0 mt.**

Measurement shall be taken and paid on Cum basis.

Item No. 22 : Providing and fixing Guard stone as per I.R.C. type design including white washing etc. complete (i) Fixing in C.C. 1:5:10.

The guard stone shall be approved quality as per I.R.C. type design including necessary reinforcement and of 20 x 15 cm. size and its length shall not be less than 75 cms. The top portion shall be rounded. The top 38 cms. shall be chilleseled dressed on all sides. The size, shape and dimensions of the guard stone shall be exact and shall be neatly dressed and finished.

Fixing in C.C. 1:5:10

The Guard stone shall be fixed in C.C. 1:5:10 which will consist of one part of cement, five part of good sand and ten parts of good brick bats. Rate includes all labour and curing etc. necessary for concrete.

Unit rate of guard stone includes the cost of all materials, labours, tools, fixing & white washing as directed by the Engineer-in-charge.

In case of Deep/Causeway the guard stone shall be fixed in masonry of head wall as directed by Engineer-in-charge.

Measurement shall be taken and paid on **Number** basis.

Item No. 23 :- Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layer not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering etc. complete.

1.0 WORKMANSHIP

- 1.1. The earth to be used for filling shall be free from salts, organic or other foreign matter all clots of earth shall be broken.
- 1.2. As soon as the work in foundation has been completed and measured the site of foundation shall be cleared of all debris brick bats mortar dropping etc. and filled with earth in layers not exceeding 20 cms. each layer shall be adequately watered, rammed and consolidated before the succeeding layer is laid. The earth shall be rammed with iron rammers where feasible and with the ends of crow-bars, where rammer cannot be used.
- 1.3. The plinth shall be similarly filled with earth in layers not exceeding 20 cms adequately watered and consolidated by ramming with iron or wooden rammers. When filling reaches finished level the surface shall be flooded with water for at least 24 hours and allowed to dry and then rammed and consolidated.
- 1.4. The finished level of filling shall be kept to shape intended to be given to floor.
- 1.5. In case of large heavy duty flooring like factory flooring, the consolidation may be done by power rollers, where so specified. The extent of consolidation required shall also be as specified.

2.0. Mode of Measurements & Payment

- 2.1. The payment shall be made for filling in plinth and trenches. No deduction shall be made for shrinkage or voids, if consolidated as instructed above.
- 2.2. The rate shall be for a unit of one cubic meter.

Item No. 24 Providing and laying filter media 600 mm thick as directed at back of abutment, returns and wing walls as per detailed specifications.

1. Well graded pebbled or metal of 40 mm to 63 mm. size shall be used. The grading and tolerances of metal of pebbles shall be as under:-

Sr. No.	No. of Size Range	Sieve designation	Percentage by weight passing through the
1	63 mm. to 40 mm	90 mm.	100-00
		63 mm.	85-100
		50 mm.	35-70
		40 mm.	00-15
		20 mm.	00-05

The size shall be 40 mm. to 63 mm. where in tolerance limit for over size shall be upto 15% and that for lower size should be upto 15% and below 20 mm. it shall be allowable upto 5%. The filter Materials shall be tightly placed to a thickness of not less than 600 mm. and provided over the entire surface behind abutments, wings or return walls to the full height.

2. Materials shall be first stacked in boxed of 2 m. 1.1/2 m. x 0.5 m. size on fairly level ground and measured.
3. The measurement for payment shall be made on **Sq.m.** basis of Specified Thickness.
4. The unit rate includes the cost of materials, scaffolding labour and tools to complete the work.

2504.2.2 Filter Medium

The material for the filter shall consist of coarse sand, gravel or stone. One or more layers of graded materials, to act as a filter medium, shall be provided underneath the pitching, to prevent loss of the embankment material and build up of uplift head on the pitching.

The gradation of the filter material shall satisfy the following requirements :

$$\frac{D_{15} \text{ of Filter}}{D_{85} \text{ of Base Material}} < 5$$

$$4 > \frac{D_{15} \text{ of Filter}}{D_{15} \text{ of Base Material}} < 20$$
$$\frac{D_{50} \text{ of Filter Material}}{D_{50} \text{ of Base Material}} < 25$$

Notes :

1. Filter design may not be required if embankment consists of CH or CL soils with liquid limit greater than 30, resistant to surface erosion. In this case, if a layer of material is used as bedding for pitching, it shall be well graded and its D 85 size shall be at least twice the maximum void size in pitching
2. In the foregoing, D15 means the size of that sieve which allows 15 percent by weight of the filter material to pass through it and similar is the meaning of D 50 and D 85 (15 being replaced with 50 and 85 respectively).
3. If more than one filter layer is required, the same requirement as above shall be followed for each layer. The finer filter shall be considered as base material for selection of coarser filter.
4. The filter shall be compacted to a firm condition. The thickness of filter is generally of the order of 200 mm to 300 mm. Where filter is provided in two layers, thickness of each layer shall be 600 mm.

Item No. 25 Providing and filling sand behind abutment & between returns in layers as directed etc. complete.

1. The sand to be used for filling shall be coarse, granular, clean, free from dust and deleterious matters obtained from a source as approved by the Engineer-in-charge. Sand between returns shall conform to I.S. : 383.
2. After the bottom plug has been laid and tested for leakage the level of its top shall be ascertained and recorded and the well shall be filled with sand under water in suitable layers not exceeding 30 cm. at a time and each layer well compacted by rodding to maximum density upto the level of the underside of the plug as per detailed drawing or as directed by the Engineer-in-charge.
3. Sand behind abutment & between returns in layers shall be filled in suitable layers not exceeding 30 cms. at a time and each layer shall be well compacted.
4. Mode of measurement shall be the total cubical content (in **Cum.**) of the area covered by sand filling.
5. Unit rate includes the cost of materials, labour and tools and plant to complete the work.

Item No. 26 Providing flood gauge marks on sub structure as per design including painting complete.

1. The width of the flood gauge shall be 60 cm. and will have cannerly yellow background colour. The flood gauge marking will be in 10 cm. thick strips of alternative black and white colour. The width of the strip shall be as under :-
 - (a) At every 10 cm. 15 cm. width
 - (b) At every 1/2 cm. 25 cm. width in black
 - (c) At every metre... 35 cm. width in white

The lettering shall be in black colour and of 10 cm. height. The lettering shall show every metre and 1/2 m. level. The lettering shall show based on either GST B.M. or Arbitrary B.M. as furnished by Engineering-in-charge.

2. All the painting work shall be done in 3 coats. The paint shall be of approved make.
3. The measurement for payment shall be on **running meter** basis measured in vertical.
4. The unit rate includes the cost of materials, labour, painting, equipment if any to complete the work.

Item No. 27 :- Providing masonry steps with cement pointing on approaches as directed.

1. Stones subject to mark deterioration will not be accepted. The stone shall be sound, hard, durable and fairly regular in shape and its thickness in any one direction shall not be less than 15 cm.
2. Before laying the stones, the slope of embankment shall be trimmed to the required profile put up by the means of line and page§ to receive the steps and kerb on it. Depression shall be filled and thoroughly compacted. The width of the tread shall be 30 cm. (clear) and shall extend further 15 cm. below next tread, thickness of the stone work of the shall depend upon the slop of the embankment as under:-
 - (a) Slope 1 to 2... 15 cm.
 - (2) Slope 1 to 3... 10cm.The thickness of the stones work shall be uniform throughout and shall not be less than the height of the riser depending upon the slope of the embankment as stated above. There shall not be more than 3 stones in the total 45 cms. width of the tread.
3. Kerb of 15 cm. width & 25 cm. depth, flush with the embankment slope line shall be provided to prevent spilling of earth on the steps. Width of the steps between the kerbs shall be 90 cms. Unevenness and voids shall be filled with quarry spalls and exposed faces of the tread riser and kerb of the stones work shall be cement pointed in proportion as specified so that they are stable and remain in line and level. For cement pointing relevant specifications of that item shall apply.
4. The unit rate includes the cost of materials, labour and tools including cement pointing to complete the work.
5. The payment shall be made on **step** basis for completed item.

Item No. : 28 Providing fusion bonded epoxy coating not less than 175 micron thickness and up to 300 micron to reinforcement bars as per IS-13620-1993/ATM-775M including testing of coating at plant and all taxes (A) 10mm to 16mm dia. bar.

2804. EPOXY MORTAR FOR REPLACEMENT OF SPALLED CONCRETE

2804.1. Material

2804.1.1. Formulation

The epoxy resins for use in the mortar shall be obtained from a reputed manufacturer and the mortar shall be prepared in conformity with the manufacturer's recommendations.

They shall generally conform to the following :

Pot life	:	90 minutes at 25 degrees Celsius
		60 minutes at 30 degrees Celsius
		45 minutes at 35 degrees Celsius
Bond strength	:	12 MPa
Tensile strength	:	16 MPa

The contractor shall carry out tests on the samples made out or requirements indicated above.

The sand content in the mortar shall be in accordance with the desired consistency.

2804.2. Proportioning and Mixing

The resin and hardener shall be mixed before adding the dry filler. The mixed ready to use mortar should not contain lumps of unwetted filler and should be uniform in colour. For a total weight of 1 kg or less, hand mixing will be sufficient. For quantities in excess of 1 kg, the component shall be mixed for 3 minutes with a slow speed –400 – 600 rpm – electric drill with a jiffy mixer. The stirrer shall be moved up and down and along the sides until an even streak free colour is obtained. Whipping in an excessive amount of air shall be avoided. If no power is available, a flat putty knife may be used to reach into the corners of the can and hand mixing done for at least 5 minutes.

2804.3. Surface Preparation

Surface upon which epoxy is to be placed shall be free of rust, grease, oil, paint, loose material, unsound concrete, dust or any other deleterious material.

Since cured epoxy does not provide adequate bond with any material, all overlay, whether epoxy or cement based, shall be done within pot life of the base epoxy layer.

2804.4. Contaminants, such as oil, grease, tar, asphalt, paint, wax, curing compounds or surface impregnants like linseed oil or silicones, including laitance and weak or loose concrete shall be removed. When bonding to asphalt, the surface should be roughened so that clean aggregate is exposed. Epoxy bonding agents shall not be applied when it rains, or in standing water. The surface must be dry.

Two general methods of surface preparation shall be followed :

- a) Mechanical that includes grinding, grit blasting, water blasting and scarification.
- b) Chemical that includes acid etching with 15 per cent by weight of hydrochloric solution, followed by repeated flushing with high pressure stream of water.

2804.5. Application

Epoxy primer coat shall be applied with the help of stiff nylon bristle brushes or hard rubber rollers or spray gun depending upon the nature of surface and extent of work area. As far as possible, the coating shall be uniformly thick.

Before the primer coat is fully cured, epoxy mortar shall be applied by means of trowels and floats. The interval between the application of primer coat and epoxy mortar shall be approximately 15 /30 minutes depending upon the ambient temperature.

Seal Coat shall be applied after 24 hours curing, after mild roughening of the surface of the mortar.

2804.6. Coverage

The coverage of resin mix would depend on the system of resin used. However, as a general guideline the coverage area shall be as under:

- a) **Primer coat:** One kg of resin – hardener mix covers an area of 3-6 square metres per coat depending on the finish of the concrete.
- b) **Epoxy mortar.** One square metre of surface requires approximately 20-24 kg of epoxy mortar when laid to a thickness of 10 mm.
- c) **Seal coat:** 4 to 6 square metres per kg of mix depending on the temperature of application.

2804.7. Cleaning and Maintenance of Equipment

Tools and equipment are best cleaned immediately after use since the removal using a scraper and remainder washed away completely using solvents such as toluene, xylene or acetone. Equipments used for epoxy shall always be cleaned before it hardens. Solvents used for this purpose may be Methyl Chloride (non-flammable). Cured epoxies may be removed using Methylene Chloride.

2804.8. Testing

Epoxy used for making mortar shall conform to all requirements and testing procedures as laid down in Clause 2803.9.

2804.9. Handling precautions

Epoxy resins can cause irritation of skin in sensitive persons if incorrectly handled. The resin and hardener should be allowed to come into direct contact with skin. The most effective protection is achieved by wearing rubber or polythene gloves.

2804.10. Personnel and Environment Safety

Any skin contact with epoxy materials, solvents and epoxy strippers should be avoided. Epoxy resins and particularly epoxy hardeners (B Component) may cause a rash on the skin. The official toxicity classification on the container labels may be looked for before starting work.

Rubber gloves, with a cloth liner and protective clothing shall be worn. Barrier creams are recommended but are not substitutes for protective clothing. Eyes shall be protected where splashing could occur while spraying or mixing. Good ventilation shall be ensured and inhalation of vapours avoided. If materials are sprayed, a respirator shall be used.

If skin contact occurs, it shall be immediately washed with a cleaner, followed by soap and water. Should eye contact occur, it shall be flushed immediately with plenty of water for 15 minutes and a doctor called for.

If contact occurs with the clothing, it shall be immediately changed to prevent further skin contact, and if the contact occurs with components A or B, the clothing shall be thrown away. Hardened epoxy is not harmful but will break the clothing.

All emptied, used buckets, rags and containers shall be removed from site. These shall be stored in waste disposal bags and suitably disposed.

➤ **Mode of Measurement & Payment :-**

Payment shall be measured and paid for a unit of **M.T.**

Item No. 29 :- Providing fusion bonded epoxy coating not less than 175 micron thickness and up to 300 micron to reinforcement bars as per IS-13620-1993/ATM-775M including testing of coating at plant and all taxes (B) 20mm to 32mm dia. bar.

The work shall be executed as per specification of **Item No. 28** except the work is for **providing fusion bonded epoxy coating not less than 175 micron thickness and up to 300 micron to reinforcement bars as per IS-13620-1993/ATM-775M including testing of coating at plant and all taxes (B) 20mm to 32mm dia. bar.**

Measurement shall be taken and paid on M.T. basis.

Item No. 30 : Demolition including stacking of serviceable materials and disposal of unserviceable material with all lead and lift (1) RCC work.

➤ **Scope**

This work shall consist of dismantling and removing existing culverts, bridges, pavements, kerbs and other structures like guard-rails, fences, utility services, manholes, catch basins, inlets etc. from the right of way which in the opinion of the Engineer interfere with the construction of road or are not suitable to remain in place, disposing of the surplus / unsuitable materials and backfilling to after the required compaction as directed by the Engineer.

Existing culverts, bridges, pavements and other structures which are within the highway and which are designed for removed shall be removed upto the limits and extent specified in the drawings or as indicated by the Engineer-in-charge.

Dismantling and removal operations shall be carried out with equipment and in such a manner as to leave undisturbed, adjacent pavement, structure and any other work to be left in place.

All operations necessary for the removal of any existing structure which might endanger new construction shall be completed prior to the start of new work.

➤ **Dismantling Culverts and Bridges**

The structures shall be dismantled carefully and the resulting materials so removed as not to cause any damage to the part of the structure to be retained and any other properties or structures nearby.

Unless otherwise specified, the superstructure portion of culverts/ bridges shall be entirely removed and other parts removed upto at least 600mm below the sub-grade, slope face or original ground level whichever is the lowest or as necessary depending upon the interference they cause to the new construction. Removal of overlying or adjacent materials, if required in connection with the dismantling of the structures, shall be incidental to this item.

Where existing culverts/ bridges are to be extended or otherwise incorporated in the new work, only such part or parts of the existing structure shall be removed as are necessary and directed by the Engineer to provide a proper connection to the new work. The connecting edges shall be cut, chipped and trimmed to the required lines and grades without weakening or damaging any part of the structure to be retained. Due care should be taken to ensure that reinforcing bars which are to be left in place so as to project into new work as dowels or ties are not be injured during removal of concrete.

Pipe culverts shall be carefully removed in such a manner as to avoid damage to the pipes.

Steel structures shall unless otherwise provided be carefully dismantled in such a manner as to avoid damage to members thereof. If specified in the drawing or directed by the Engineer that the structure is to be removed in a condition suitable for re-erection, all members shall be match marked by the contractor with white lead paint before dismantling end pins, nuts, loose plates, etc. shall be similarly marked to indicate their proper location, all pins, pin holes and machined surface shall be painted with a mixture of white lead and tallow and all loose parts shall be securely wired to adjoined members or packed in boxes.

Timber structures shall be removed in such a manner as to avoid damage to such timber or lumber having salvage value as is designated by the Engineer.

➤ **Dismantling Pavements and Other structures**

In removing pavements, kerbs, gutters and other structures like guard rails, fences, manholes, catch basins, inlets etc. where portions of the existing construction are to be left

in the finished work the same shall be removed to an existing joint or out and chipped to a true line with a face perpendicular to the surface of the existing structure. Sufficient removal shall be made to provide for proper grades and connections with the new work as directed by the Engineer.

All concrete pavements, base course in carriageway and shoulders etc. designed for removal shall be broken to pieces whose volume shall not exceed 0.02 cubic metre and used with the approval of the Engineer or disposed of.

➤ **Back-filling**

Holes and depressions caused by dismantling operations shall be backfilled with excavated or other approved materials and compacted to required density as directed by the Engineer.

➤ **Disposal of Materials**

All surplus materials shall be taken over by the Contractor which may either be re-used with the approval of the Engineer or disposed of with all lead and lifts.

➤ **Measurements for Payment**

The work of dismantling shall be paid for in units indicated below by taking measurements before and after, as applicable.

(i)	Dismantling brick/stone masonry / concrete (Plain and reinforced)	Cubic Metre
(ii)	Dismantling flexible and cement concrete pavement	Cubic Metre
(iii)	Dismantling steel structure.	Tonne
(iv)	Dismantling timber structure	Cubic Metre
(v)	Dismantling pipes, guard rails, kerbs, gutters and fencing.	Linear Metre
(vi)	Utility services	No.

➤ **Rate**

The contract unit rates for the various items of dismantling shall be payment in full for carrying out the required operations including full compensation for all labour, materials, tools, equipment, safeguards and incidentals necessary to complete the work. The rates will include excavation and backfilling to the required compaction and for handling, giving credit towards salvage value disposing of the dismantled materials within all lead and lifts.

➤ Payment shall be made on **Cubic Meter** basis.

Item No. 31 : Excavation for foundation in sand, gravel, clay soft soils and murrum etc. including shoring, strutting dewatering as necessary and disposing of the excavated stuff as directed. (A) Depth upto 3.0 M. and lead upto 100m for 10 Cum.

The work shall be executed as per specification of **Item No. 19** except the work is for **excavation for foundation in sand, gravel, clay soft soils and murrum etc. including shoring, strutting dewatering as necessary and disposing of the excavated stuff as directed. (A) Depth upto 3.0 M. and lead upto 100m for 10 Cum.**

Payment shall be made on **Cubic Meter** basis.

Item No. 32 : Providing and casting in situ ordinary cement concrete M-150 for R.C.C. raft and cut-off walls including necessary shuttering, laying, vibrating, ramming and curing complete.

The work shall be executed as per specification of **Item No. 20** except the work is for **providing and casting in situ ordinary cement concrete M-150 for R.C.C. raft and cut-off walls including necessary shuttering, laying, vibrating, ramming and curing complete.**

Measurement shall be taken and paid on Cum basis.

Item No. 33 : Providing and casting in situ controlled cement concrete M-300 for R.C.C. raft and cut-off walls including necessary shuttering, laying, vibrating, ramming and curing complete upto 5 mt.

1701 DESCRIPTION

The work shall consist of producing, transporting, placing and compacting of structural concrete including fixing formwork and temporary works etc. and incidental construction in accordance with these Specifications and in conformity with the lines, grades and dimensions, as shown on the drawings or as directed by the Engineer.

1702 MATERIALS

All materials shall conform to Section 1000 of MORTH SPECIFICATION 5th Revision.

1703 GRADES OF CONCRETE

1703.1 The grades of concrete shall be designated by the characteristic strength as given in Table 1700-1, where the characteristic strength is defined as the strength of concrete below which not more than 5 percent of the test results are expected to fall.

Table 1700-1: Grades of Concrete

Type of Concrete / Grade Designation			Characteristic Strength in MPa
Nominal Mix Concrete	Standard Concrete	High Performance Concrete	
M15	M15		15
M20	M20		20
	M25		25
	M30	M30	30
	M40	M35	35
	M45	M40	40
	M50	M45	45
		M50	50
		M55	55
		M60	60
		M65	65
		M70	70
		M75	75
		M80	80
		M85	85
		M90	90

1. Normal Mix Concrete is made on the basis of nominal mix proportioned by weight of its main ingredients - cement, coarse and fine aggregates and water.
2. Standard concrete is made on the basis of design mix proportioned by weight of its ingredients, which in addition to cement, aggregates and water, may contain chemical admixtures to achieve certain target values

of various properties in fresh condition, achievement of which is monitored and controlled during production by suitable tests. Generally concrete of grades up to M50 are included in this type.

3. High Performance Concrete is similar to standard concrete but contains additional one or more mineral admixtures providing binding characteristics and partly acting as inert filler material which increases its strength, reduces its porosity and modifies its other properties in fresh as well as hardened condition. Concrete of grades upto M90 are included in this type.
4. For concrete of grades higher than M90, the design parameters may be obtained from specialized literature and experimental results.

1703.2 The minimum grades of concrete and corresponding minimum cement content and maximum water/cement ratios for different exposure conditions shall be as indicated in Table 1700-2.

1703.3 For concrete subjected to sulphate attack the minimum grades of concrete, minimum cement content and maximum water/cement ratios and types of cement for different concentration of sulphate content shall be as indicated in Table 1700-3.

Table 1700-2: Requirement of Concrete for Different Exposure Condition using 20 mm Aggregate

Exposure Condition	Maximum Water Cement Ratio	Minimum Cement Content, kg/m ³	Minimum Grade of Concrete
Moderate	0.45	340	M25
Severe	0.45	360	M30
Very Severe	0.40	380	M40

Note:

- i. All three provisions given in the above table for a particular exposure condition, shall be satisfied.
- ii. The term cement for maximum w/c ratio and minimum cement content shown in Table includes all cementitious materials mentioned in Clause 1715.2. The maximum limit of fly ash and ground granulated blast furnace slag in the blended cement shall be as specified in 18:1489 (Part 1) and 18:455 respectively.
- iii. For plain cement concrete, with or without surface reinforcement, the minimum grade of concrete can be lowered by 5 MPa and maximum water/cement ratio exceeded by 0.05.

Cement content shown in the above table shall be increased by 40 kg/m³ for use of 12.50 mm nominal size aggregates and decreased by 30 kg/m³ for use of 40 mm nominal size aggregates.

Table 1700-3: Requirement of Concrete Exposed to Sulphate Attack

Class	Concentration of Sulphates as SO ₃			Type of Cement (Note ii)	Minimum Cement Content kg/m ³	Maximum Water/Cement Ratio	Minimum Grade of Concrete
	In Soil		In Ground Water, g/l				
	Total SO ₃ %	SO ₃ in 2:1 Water: Soil Extract, g/l					
1	Traces	<1.0	<0.3	-OPC, PPC or PSC	280	0.5	M25
2	2.0 to 0.5	1.0 to 1.9	0.3 to 1.2	-OPC, PPC or PSC -SRPC	330	0.5	M25
3	0.5 to 1.0	1.9 to 3.1	1.2 to 2.5	-SRPC, -PPC or PSC	330 350	0.5 0.45	M25 M30
4	1.0 to 2.0	3.1 to 5.0	2.5 to 5.0	-SRPC	370	0.45	M35
5	>2.0	>5.0	>5.0	-SRPC with protective coating	400	0.4	M40

Note: If the requirements of maximum water/cement ratio, minimum grade of concrete and minimum cement content from other durability considerations as given in Table 1700-2 are more stringent than those given in this table, then the former will govern.

OPC : Ordinary Portland Cement, **PPC:** Portland Pozzolona Cement. **PSC:** Portland Slag Cement, **SRPC:** Sulphate Resisting Portland cement.

The minimum cement content shall be as low as possible but not less than the quantities specified in Table 1700-2 and 1700-3.

The maximum cement content excluding any mineral admixtures (Portland cement component alone) shall not exceed 450 kg/cu.m.

1703.4 Concrete used in any component or structure shall be specified by designation along with prescribed method of design of mix i.e. 'Design Mix' or 'Nominal Mix'. For all items of concrete, only design mix shall be used, except where nominal mix concrete is permitted as per drawing or by the Engineer. Nominal mix may be permitted only for minor bridges and culverts or other incidental construction, where strength requirements are up to M 20 only. Nominal mix may also be permitted for non-structural concrete or for screed below open foundations.

1703.5 If the Contractor so proposes, the Engineer may permit the use of concrete of higher grade than that specified on the drawing, provided the higher grade concrete meets the specifications applicable. The additional cost of such higher grade concrete shall be borne by the Contractor.

1704 PROPORTIONING OF CONCRETE

Prior to the start of construction, the Contractor shall design the mix in case of design mix concrete or propose nominal mix in case of nominal mix concrete, and submit to the Engineer for approval, the proportions of materials, including admixtures to be used. Water-reducing admixtures (including plasticisers or super-plasticisers) may be used at the Contractor's option, subject to the approval of the Engineer.

1704.1 Requirements of Consistency

The mix shall have the consistency which will allow proper placement and compaction in the required position. Every attempt shall be made to obtain uniform consistency. Slump test shall be used to measure consistency of the concrete.

The optimum consistency for various types of structures shall be as indicated in Table 1700-4, or as directed by the Engineer. The slump of concrete shall be checked as per IS:516.

Table 1700-4: Requirements of Consistency

Type	Slump (mm) (at the Time of Placing of Concrete)
1 a) Structure with exposed inclined surface requiring low slump concrete to allow proper compaction b) Plain Cement concrete	25
3 RCC structure with widely spaced reinforcements; e.g. solid columns, piers, abutment, footing, well steining	40-50
3 RCC structure with fair degree of congestion of reinforcement; e.g. pier and abutment caps, box culverts, well curb, well cap, walls with thickness greater than 300 mm	50-75
4 RCC and PSC structure with highly congested reinforcements e.g. deck slab girders, box girder, walls with thickness less than 300 mm	75-125
5 Under water concreting through tremie e.g. bottom plug, cast in-situ piling	150-200

Not with standing the optimum consistency indicated against SI. No. 1 to 3, the situation should be property assessed to arrive at the desired workability with the adjustment of admixture in each case, where the concrete is to be transported through transit mixer and placed using concrete pump. Under these circumstances, the optimum consistency during placement for the items of work of SI. No. 1 to 3, can be considered ranging from 75 mm to 150 mm. This is, however, subject to satisfying the other essential criteria of strength, durability etc. and approval of the Engineer.

1704.2 Requirements for Design Mixes

1704.2.1 Target Mean Strength

The target mean strength of specimen shall exceed the specified characteristic compressive strength by at least the current margin.

The current margin for a concrete mix shall be determined by the Contractor shall be taken as 1.64 times the standard deviation of sample test results taken from at least 40 separate batches of concrete of nominally similar proportions produced at site by the same plant under similar supervision, over a period exceeding 5 days, but not exceeding 6 months.

Where there is insufficient data to satisfy the above, the current margin for the initial design mix shall be taken as given in Table 1700-5 :

Table 1700-5: Current Margin for Initial Design Mix

Concrete Grade	Current Margin (MPa)	Target Mean Strength (MPa)
M15	10	25
M20	10	30
M25	11	36
M30	12	42
M35	12	47
M40	12	52
M45	13	58
M50	13	63
M55	14	69
M60	14	74
M65	15	80
M70	15	85
M75	15	90
M80	15	95
M85	16	101
M90	16	106

The initial current margin given in Table 1700-5 shall be used till sufficient data is available to determine the current margin as per Sub-Clause 1704.2.1 (i).

1704.2.2 Trial Mixes

The Contractor shall give notice to the Engineer to enable him to be present at the time of carrying out trial mixes and preliminary testing of the cubes. Prior to commencement of trial mix design, all materials forming constituents of proposed design mix should have been tested and approval obtained in writing from the Engineer. Based on test

results of material draft mix design calculation for all grades of concrete to be used in the works, shall be prepared after taking into account the provisions in the Contract Technical Specifications Guidelines of IS:10262, IS:SP:23 and IRC:112 and submitted to the Engineer for approval. Prior to commencement of concreting, trial mix design shall be performed for all grades of concrete and trial mix which has been found successful, shall be submitted by the Contractor and approval obtained. During concreting with the approved trial mix design, if source of any constituents is changed, the mix design shall be revised and tested for satisfying the strength requirements.

The initial trial mixes shall be carried out in a laboratory approved by the Engineer. However, Engineer may permit the initial trial mixes to be prepared at the site laboratory of the Contractor, if a full fledged concrete laboratory has been established well before the start of construction, to his entire satisfaction. Sampling and testing procedures shall be in accordance with these Specifications.

When the site laboratory is utilized for preparing initial mix design, the concrete production plant and means of transport employed to make the trial mixes shall be similar to those proposed to be used in the works.

For each trial mix, a set of six cubes shall be made from each of three consecutive batches for purposes of testing. Three cubes from each set of six shall be tested at an age of 28 days and three at an earlier age approved by the Engineer. The cubes shall be made, cured, stored, transported and tested in accordance with these Specifications. The mean strength of the nine cubes at 28 days shall exceed the specified characteristic strength by the current margin minus 3.5 MPa.

1704.2.3 Control of Strength of Design Mixes

- **Adjustment to Mix Proportions**

Adjustment to mix proportions arrived at in the trial mixes, shall be made subject to the Engineer's approval, in order to minimize the variability of strength and to maintain the target mean strength. Such adjustments shall not be taken to imply any change in the current margin.

- **Change of Current Margin**

When required by the Engineer, the Contractor shall recalculate the current margin in accordance with clause 1704.2.1. The recalculated value shall be adopted as directed by the Engineer, and it shall become the current margin for concrete produced thereafter.

- **Additional Trial Mixes**

In case any changes are observed in the properties of fresh concrete and/or strength of hardened concrete on the basis of early age tests, additional mixes and tests shall be carried out during production, so as to control and bring the quality of concrete within acceptable limits. In case of any change in the source or properties of materials, the design of mix shall be established afresh.

1704.3 Requirements of Nominal Mix Concrete

Requirements for nominal mix concrete unless otherwise specified shall be as given in Table 1700-6.

Table 1700-6: Requirements for Nominal Mix Concrete

Concrete Grade	Total Quantity of dry Aggregate by mass per 50 kg of cement to be taken as the Sum of individual masses of fine and coarse Aggregate	Proportion of Fine to Coarse Aggregate (by Mass)	Maximum Quantity of water for 50 kg of Cement (Litres)	
			PCC	RCC
M 15	350	Generally 1:2, subject to upper limit 1:1.5 and lower limit of 1:2.5	25	
M 20	250		2	22

1704.4 Additional Requirements

Concrete shall meet any other requirements as specified on the drawing or as directed by the Engineer. The overall limits of deleterious substances in concrete shall be as follows:

Total acid soluble chloride content in the concrete mix expressed as chloride ions shall not exceed the following values by mass of cement.

Prestressed concrete	0.10 percent
Reinforced concrete (in severe, very severe or extreme exposure condition)	0.20 percent
Reinforced concrete in moderate exposure condition	0.30 percent

The total water soluble sulphate content of the concrete mix expressed as S03, shall not exceed 4 percent by mass of cement in the mix.

For concrete made with Portland pozzolona cement, Portland blast furnace slag cement or mineral admixtures, the setting time and rate of gain of strength are different from those for concrete made with OPC alone. Such modified properties shall be taken into account while deciding the de-shuttering time, curing period, early age loading and time of prestressing. Additional cube samples may be required to be taken for verifying the concrete properties.

1704.5 Suitability of Proposed Mix Proportions

The Contractor shall submit the following information for the Engineer's approval :

Nature and source of each material

Quantities of each material per cubic metre of fully compacted concrete

Either of the following :

Appropriate existing data as evidence of satisfactory previous performance for the target mean strength, current margin, consistency and water/cement ratio and any other additional requirement (s) as specified.

full details of tests on trial mixes.

Statement giving the proposed mix proportions for nominal mix concrete

Any change in the source of material or in the mix proportions shall be subject to the Engineer's prior approval.

1704.6 Checking of Mix Proportions and Water/Cement Ratio

In proportioning concrete, the quantity of both cement and aggregate shall be determined by weight. Where the weight of cement per bag as given by the manufacturer is accepted, a reasonable number of bags shall be weighed separately to check the net weight. Where cement is weighed from bulk stock at site and not by bag, it shall be weighed separately from the aggregates. Water shall either be measured by volume in calibrated tanks or weighed. All measuring equipment shall be maintained in a clean and serviceable condition. Their accuracy shall be periodically checked.

The specified water/cement ratio shall always be kept constant and at its correct value. To this end, moisture content in both fine and coarse aggregates shall be determined as frequently as possible, the frequency for a given job being determined by the Engineer according to the weather conditions. The amount of water to be added shall then be adjusted to compensate for variations in the moisture content. For the determination of moisture content in the aggregates 18:2386 (Part III) shall be referred. Suitable adjustments shall also be made in the weight of aggregates to allow for their variation in weight due to variation in their moisture content.

1704.7 Grading of Aggregates for Pumped Concrete

Materials for pumped concrete shall be batched consistently and uniformly. Maximum size of aggregate shall not exceed one-third of the internal diameter of the pipe.

The grading of aggregates shall be continuous and shall have sufficient ultra fine materials (material finer than 0.25 mm). Proportion of fine aggregates passing through 0.25 mm shall be between 15 and 30 percent and that passing through 0.125 mm sieve shall not be less than 5 percent of the total volume of aggregate. Admixtures to increase workability can be added. When pumping long distances and in hot weather, set-retarding admixtures can be used. Fluid mixes can be pumped satisfactorily after adding plasticisers and super plasticisers. Suitability of concrete shall be verified by trial mixes and by performing pumping test.

1705 ADMIXTURES

1705.1 Chemical Admixtures

Chemical admixtures such as superplasticisers, or air entraining, water reducing, accelerating and retarding agents for concrete, may be used with the approval of the Engineer.

As the selection of an appropriate concrete admixture is an integral part of the mix design, the manufacturers shall recommend the use of any one of their products only after obtaining complete information of all the actual constituents of concrete as well as methodologies of manufacture, transportation and compaction of concrete proposed to be used in the work. Admixtures/additives conforming to IS:9103 may be used subject to approval of the Engineer. However, admixtures/additives generating hydrogen or nitrogen and containing chlorides, nitrates, sulphides, sulphates or any other material likely to adversely affect the steel or concrete, shall not be permitted.

The general requirements for admixtures are given in Clause 1007 of these Specifications.

Compatibility of the admixtures with the cement and any other pozzolona or hydraulic addition shall be ensured by for avoiding the following problems :

Requirement of large dosage of super plasticiser for achieving the desired workability,

Excessive retardation of setting,

Excessive entrainment of large air bubbles,

Unusually rapid stiffening of concrete,

Rapid loss of slump

Excessive segregation and bleeding.

1705.2 Mineral Admixtures

For use of mineral admixtures, refer Clauses 1714.1 and 1715.2.

1706 SIZE OF COARSE AGGREGATES

The size (maximum nominal) of coarse aggregates for concrete to be used in various components shall be as given in Table 1700-7.

Table 1700-7: Maximum Nominal Size of Coarse Aggregates

Components		Maximum Nominal Size of Coarse Aggregate (mm)
I)	RCC well curb	20
ii)	RCC/PCC well steining	40
iii)	Well cap or Pile Cap Solid type pier and abutment	40
iv)	RCC work in girder, slabs wearing coat, kerb, approach slab, hollow piers and abutments, pier/abutment caps, piles	20
V)	PSC Work	20

vi)	Any other work	As specified by the Engineer
-----	----------------	------------------------------

Maximum nominal size of aggregates shall also be restricted to the smaller of the following values:

10 mm less than the minimum lateral clear distance between individual reinforcements

10 mm less than the minimum clear cover to the reinforcement

One quarter of minimum thickness of member

The proportions of the various individual sizes of aggregates shall be so adjusted that the grading produces the densest mix and the grading curve corresponds to the maximum nominal

1707 EQUIPMENT

Unless specified otherwise, equipment for production, transportation and compaction of concrete shall be as under:

Production of Concrete :

For overall bridge length of less than 200 m - batch type concrete mixer, diesel or electric operated, with a minimum size of 200 litres automatic water measuring system and integral weigher (hydraulic/pneumatic type).

For overall bridge length of 200 m or more - concrete batching and mixing plant fully automatic, with minimum capacity of 15 cum per hour.

All measuring devices of the equipment shall be maintained in a clean and serviceable condition. Their accuracy shall be checked over the range in use, when set up at each site and thereafter, periodically as directed by the Engineer. Size adopted for the concrete mix.

The accuracy of the measuring devices shall fall within the following limits :

Measurement of Cement	± 3 percent of the quantity of cement in each batch
Measurement of Water	± 3 percent of the quantity of water in each batch
Measurement of Aggregate	± 3 percent of the quantity of aggregate in each batch
Measurement of Admixture	± 3 percent of the quantity of admixture in eqch batch

Transportation of Concrete:

Concrete dumpers	minimum 2 tonnes capacity
Powered hoists	minimum 0.5 tonne capacity

Chutes

Buckets handled by cranes

Transit truck mixer

Concrete pump

Concrete distributor booms

Belt conveyor

Cranes with skips

Tremies

For Compaction of Concrete:

Internal vibrators	size 25 mm to 70 mm
Form vibrators minimum	500 watts
Screed vibrators	full width of carriageway (upto two lanes)

1708 BATCHING, MIXING, TRANSPORTING, PLACING AND COMPACTION

1708.1 General

Prior to start of concreting, the Contractor shall submit for approval of the Engineer, his programme along with list of equipment proposed to be used by him for batching, mixing, transporting and placing concrete.

1708.2 Batching of Concrete

In batching concrete:

The quantity of cement, aggregate and mineral admixtures, if used, shall be determined by mass.

Chemical admixtures, if solid, shall be determined by mass.

Liquid admixtures may be measured in volume or mass, and

Water shall be weighed or measured by volume in a calibrated tank.

The concrete shall be sourced from on-site or off-site batching and mixing plants, or from approved Ready Mixed Concrete plants, preferably having quality certification.

Except where supply of properly graded aggregate of uniform quality can be maintained over a period of work, the grading of aggregate should be controlled by obtaining the coarse aggregate in different sizes and blending them in the right proportions when required, the different sizes being stocked in separate stock piles. The materials should be stock piled several hours, preferably a day before use. The grading of coarse and fine aggregate should be checked as frequently as possible to ensure that the specified grading is maintained.

The water/cement ratio shall always be maintained constant at its correct value. To this end, determination of moisture content in both fine and coarse aggregates shall be made as frequently as possible, depending on weather conditions. The amount of added water shall be adjusted to compensate for any observed variations in the moisture content. To allow for the variation in mass of aggregate due to variation in moisture content, suitable adjustment in the mass of aggregate shall also be made. Accurate control shall be kept on the quantity of mixing water, which when specified, shall not be changed without approval.

1708.3 Mixing Concrete

1708.3.1 Mixing at Site

All concrete shall be machine mixed. In order to ensure uniformity and good quality of concrete the ingredients shall be mixed in a power driven batch mixer with hopper and suitable weigh batching arrangement or in a central mix plant. Hand mixing shall not be permitted. The mixer or the plant shall be at an approved location considering the properties of the mixes and the transportation arrangements available with the Contractor. The mixer or the plant shall be approved by the Engineer.

Mixing shall be continued till materials are uniformly distributed, a uniform colour of the entire mass is obtained and each individual particle of the coarse aggregate shows complete coating of mortar containing its proportionate amount of cement. In no case shall mixing be done for less than 2 minutes. It shall be ensured that the mixers are not loaded above their rated capacities and are operated at a speed recommended by the manufacturer. When mineral admixtures are added at the mixing stage, their thorough and uniform blending with cement shall be ensured, if necessary by longer mixing time. The addition of water after the completion of the initial mixing operation shall not be permitted.

Mixers which have been out of use for more than 30 minutes shall be thoroughly cleaned before putting in a new batch and also before changing from one type of cement to another.

1708.3.2 Ready Mix Concrete

Use of ready mix concrete proportioned and mixed off the project site and delivered to site in a freshly mixed and unhardened state conforming to 18:4926, shall be allowed with the approval of the Engineer.

1708.4 Transporting Concrete

Mixed concrete shall be transported from the place of mixing to the place of final deposit as rapidly as possible by methods which will prevent the segregation or loss of the ingredients. The method of transporting or placing of concrete shall be approved by the Engineer. Concrete shall be transported and placed as near as practicable to its final position so that no contamination, segregation or loss of its constituents materials take place.

Concrete may be transported by transit mixers or properly designed buckets or by pumping. Transit mixers or other hauling equipment when used should be equipped with the means of discharge of concrete without segregation. During hot or cold weather, concrete shall be transported in deep containers. Other suitable methods to be reduce the loss of water by evaporation in hot weather and heat loss in cold weather may also be adopted.

When concrete is conveyed by chute, the plant shall be of such size and design as to ensure practically continuous flow. Slope of the chute shall be so adjusted that the concrete flows without excessive quantity of water and without any segregation of its ingredients. The delivery end of the chute shall be as close as possible to the point of deposit. The chute shall be thoroughly flushed with water before and after each working period and the water used for this purpose shall be discharged outside the formwork.

In case concrete is to be transported by pumping, the fresh concrete should have adequate fluidity and cohesiveness to be pumpable. Proper concrete mix proportioning and initial trials should ensure this. The conduit shall be primed by pumping a batch of mortar through the line to lubricate it. Once the pumping is started, it shall not be interrupted, as concrete standing idle in the line is liable to cause plug. The operator shall ensure that some concrete is always there in the pumps receiving hopper during operation. The lines shall always be maintained clean and free of dents.

Pipelines from the pump to the placing area shall be laid with minimum bends. For large quantity placements, standby pumps shall be available. Suitable air release valves, shutoff valves etc. shall be provided as per site requirements. The pumping of priming mix i.e. rich mix of creamy consistency, to lubricate the concrete pump and pipelines, shall precede the pumping of concrete. Continuous pumping shall be done to the extent possible. After concreting, the pipelines and accessories shall be cleaned immediately. The pipes for pumping shall not be made of material which has adverse effect on concrete. Aluminium alloy pipelines shall not be used.

1708.5 Placing of Concrete

All formwork and reinforcement contained in it shall be cleaned and made free from standing water, dust, snow or ice immediately before placing of concrete.

No concrete shall be placed in any part of the structure until the approval of the Engineer has been obtained. If concreting is not started within 24 hours of the approval being given, the approval shall have to be obtained again from the Engineer. Concreting shall proceed continuously over the area between the construction joints. Fresh concrete shall not be placed against concrete which has been in position for more than 30 minutes, unless a proper construction joint is formed.

The concrete shall be deposited as nearly as practicable in its original position to avoid re-handling. Methods of placing should be such as to preclude segregation. Care should be taken to avoid displacement of reinforcement or movement of formwork. To achieve this, concrete should be lowered vertically in the form and horizontal movement of concrete inside the forms should, as far as practicable, be minimised.

The concrete shall be placed and compacted before its initial setting so that it is amenable to compaction by vibration. The workability of concrete at the time of placement shall be adequate for the compaction equipment to be used. If there is considerable time gap between mixing and placing of concrete, as in the case of ready mixed concrete plants or off-site batching and mixing plants, concrete mix shall be designed to have appropriately higher workability at the time of discharge from the mixer, in order to compensate the loss of workability during transit.

This is generally achieved by suitable chemical admixtures. Keeping these considerations in view, the general requirement for ready mixed concrete plants or off-site batching and mixing plants, is that concrete shall be discharged from the truck mixer within two hours of the time of loading. A longer period may be permitted if suitable retarding admixtures are used.

In wall forms, drop chutes attached to hoppers at the top should preferably be used to lower concrete to the bottom of the form. As a general guidance, the permissible free fall of concrete may not exceed 1.5 metres and under no circumstances shall it be more than 2 metres. When free fall of larger height is involved, self compacting concrete having adequate fluidity, cohesiveness and viscosity and which uniformly and completely fills every corner of the formwork by its own weight without segregation, shall be used.

Except where otherwise agreed to by the Engineer, concrete shall be deposited in horizontal layers to a compacted depth of not more than 450 mm when internal vibrators are used and not more than 300 mm in all other cases.

Concrete when deposited shall have temperature of not less than 5°C and preferably not more than 30°C and in no case more than 40°C. In case of site mixing, fresh concrete shall be placed and compacted in its final position within 30 minutes of its discharge from the mixer. When the concrete is carried in properly designed agitator operating continuously, the concrete shall be placed and compacted within 1 hour of the addition of cement to the mix and within 30 minutes of its discharge from the agitator. It may be necessary to add retarding admixtures to concrete, if trials show that the periods indicated above are unacceptable. In all such matters, the Engineer's decision shall be final.

1708.6 Compaction of Concrete

Concrete shall be thoroughly compacted by vibration or other means during placing and worked around the reinforcement, tendons or duct formers, embedded fixtures and into corners of the formwork to produce a dense homogeneous void-free mass having the required surface finish. When vibrators are used, vibration shall be done continuously during the placing of each batch of concrete until the expulsion of air has practically ceased and in a manner that does not promote segregation. Over-vibration shall be avoided to minimize the risk of forming a weak surface layer. When external vibrators are used, the design of formwork and disposition of vibrator shall be such as to ensure efficient compaction and to avoid surface blemishes. Vibrations shall not be applied through reinforcement and where vibrators of immersion type are used, contact with reinforcement and all inserts like ducts etc. shall be avoided.

When internal vibrators are used, they shall be inserted vertically to the full depth of the layer being placed and ordinarily shall penetrate the layer below for a few centimetres. The vibrator should be kept in place until air bubbles cease escaping from the surface and then withdrawn slowly to ensure that no hole is left in the concrete, care being taken to see that it remains in continued operation while being withdrawn. The internal vibrators shall be inserted in an orderly manner and the distance between insertions should be about one and half times the radius of the area visibly affected by vibration. Additional vibrators in serviceable condition shall be kept at site so that they can be used in the event of breakdown.

Mechanical vibrators used shall comply with 18:2502, 18:2506, 18:2514 and 18:4656.

1709 CONSTRUCTION JOINTS

Construction joints shall be avoided as far as possible. In no case shall the locations of such joints be changed or increased from those shown on the drawings except with the express approval of the Engineer.

Joints should be positioned where they are readily accessible for preparation and concreting. Construction joints should be positioned to minimize the effects of the discontinuity of the durability, structural integrity and appearance

of the structure. As far as possible, joints should be provided in non-aggressive zones, but if joints in aggressive zones cannot be avoided, they should be sealed. Joints should be located away from the regions of maximum stress caused by loading; particularly where shear and bond stresses are high.

In beams and slabs joints should not be near the supports. Construction joints between slabs and ribs in composite beams shall be avoided. For box girders, there shall be no construction joint between the soffit and webs.

Joints should be either vertical or horizontal. For a vertical construction joint, the lifts of concrete shall finish level or at right angles to the axis of the member. Concreting shall be continued right up to the joint.

Before resuming work at a construction joint when concrete has not yet fully hardened, all laitance shall be removed thoroughly. The surface shall be roughened, taking care to avoid dislodgement of coarse aggregates. Concrete shall be brushed with a stiff brush soon after casting, while the concrete has only slightly stiffened. If the concrete has partially hardened, it may be treated by wire brushing or with a high pressure water jet, followed by drying with an air jet, immediately before the new concrete is placed. Fully hardened concrete shall be treated with mechanical hand tools or grit blasting, taking care not to split or crack aggregate particles. The practice of first placing a layer of mortar or grout when concreting joints, shall be avoided. The old surface shall be soaked with water, without leaving puddles, immediately before starting concreting. The new concrete shall be thoroughly compacted against it.

Where there is likely to be a delay before placing the next concrete lift, protruding reinforcement shall be protected. In all cases, where construction joints are made, the joint surface shall not be contaminated with release agents, dust, or sprayed curing membrane and reinforcement shall be firmly fixed in position at the correct cover.

The sequence of concreting, striking of forms and positioning of construction joints for every individual structure, shall be decided well in advance of the commencement of work.

1710 CONCRETING UNDER WATER

When it is necessary to deposit concrete under water, the methods, equipment, materials and proportions of mix to be used, shall be got approved from the Engineer before any work is started.

Concrete shall not be placed in water having a temperature below 5°C. The temperature of the concrete, when deposited, shall not be less than 16°C, nor more than 30°C.

Coffer dams or forms shall be sufficiently tight to ensure still water conditions, if practicable, and in any case to reduce the flow of water to less than 3 m per minute through the space into which concrete is to be deposited. Coffer dams or forms in still water shall be sufficiently tight to prevent loss of mortar through the joints in the walls. Pumping shall not be done while concrete is being placed, or until 24 hours thereafter. To minimize the formation of laitance, care shall be exercised not to disturb the concrete as far as possible while it is being deposited.

All under water concreting shall be carried out by tremie method only. The number and spacing of the tremies should be worked out to ensure proper concreting. However, it is necessary to have a minimum number of 2 tremies for any concreting operation, so that even if one of the tremies goes out of commission during concreting, the other one can be used to complete the work. The tremie concreting when started should continue without interruption for the full height of the member being concreted. The capacity of the concrete production and placement equipment should be sufficient to enable the underwater concreting to be completed uninterrupted within the stipulated time. The top section of the tremie shall have a hopper large enough to hold one full batch of the mix or the entire contents of the transporting bucket, as the case may be. The tremie pipe shall not be less than 200 mm in diameter and shall be large enough to allow a free flow of concrete and strong enough to withstand the external pressure of the water in which it is suspended, even if a partial vacuum develops inside the pipe. Preferably, flanged steel Pipe of adequate strength shall be used. A separate lifting device shall be provided for each tremie pipe with its hopper at the upper end. Unless

the lower end of the pipe is equipped with an approved automatic check valve, the upper end of the pipe shall be plugged with a wadding of gunny sacking or other approved material before delivering the concrete to the tremie pipe through the hopper, so that when the concrete is forced down from the hopper to the pipe, it will force the plug (and along with it any water in the pipe) down the pipe and out of the bottom end, thus establishing a continuous stream of concrete. It will be necessary to raise the tremie slowly in order to allow a uniform flow of concrete. At all times after placing of concrete is started and until all the required quantity has been placed, the lower end of the tremie pipe shall be kept below the surface of the plastic concrete and shall not be taken out of concrete. This will cause the concrete to build up from below instead of flowing out over the surface and thus avoid formation of layers of laitance. It is advisable to use retarders or suitable super plasticizers to retard the setting time of concrete, which shall be established before the commencement of work.

1711 CONCRETING IN EXTREME WEATHER

1711.1 Concreting in Cold Weather

Where concrete is to be deposited at or near freezing temperature, precautions shall be taken to ensure that at the time of placing, it has a temperature of not less than 5°C and that the temperature shall be maintained above 4°C until the concrete has hardened. When necessary, concrete ingredients shall be heated before mixing but cement shall not be heated artificially other than by the heat transmitted to it from other ingredients of the concrete. Stock-Copiled aggregate may be heated by the use of dry heat or steam. Aggregates shall not be heated directly by gas or on sheet metal over fire. In general, the temperature of aggregate or water shall not exceed 65°C. Salt or other chemicals shall not be used for the prevention of freezing. No frozen material or materials containing ice shall be used. All concrete damaged by frost shall be removed. Concrete exposed to freezing weather shall have entrained air and the water content of the mix shall not exceed 30 litres per 50 kg of cement. To counter slower setting of concrete, accelerators can be used with the approval of the Engineer. However, accelerators containing chloride shall not be used.

1711.2 Concreting in Hot Weather

When depositing concrete in hot weather, precautions shall be taken so that the temperature of wet concrete does not exceed 30°C while placing. This shall be achieved by using chilled mixing water, using crushed ice as a part of mixing water, shading stock piles of aggregates from direct rays of the sun, sprinkling the stock piles of coarse aggregate with water to keep them moist, limiting temperature of cement below 30°C at the time of use, starting curing before concrete dries out and restricting time of concreting as far as possible to early mornings and late evenings. When ice is used to cool mixing water, it will be considered as part of the water in design mix. Under no circumstances shall the mixing operation be considered complete until all ice in the mixing drum has melted. The Contractor will be required to state his methodology for the Engineer's approval when temperatures of concrete are likely to exceed 30°C during the work.

1712 PROTECTION AND CURING

1712.1 General

Concreting operations shall not commence until adequate arrangements for concrete curing have been made by the Contractor. Curing and protection of concrete shall start immediately, after compaction of the concrete.

The concrete shall be protected from:

Premature drying out particularly by solar radiation and wind

High internal thermal gradients

Leaching out by rain and flowing water

Rapid cooling during the first few days after placing

Low temperature or frost

Vibration and impact which may disrupt the concrete and interfere with its bond to the reinforcement.

Vibration caused by traffic including construction traffic.

Concrete shall be protected, without allowing ingress of external water, by means of wet (not dripping) gunny bags, hessian etc. Once the concrete has attained some degree of hardening (approximate 12 hrs after mixing), moist curing shall commence and be continued through the requisite period. Where members are of considerable size and length, with high cement content, accelerated curing methods may be applied, as approved by the Engineer.

1712.2 Water Curing

Water for curing shall be as specified in Section 1000 of these specifications.

Sea water shall not be used for curing. Sea water shall not come into contact with concrete members before they have attained adequate strength.

The concrete should be kept constantly wet by ponding or covering or use of sprinklers/ perforated pipes for a minimum period of 14 days after concreting, except in the case of concrete with rapid hardening cement, where it can be reduced to 5 days. Water should be applied on surfaces after the final set. Curing through watering shall not be done on green concrete. On formed surfaces, curing shall start immediately after the forms are stripped. The concrete shall be kept constantly wet with a layer of sacking, canvas, hessian or similar absorbent material.

1712.3 Steam Curing

Where steam curing is adopted, it shall be ensured that it is done in suitable enclosure to contain the live steam in order to minimize moisture and heat losses. The initial application of the steam shall be after about four hours of placement of concrete to allow the initial set of the concrete to take place.

Where retarders are used, the waiting period before application of the steam shall be increased to about six hours.

The steam shall be at 100 percent relative humidity to prevent loss of moisture and to provide excess moisture for proper hydration of the cement. The application of steam shall not be directly on the concrete. Steam curing is applied in enclosures or tunnels through which concrete members are transported on a conveying system. Alternatively, portable enclosures or plastic covers are placed over precast members and steam is supplied to the enclosures. The rate of increase or decrease of temperature should not be more than 10°C to 20°C per hour and the maximum temperature shall be about 70°C. The maximum temperature shall be maintained until the concrete has attained the desired strength required at the end of steam curing period and shall be decided by prior trials. When steam curing is discontinued, the air temperature shall not drop at a rate exceeding 10°C per hour, until a temperature of about 10°C above the ambient temperature outside has been reached. Steam curing of concrete shall be followed by water curing for at least 7 days. The concrete shall not be exposed to temperatures below freezing for at least six days after curing.

1712.4 Curing Compound

Membrane forming curing compounds consisting of waxes, resins, chlorinated rubbers etc. may be permitted by the Engineer in special circumstances. Curing compounds shall not be used on any surface which requires further finishing to be applied. All construction joints shall be moist cured and no curing compound shall be permitted in locations where concrete surfaces are required to be bonded together.

Liquid membrane forming compounds shall conform to ASTM C 309 and the curing efficiency shall be as per ASTM C 156.

Curing compounds shall be continuously agitated during use. All concrete cured by this method shall receive two applications of the curing compound. The first coat shall be applied immediately after acceptance of concrete finish. If the surface is dry, the concrete shall be saturated with water and curing compound applied as soon as the surface film of water disappears. The second application shall be made after the first application has set. Placement in more than two coats may be required to prevent streaking.

The membrane formed shall be stripped off after 14 days, when curing is complete. Impermeable membranes, such as sheet materials for curing concrete conforming to ASTM C 171 or polyethylene sheeting covering closely the concrete surface, may also be used to provide effective barrier against Evaporation.

1713 FINISHING

Immediately after the removal of forms, exposed bars or bolts, if any, shall be cut inside the concrete member to a depth of at least 50 mm below the surface of the concrete and the resulting holes filled with cement mortar. All fins caused by form joints, all cavities produced by the removal of form ties and all other holes and depressions, honeycomb spots, broken edges or corners, and other defects, shall be thoroughly cleaned, saturated with water and carefully pointed and rendered true with mortar. The mortar shall be of cement and fine aggregate mixed in the proportions used in the grade of concrete that is being finished and of as dry a consistency as possible. Considerable pressure shall be applied in filling and pointing to ensure thorough filling in all voids. Surfaces which have been pointed shall be kept moist for a period of twenty four hours. Special pre-packaged proprietary mortars shall be used where appropriate or where specified in the drawing.

All construction and expansion joints in the completed work shall be left carefully tooled and free from any mortar and concrete. Expansion joint filler shall be left exposed for its full length with clean and true edges.

Immediately on removal of forms, the concrete work shall be examined by the Engineer before any defects are made good. The work that has sagged or contains honeycombing to an extent detrimental to structural safety or architectural appearance of the member, shall be rejected. Surface defects of a minor nature may be accepted. On acceptance of such work, the same shall be rectified as directed by the Engineer.

1714 CONCRETE WITH BLENDED CEMENTS OR MINERAL ADMIXTURES

1714.1 Production of Concrete

In order to improve the durability of the concrete, use of blended cement or blending of mineral admixtures, is permitted. The maximum limit of flyash and ground granulated blast furnace slag in concrete, shall be as specified in Clause 1715.2. Blending at site shall be permitted only through a specific facility with complete automated process control to achieve the specified design quality or through RMC plants with similar facility.

1714.2 Modified Properties

For concrete made with Portland Pozzolona Cement, Portland Blast furnace slag cement or mineral admixtures, the setting time and rate of gain of strength are different from those of concrete made with OPC alone. Cognizance of such modified properties shall be taken in deciding de-shuttering time, initial time of prestressing, curing period and for early age loading.

1714.3 Compatibility of Chemical Admixtures

Compatibility of chemical admixtures and super plasticizers with Portland Pozzolona cement Portland blast furnace slag cement and mineral admixtures shall be ensured by trials outlined in Clause 1705.

1714.4 Additional Tests

In addition to the strength tests prescribed in other Sections of these Specifications, the following additional tests are required to be carried out from considerations of durability.

Rapid Chloride Ion Permissibility Test

Rapid Chloride Ion permeability test on as per ASTM C 1202 at 56 days for extreme, very severe and severe conditions of exposure. The permissible value of Chloride-Ion permeability for extreme condition 800 Coulombs very severe condition 1200 coulombs and severe exposure condition 1500 coulombs.

Water Permeability Test

Water permeability test as per DIN: 1048 Part 5-1991 shall be carried out as described in Clause 1717.2.5.5.

1715 HIGH PERFORMANCE CONCRETE

1715.1 General

High Performance Concrete shall be used where special performance requirements of high strength, high early strength, high workability, low permeability and high durability for severe service environments, are required. Production and use of such concrete in the field shall be carried out with high degree of uniformity between batches and very stringent quality control.

1715.2 Materials

Cement, mineral admixtures, chemical admixtures, aggregates and water shall conform to Section 1000 of these Specifications and this Section.

Flyash when used, shall neither be less than 20 percent nor shall be greater than 35 percent of the total by mass of ordinary Portland cement and flyash and shall conform to grade-1 of IS:3812.

Ground granulated blast furnace (GGBS) slag when used, shall neither be less than 50 percent nor greater than 70 percent of the total mass of ordinary Portland cement and GGBS and shall conform to 18:12089.

Silica fume conforming to 18:15388 shall be used.

The cement content of concrete inclusive of any mineral admixtures shall not be less than 380 kg/m³. The cement content excluding any mineral admixtures (Portland cement content alone) shall not exceed 450 kg/m³. The water/cement (cement plus all cementitious materials) ratio should generally not exceed 0.33 but in no case shall be more than 0.40.

1715.3 Compatibility of Admixtures

Compatibility of the super plasticiser and admixtures with the cement and any other Pozzolanic or hydraulic dilutes shall be ensured by trials as outlined under Clause 1705.

1715.4 Characteristic Strength and Target Mean Strength

Characteristic strength and the initial target mean strength of concrete shall be as given in Table 1700-8.

The target mean strength shall be calculated as per Clause 1704.2 after obtaining data on standard deviation from sufficient samples.

Table 1700-8: Characteristic Compressive Strength and Target Mean Strength

Grade Designation	Specified Characteristic Compressive Strength at 28 days (MPa)	Target Mean Strength (MPa)
M40	40	52
M45	45	58
M50	50	63
M55	55	69
M60	60	74
M65	65	80

M70	70	85
M75	75	90
M80	80	95
M85	85	101
M90	90	106

1715.5 Workability and Other Requirements

Workability, concrete mix design, field trial mixes, chloride and sulphate contents shall be laid down in other Sections of these Specifications.

1715.6 Mixing of Concrete

The concreting plant and means of transportation employed to make trial mixes and to transport them to representative distances shall be similar to the corresponding plant and transport to be used in the works. The optimum sequence of mixing of ingredients shall be established by trials. Mixing time may be longer than in normal grade concrete mixes.

The temperature of concrete at the time of placement shall not exceed 25°C. The temperature of concrete at the mixing stage should be lower, to allow for rise in temperature during transport. When considerable distance of transport is involved, particular attention should be paid to ensure retention of slump as targeted for placement.

1715.7 Prototype Testing

Mock-up trials or prototype testing may be carried out to ensure that the concrete can be satisfactorily placed and compacted, taking into account the location of placement and provision of reinforcement, and required adjustments made in concrete mix design and/or detailing of reinforcement.

1715.8 Curing of Concrete

High performance concrete containing silica fume is more cohesive than normal mixes hence, there is a little or no bleeding and no bleed water to rise to the surface to offset water loss due to evaporation. Plastic shrinkage cracking is possible, if curing is not proper. Initial curing should commence soon after initial setting of concrete. Concrete should be covered with moist covers, opaque colour plastic sheets or suitable curing compound. Final moist curing should commence after final setting of concrete and continue for at least 14 days.

1715.9 Additional Tests for Concrete

Apart from the strength tests prescribed in other Sections of these Specifications, the additional tests as specified under Clause 1714.3 shall also be carried out.

1716 TOLERANCES

Tolerances for dimensions/shape of various components shall be as indicated in these Specifications or shown on the drawings or as directed by the Engineer.

1717 TESTS AND STANDARDS OF ACCEPTANCE

1717.1 Concrete shall conform to the surface finish and tolerance as prescribed in these Specifications for respective components.

1717.2 Random sampling and lot by lot acceptance inspection shall be made for the 28 days cube strength of concrete.

1717.3 Concrete under acceptance, shall be notionally divided into lots for the purpose of sampling before commencement of work. The basis of delimitation of lots shall be as follows:

No individual lot shall be more than 30 cu.m in volume

Different grades of mixes of concrete shall be divided into separate lots.

Concrete of a lot shall be used in the same identifiable component of the bridge.

1717.4 Sampling and Testing

Concrete for preparing 3 test cubes shall be taken from a batch of concrete at point of delivery for construction, according to procedure laid down in 18:1199.

A random sampling procedure shall be adopted which ensures that each of the concrete batches forming the lot under acceptance inspection has equal chance of being chosen for taking cubes.

150 mm cubes shall be made, cured and tested at the age of 28 days for compressive strength in accordance with 18:516. The 28 day test strength result for each cube shall form an item of the sample. Tests at other age shall also be performed, if specified.

Where automated batching plant/Ready Mixed Concrete Plant is located away from the place of use and the time gap between production and placement is more than the initial setting time or where any ingredients are added subsequent to mixing, separate sets of samples shall be collected and tested at batching plant and at location of placement. The results shall be compared and used to make suitable adjustment at batching plants so that properties of concrete at placement are as per the requirements.

1717.5 Test Specimen and Sample Strength

Three test specimens shall be made from each sample for testing at 28 days. Additional cubes may be required for various purposes such as to determine the strength of concrete at 7 days or for any other purpose.

The test strength of the sample shall be the average of the strength of 3 cubes. The individual variation should not be more than ± 15 percent of the average. If variation is more, the test results of the sample are invalid.

1717.6 Frequency

The minimum frequency of sampling of concrete of each grade shall be in accordance with Table 1700-9.

Table 1700-9: Minimum Frequency of Sampling

Quantity of Concrete in Work, m ³	No. of Samples
1 – 5	1
6 – 15	2
16 – 30	3
31 – 50	4
50 and above	4 plus one additional sample for each additional 50 m ³ or part thereof

At least one sample shall be taken from each shift of work.

1717.7 Acceptance criteria

1717.7.1 Compressive Strength

Cubes

The concrete shall be taken as having the specified compressive strength when both the following conditions are met:
The mean strength determined from any group of four consecutive non-overlapping samples exceeds the specified characteristic compressive strength by 3 MPa.

Strength of any sample is not less than the specified characteristic compressive strength minus 3 MPa.

The quantity of concrete represented by the test results include the batches from which the first and last samples were taken, together with all intervening batches.

Cores

When the concrete does not satisfy both the conditions given in (1) above, representative cores shall be extracted from the hardened concrete for compression test in accordance with the method described in IS: 1199 and tested to establish whether the concrete satisfies the requirement of compressive strength.

Evaluation of compressive strength by taking cores may also be done in case of doubt regarding the grade of concrete used either due to poor workmanship or based on results of cube strength tests.

The locations from which core samples are to be taken and their number shall be decided so as to be representative of the whole of the concrete under consideration. However, in no case shall fewer than three cores be tested. Cores shall be prepared and tested as described in IS:516. Concrete in the member represented by a core test shall be considered acceptable if the average equivalent cube strength of the cores is equal to at least 85 percent of the cube strength of the grade of concrete specified for the corresponding age and no individual core has strength less than 75 percent of the specified strength.

1717.7.2 Chloride and Sulphate Content

The total chloride and sulphuric anhydride (SO₃) content of all the constituents of concrete as a percentage of mass of cement in the mix shall not exceed the values given in this Section.

1717.7.3 Density of Fresh Concrete

Where minimum density of fresh concrete is specified, the mean of any four consecutive non-overlapping samples shall not be less than the specified value and any individual sample result shall not be less than 97.5 percent of the specified value.

1717.7.4 Density of Hardened Concrete

Where minimum density of hardened concrete is specified, the mean of any four consecutive non-overlapping samples shall not be less than the specified value and any individual sample result shall not be less than 97.5 percent of the specified value.

1717.7.5 Permeability Test

Water permeability test as per DIN:1048 Part 5-1991 shall be carried out as described below:

A cylindrical test specimen 150 mm dia. and 160 mm high shall be prepared.

After 28 days of curing, the test will be conducted between 28 and 35 days. The test specimen shall be fitted in a machine such that specimen can be subjected to a water pressure of up to 7 bars. A typical machine is shown in Appendix-1700/1.

The concrete specimen shall be subjected to a water pressure of 0.5 N/mm² from the top for a period of 3 days. The pressure shall be maintained constant throughout the test period. If the water penetrates through to the underside of the specimen, the test may be terminated and the specimen rejected as failed.

After 3 days, the pressure shall be released and the sample shall be taken out. The specimen shall be split in the middle by compression applied on two round bars on opposite sides above and below.

When the split faces show signs of drying (after 5 to 10 minutes) the maximum depth of penetration in the direction of height shall be measured with the scale and extent of water penetration established.

The mean of maximum depth of penetration obtained from three specimens thus tested, shall be taken as the test result and it shall not exceed 25 mm.

1717.7.6 If the concrete is not able to meet any of the standards of acceptance as prescribed, the effect of such deficiency on the structure shall be investigated by the Contractor as directed by the Engineer. The Engineer may accept the concrete as sub-standard work. Any additional work required by the Engineer for such acceptance, shall

be carried out by the Contractor at his cost. In case the concrete is not found to be acceptable even after investigation, the Contractor shall remove the rejected concrete forthwith.

1717.7.7 When durability of concrete is desired the rapid chloride ion permeability test as stated under Clause 1714.3.1 shall also be performed in addition to above tests.

1718 MEASUREMENTS FOR PAYMENT

Structural concrete shall be measured in cubic metres. In reinforced or prestressed concrete, the volume occupied by reinforcement or prestressing cables and sheathing shall not be deducted. The slab shall be measured as running continuously through and the beam as the portion below the slab.

1719 RATE

The contract unit rate for structural concrete shall cover costs of all materials, labour, tools, plant and equipment required for mixing, transporting and placing in position, vibrating and compacting, finishing and curing as per this Section or as directed by the Engineer, including all incidental expenses, sampling and testing, quality assurance and supervision. Unless mentioned separately as an item in the contract, the contract unit rate for concrete shall also include the cost of providing, fixing and removing formwork required for concrete work as per **Section 1500** of these Specifications.

If the concrete is found to be acceptable by the Engineer as sub-standard work, the Contractor shall be subjected to reduction in his contract unit rate. For deficiency in compressive strength of concrete when accepted by the Engineer, the reduction in rate shall be applied as under:

$$\text{Percentage reduction in rate} = \frac{\text{Design Strength} - \text{Observed Strength}}{\text{Design Strength}} \times 100$$

The payment will be made on cumt. basis of the finished work.

Item No. 34 Providing and laying in position I.S.I. mark Fe-550D T.M.T. bar reinforcement including cutting, bending, hooking and tying complete as per detailed drawing for foundations.

The work shall be executed as per specification of **Item No. 8** except the work is for **providing and laying in position I.S.I. mark Fe-550D T.M.T. bar reinforcement including cutting, bending, hooking and tying complete as per detailed drawing for foundations.**

Measurement shall be taken and paid on M.T. basis.

Item No. 35 : Providing and casting in situ controlled cement concrete M-300 for R.C.C. return as per drawings including centering, shuttering, scaffolding wherever necessary laying, vibrating, curing and finishing complete. (A) Height from 5.0 mt. to 10.0 mt. (1) Piers & Caps (2) Abutment & caps (3) R.C.C. returns.

The work shall be executed as per specification of **Item No. 33** except the work is for providing and casting in situ controlled cement concrete M-300 for R.C.C. return as per drawings including centering, shuttering, scaffolding wherever necessary laying, vibrating, curing and finishing complete. (A) Height from 5.0 mt. to 10.0 mt. (1) Piers & Caps (2) Abutment & caps (3) R.C.C. returns.

Measurement shall be taken and paid on Cum basis.

Item No. 36 : Providing and laying in position I.S.I. mark Fe-550D (T.M.T.) bar reinforcement including cutting, bending, hooking and tying complete as per detailed drawing for the following (A) Piers (B) Abutment & (C) R.C.C. return.

The work shall be executed as per specification of **Item No. 8** except the work is for providing and laying in position I.S.I. mark Fe-550D (T.M.T.) bar reinforcement including cutting, bending, hooking and tying complete as per detailed drawing for the following (A) Piers (B) Abutment & (C) R.C.C. return.

Measurement shall be taken and paid on M.T. basis.

Item No. 37 :- Providing and laying weep hole in abutment and returns by using A.C. pipes of 100 mm dia. with laying in proper grade and jointing the completed as per detailed specification.

The weep holes in the masonry and returns shall be provided of the A.C. pipes of 100 mm dia. The pipe shall be fixed of suitable length & in full thickness of the masonry / concrete work. Necessary C.I. grating shall be provided on back side of abutment & returns on the inlet of opening of weep holes.

Materials the A.C. pipes of 100mm dia.

The Asbestos cement pipe of diameters specified in description of the item shall conform to I.S. 1626-1900. The interior of pipe shall have a smooth finish, regular surface & regular internal diameter.

The tolerance in all dim. shall be as per IS 1926-Part-I 1980.

The grating shall be of C.I. 100 mm. dia. & per IRC specification.

The weep holes shall be provided 1 meter C/C shall be placed in staggered. After laying weep holes, it shall be clear of earth and other materials from its complete length.

The rate shall be paid on **Number** basis.

Item No. 38 : Providing and casting in situ or precast controlled cement concrete M-350 for prestressed concrete work in super structure including centering, shuttering, curing, scaffolding, ramming, vibrating, finishing and launching or shifting complete (i) Solid slab.

The work shall be executed as per specification of **Item No. 33** except the work is for providing and casting in situ or precast controlled cement concrete M-350 for prestressed concrete work in super structure including centering, shuttering, curing, scaffolding, ramming, vibrating, finishing and launching or shifting complete (i) Solid slab.

Measurement shall be taken and paid on Cum basis.

Item No. 39 : Providing and placing in position I.S.I. mark Fe-550D T.M.T. bar reinforcement including cutting, bending, hooking and tying complete as per detailed drawing. (B) T-Beam and deck slab type of super structure (i) Solid slab.

The work shall be executed as per specification of **Item No. 8** except the work is for providing and placing in position I.S.I. mark Fe-550D T.M.T. bar reinforcement including cutting, bending, hooking and tying complete as per detailed drawing. (B) T-Beam and deck slab type of super structure (i) Solid slab.

Measurement shall be taken and paid on M.T. basis.

Item No. 40 :- Providing C.I. 100mm diameter water spout including necessary iron grating as per drawings.

2705 DRAINAGE SPOUTS

Drainage along longitudinal direction shall be ensured by sufficient number of drainage fixtures embedded in the deck slab. The spouts shall be of not less than 100 mm in diameter and shall be of corrosive resistant material such as galvanised steel with suitable cleanout fixtures. The spacing of drainage spouts shall not exceed 10 m. The discharge from drainage spout shall be kept away from the deck structure by means of suitable down pipes upto 500 mm above High Flood Level. In case of viaducts in urban areas, the drainage spouts should be connected with suitably located runners and down pipes to discharge the surface run-off into drains provided at ground level.

2705.1 Fabrication

The drainage assembly shall be fabricated to the dimensions shown on the drawings. All materials shall be corrosion resistant. Steel components shall be of mild steel conforming to IS:226. The drainage assembly shall be seam welded for water tightness and then hot-dip galvanised.

2705.2 Placement

The galvanised assembly shall be given two coats of bituminous paint before placement. The whole assembly shall be placed in true position, lines and levels as shown on the drawings with necessary cutouts in the shuttering for deck slab and held in place firmly. Where the reinforcements of the deck are required to be cut, equivalent reinforcements shall be placed at the corners of the cut out.

2705.3 Finishing

After setting of the deck slab concrete, the shrinkage cracks around the assembly shall be sealed with polysulphide sealant or bituminous sealant as per 18:1834 and the excess sealant trimmed to receive the wearing coat. After the wearing coat is completed, similar sealant shall be provided to cover at least 50 mm on the wearing coat surface all round the drainage assembly.

2708 MEASUREMENTS FOR PAYMENT

Drainage / water spouts shall be measured in **numbers**.

2709 RATE

The contract unit rate for drainage spout shall include the cost of all labour, material, tools and plant required for completing the work as per these specifications. It shall also include the cost of providing runners and down pipes with all fixtures upto 500 mm above high flood level or up to the drains at ground, as applicable or as shown on the drawings.

Item No. 41 : Providing and casting in situ controlled cement concrete M-40 for average 100mm thick wearing coat laid as directed including tamping, vibrating, finishing, curing and filling in joints with bitumen complete.

The work shall be executed as per specification of **Item No. 33** except the work is for **providing and casting in situ controlled cement concrete M-40 for average 100mm thick wearing coat laid as directed including tamping, vibrating, finishing, curing and filling in joints with bitumen complete.**

Measurement shall be taken and paid on Cum basis.

Item No. 42 :- Reinforced cement concrete crash barrier (Provision of an Reinforced cement concrete crash barrier at the edges of the road, approaches to bridge structures and medians, constructed with M-40 grade concrete with T.M.T. Fe-550D reinforcement conforming to IRC:21 and dowel bars 25 mm dia., 450 mm long at expansion joints filled with pre-moulded asphalt filler board as per drawing having bottom size of 450mm, top 225mm and Ht. 1100mm all locations directed by the Engineer.

809. CONCRETE CRASH BARRIERS

809.1. General

809.1.1. This work shall consist of construction, provision and installation of concrete crash barrier at the edges of the road and median at locations and of dimensions as shown on the drawings or as directed by the Engineer.

809.1.2. Concrete barrier shall generally be located on approaches to bridge structures, at locations where the embankment height is more than 3 metres and at horizontal curves.

809.2. Materials

809.2.1. All materials shall conform to Section 1000 Materials for Structures as applicable and relevant clauses in Section 1600 shall govern the steel reinforcement. The concrete barriers shall be constructed either by the “cast-in-place with fixed forms” method or the “extrusion or slip form” method or a combination thereof at the contractor’s option with the approval of the Engineer. Where “extrusion or slip form” method is adopted, full details of the method and literature shall be furnished.

809.2.2. Concrete barriers shall be constructed with M-40 grade concrete and with T.M.T. Fe-550D reinforcement conforming to IRC:21. The friction slab shall be cast in situ with crash barrier. The grade of concrete of friction slab shall be in M-40. The capping beam also in M-40 which is cast after Retaining wall fascia panel achieved desired height and desired longitudinal gradient.

809.2.3. An expansion joint with pre-moulded asphalt filler board shall be provided at the junction of crash barrier on structure and crash barrier on the fill. The crash barrier on the fill shall be constructed in pieces of length not exceeding 20 m, with pre-moulded asphalt filler board joints.

809.3. Construction Operations

809.3.1. The location of crash barrier shall be strictly adhered to as shown on the drawing and as directed by the Engineer. Concrete crash barriers shall present a smooth, uniform appearance in their final position, conforming to the horizontal and vertical lines shown on the plans or as ordered by the Engineer and shall be free of lumps, sags or other irregularities. The top and exposed faces of the barriers shall conform to the specified tolerances, as defined in Clause 809.4 when tested with 3 m straight edge, laid on the surface.

809.3.2. When concrete barriers are to be constructed on recently completed bridges, the height of the barriers shall be adjusted to compensate for the camber and dead load deflection

of the superstructure. The amount of adjustment shall be determined by the Engineer and shall be ordered before the concrete is placed. Such barriers shall be placed after formwork has been released and as long after the superstructure construction as possible without hampering the progress of the work.

809.3.3 Back filling to the concrete barriers shall be compacted in layers to the compaction of the surrounding earthwork.

809.4. Tolerance - The overall horizontal alignment of rails shall not depart from the road alignment by more than ± 30 mm, nor deviate in any two successive lengths from straight by more than 6 mm and the faces shall not vary more than 12 mm from the edge of a 3 m straight edge. Barriers shall be at the specified height as shown in the plans above the edge of the nearest adjacent carriageway or shoulder, within a tolerance of ± 30 mm.

The reinforced cement concrete crash barrier (Provision of an Reinforced cement concrete crash barrier at the edges of the road, approaches to bridge structures and medians, constructed with M-40 grade concrete with T.M.T. Fe-550D reinforcement conforming to IRC:21 and dowel bars 25 mm dia., 450 mm long at expansion joints filled with pre-moulded asphalt filler board as per drawing having bottom size of 450mm, top 225mm and Ht. 1100mm all locations directed by the Engineer.

809.5. Measurements for Payment

All barriers will be measured by linear metres of completed and accepted length in place, corresponding end to end along the face of concrete barriers including approach and departure ends.

809.6. Rate

The Contract unit rate shall include full compensation for furnishing all labour, tools, materials, equipment and incidental costs necessary for doing all work involved in constructing the concrete barrier complete in place in all respects as per these specifications.

The Rate shall be for unit of one **Running Meter**.

Item No. 43 : Providing and casting in situ controlled cement concrete M-150 for approach slab including form work, curing and finishing complete.

The work shall be executed as per specification of **Item No. 33** except the work is for **providing and casting in situ controlled cement concrete M-150 for approach slab including form work, curing and finishing complete.**

Measurement shall be taken and paid on Cum basis.

Item No. 44 : Providing and casting in situ controlled cement concrete M-200 for approach slab including form work, curing and finishing complete.

The work shall be executed as per specification of **Item No. 33** except the work is for **providing and casting in situ controlled cement concrete M-200 for approach slab including form work, curing and finishing complete.**

Measurement shall be taken and paid on Cum basis.

Item No. 45 Providing pre-moulded asphalt filler joints as per drawings (A) 40mm.

1. Open joints shall be constructed at the location as directed by the Engineer-in-charge using a wood strip metal (plate or other suitable material which is subsequently removed. When removing the material, care shall be exercised to avoid chipping or breaking the corners of the concrete. The edge of the concrete, at the joints, shall be well finished. Reinforcement shall not extend across an open joint.
2. When preformed filler is to be provided, the filler shall be placed in correct position before concrete is placed against the filler. The filler material shall form part of the joint and while concreting the slab, care shall be taken to prevent the former being displaced. After the work is completed, the exposed face of the joint shall be cleaned of all loose material sticking to it.
3. The material used for filling expansion joint shall be bitumen impregnated felt. Impregnate felt shall conform to the requirement of IS:1838 and shall be got approved from the Engineer-in-charge. The joint shall consist of large pieces and assembly of small pieces to make up the required size shall be avoided.
4. The expansion joint shall be measured in **Square metres**. Thickness of the expansion joint will be 40 mm. width of expansion joint shall be equal to full depth of the slab.
5. The rate shall include the cost of all materials, labour, equipments & incidental charges for fixing the joints complete in all respects as per these specifications and as shown on the drawing.

Item No. 46 : Filling around pipes with murrum including dressing, tampering etc. complete (Soil cone pitching)

Area around pipes shall be filled with murrum immediately after the pipes have been laid and the joining material has hardened. The material shall be clean, free from boulders large roots, excessive amount of sods or other vegetable matter, and lumps and shall be approved by the Engineer-in charge. Filling up to 0.3 metre above the top of the pipe shall be carefully done and the soil thoroughly rammed, temped or vibrated in layers of not exceeding 150 mm. particular care being taken to thoroughly consolidate the materials under the launches of the pipe. Filling shall be carried out simultaneously on both sides of the pipes in such a manner that unequal pressures do not occur. In case of high embankments after filling up to the top in the above said manner a loose fill of a depth equal to external diameter of the pipe shall be placed over the pipe before further layer are added and compacted. Materials shall be filled in pharas 3m. x 1.5. m x 0.5 m size and shall be measured in Cu.M.

Unit rate includes cost of materials and spreading including labour and tools needed for the above operations.

Payment shall be paid on **Cum** basis.

Item No. 47 :- Providing panel wall for dry stone pitching in uncoursed rubble masonry with hard stone of approved quality in cement mortar 1:3 including curing etc. complete.

1.0 Rubble Pitching

- 1.1 The work shall consist of covering the slopes of high banks, training works and road embankment with uncoursed rubble, over a layer of sand bedding with panel of 3.00 x 3.0 m of cement concrete 1:2:4 and cement pointing in cement mortar 1:3.
- 1.2. Rubble subject to marked deterioration by water or weather will not be accepted. The rubble shall be sound hard, durable and fairly regular in shape and its thickness in any one direction shall not be less than the thickness of pitching as specified in the item and thickness of the rubble at any place shall not be less by 15% of the thickness specified. The largest rubbles procurable shall be supplied on site. The sizes of spalls shall be minimum 25 mm and shall be suitable to fill the voids in the pitching. Thickness of the pitching shall be as specified in the pitching item. (G.C. No. SSR/2080 IB 547/28/C Dated 6th March 1982)
- 1.3. Before laying the pitching the sides of banks shall be trimmed to the required slopes and profiles put up by means of line and pegs at intervals of 3 meters to ensure regular straight work and uniform slope throughout. Depressions shall be filled and thoroughly compacted.
- 1.4. Sand for bedding shall be laid over the prepared base and suitably compacted to a thickness 150 Quality of sand will be as per its relevant specifications.
- 1.5. The rubble pitching shall commence in a trench below the toe of the slope. Rubble shall be placed by derrick or by hand to the required length, thickness and depth conforming to the drawings. Rubbles shall be set normal to the slope and placed so that the largest dimension is perpendicular to the face of the slope, unless such dimensions are greater than the specified thickness of pitching. The largest rubbles shall be placed in the bottom courses and use as headers for subsequent courses. When full depth of pitching can be formed with single rubble, the rubble shall be laid breaking joints and all interstices between adjacent rubbles shall be filled in with spalls of the proper size and wedged in with hammers to ensure tight packing. Pitching shall be done in panels of 3.0 M x 3.0 M with a 45 cm. wide and 22.5 cm. deeper band all around.

2.00 Stone Masonry

- 2.1. Panel wall of 3.00 x 3.0 m of cement concrete 1:2:4 in size at 3.0 m. centre to centre or as per guidelines of Engineer in charge in case of irregular dimensions.
- 2.2 Necessary curing shall be carried out.

3.00 Cement pointing

- 3.1. For a surface which is to be subsequently jointed, the joints shall be squarely raked out to a depth of 15 mm. while the mortar is still green. The raked joints shall be well brushed to remove dust and loose particles and the surface shall be thoroughly washed with water, cleaned and wetted.
- 3.2 Cement and sand shall be mixed in proportions as specified in the item. Cement and sand shall be proportioned by volume after making due allowance for bulking. The

required quantity of water shall then be added and the mortar mixed to produce workable consistency.

- 3.3.** The mixing shall be done intimately by hand mixing. The operation shall be carried out on a clean watertight platform and cement and sand shall be first mixed dry in the required proportion to obtain a uniform colour and then the mortar shall be mixed for at least two minutes after addition of water. In case of cement mortar, that has stiffened because of evaporation of water, the same shall be re-tempered by adding water as frequently as needed to restore the requisite consistency but this re-tempering shall be permitted only with thirty minutes from the time of addition of water at the time of initial mixing.
- 3.4.** For pointing, the mortar shall be filled and pressed into the raked out joints before giving the required finish. The pointing shall then be finished to proper type given on the drawings. If type of pointing after the mortar has been filled and pressed into the joints and finished off level with the edge of the bricks, it shall while still green ruled along the centre with a half round tool of such width as may be specified by the Engineer-in-charge. The superfluous mortar shall then be cut off from the edges of the lines and the surface of masonry shall also be cleaned of all mortar.
- 3.5** Curing shall be started as soon as the mortar used for finishing has hardened sufficiently not to be damaged when watered. It shall be kept wet for a period of at least 7 days. During this period shall be suitably protected from all damages.
- 3.6.** Stage scaffolding shall be approved for the work. This shall be independent of the structure.
- 3.7** Payment shall be made on **Square Meter** basis of the finished work. If directed by the Engineer-in charge for measurement the materials may have to be stacked at site before laying and nothing extra will be paid to the Contractor for this stacking. Preparation of base for laying bedding shall be deemed incidental to the work.
- 3.8** The rate shall include the cost preparing the base, putting to the profiles, providing, laying and compacting the sand bedding and dry stone pitching in uncoursed rubble masonry with hard stone of approved quality in cement mortar 1.5, cement pointing as per embankment slopes to specified thickness, lines curves, slopes and levels and all labour and material as well as tools and plant required of the work.

Item No. 48 Providing and laying Filter material underneath pitching in slopes complete as per drawing and Technical specification.

The material for the filter shall consist of sand, gravel, stone or coarse sand. To prevent escape of the embankments material through the voids of the stone pitching / cement concrete blocks as well as to allow free movement of water without creating any uplift head on the pitching, one or more layers of graded materials, commonly known as a filter medium, shall be provided underneath the pitching.

The gradation of the filter material shall satisfy the following requirements.

Provision of a suitably designed filter is necessary under the slope pitching to prevent the escape of underlying embankment material through the voids of stone pitching/cement concrete blocks when subjected to the attack of flowing water and wave action, etc. In order to achieve this requirement, the filter may be provided in one or more layers satisfying the following criteria :

$$\frac{D 15 (\text{Filter})}{D 85 (\text{Base})} < 5$$

$$4 < \frac{D 15 (\text{Filter})}{D 15 (\text{Base})} < 20$$

$$\frac{D 50 (\text{Filter})}{D 50 (\text{Base})} < 25$$

- Notes : 1. Filter design may not be required if embankment consists of CH or Ch soils with liquid limit greater than 30, resistant to surface erosion. In this case, if a layer of material is used as bedding for pitching, it shall be well graded and its D 85 size shall be at least twice the maximum void size in pitching.
2. In the foregoing, D 15 means the size of that sieve which allows 15 per cent by weight of the filter material to pass through it and similar is the meaning of D 50 and D 85.
3. If more than one filter layer is required, the same requirement as above shall be followed for each layer. The finer filter shall be considered as base material for selection of coarser filter.
4. The filter shall be compacted to a firm condition. The thickness of filter is generally of the order of 200 mm to 300 mm. Where filter is provided in two layers, thickness of each layer shall be 150 mm.

2504.3. Construction Operations

Before laying the pitching, the sides of banks shall be trimmed to the required slope and profiles put up by means of line and pegs at intervals of 3 metres to ensure regular

straight work and a uniform slope throughout. Depressions shall be filled and thoroughly compacted.

The filter granular material shall be laid over the prepared base and suitably compacted to the thickness specified on the drawings.

The lowest course of pitching shall be started from the toe wall and built up in courses upwards. The toe wall shall be in dry rubble masonry (uncoursed) conforming to Clause 1405.3, in case of dry rubble pitching and shall be in nominal mix cement concrete (M 15) conforming to Clause 1704.3 in case of cement concrete block pitching.

The stone pitching shall commence in a trench below the toe of the slope. Stone shall be placed by derrick or by hand to the required length, thickness and depth conforming to the drawings. Stones shall be set normal to the slope, and placed so that the largest dimension is perpendicular to the face of the slope, unless such dimension is greater than the specified thickness of pitching.

The largest stones shall be placed in the bottom courses and for use as headers for subsequent courses.

In hand placed pitching, the stone of flat stratified nature should be placed with the principal bedding plane normal to the slope. The pattern of laying shall be such that the joints are broken and voids are minimum by packing with spalls, wherever necessary, and the top surface is as smooth as possible.

When full depth of pitching can be formed with a single stone, the stones shall be laid breaking joints and all interstices between adjacent stones shall be filled in with spalls of the proper size and wedged in with hammers to ensure tight packing.

When two or more layers of stones must be laid to obtain the design thickness of pitching, dry masonry shall be used and stones shall be well bonded. To ensure regular and orderly disposition of the full intended quantity of stone as shown, template cross walls in dry masonry shall be built about a metre wide and to the full height of the specified thickness at suitable intervals and all along the length and width of the pitching.

Within these walls the stones shall be hand packed as specified.

Toe Protection

In conformity with clause 5.3.7. of IRC:89, a toe wall shall be provided at the junction of slope pitching and launching apron of a guide bund so as to protect the slope pitching from galling even when the apron is not laid at low water level. The toe wall shall be in dry rubble masonry (uncoursed) conforming to Clause 1405.3 in case of dry rubble pitching or pitching / revetment with stones in wire crates and in nominal mix cement concrete (M 15) conforming to Clause 1704.3 in case cement concrete blocks have been used in pitching. For protection of toes of bank slopes terminating either in short aprons at bed levels or anchored in flooring / rocky bed, the provisions of clause 8.2.2 of IRC:89 may be complied with. The relevant specifications of the protective works for individual components will be followed.

TESTS AND STANDARDS OF ACCEPTANCE

The materials shall be tested in accordance with these Specifications and shall meet the prescribed criteria.

The work shall conform to these Specifications and shall meet the prescribed standards of acceptance.

MEASUREMENTS FOR PAYMENT

The protection works shall be measured as set forth below. If directed by the Engineer for measurement, the materials may have to be stacked at site before laying and nothing extra will be paid to the Contractor for this stacking.

The filter underneath stone pitching shall be measured separately in **cubic** metres unless otherwise specified.

Preparation of base for laying the flooring shall be deemed incidental to the work.

RATE

The contract unit rate for one **cubic meter** of filter material underneath stone pitching on slopes shall include the cost of preparing the bases, putting to the profiles, laying and compacting the filter and stone pitching of dry rubble/cement concrete block revetment for embankment slopes to the specified thickness, lines, curves, slopes and levels and all labour and materials as well as tools and plant required for the work.

The contract unit rate for filter material underneath stone pitching shall include the cost of all material, labour and tools and plant for completing the work as per these specifications.

Item No. 49 : Providing and casting in situ ordinary cement concrete M-150 mix and providing necessary pin headers including shuttering, scaffolding, laying, vibrating, curing and finishing complete.

The work shall be executed as per specification of **Item No. 20** except the work is for **providing and casting in situ ordinary cement concrete M-150 mix and providing necessary pin headers including shuttering, scaffolding, laying, vibrating, curing and finishing complete.**

Measurement shall be taken and paid on Cum basis.

Item No. 50 : Providing and casting in situ ordinary cement concrete M-250 for R.C.C. raft and cut-off walls including necessary shuttering, laying, vibrating, ramming and curing complete.

The work shall be executed as per specification of **Item No. 20** except the work is for **providing and casting in situ ordinary cement concrete M-250 for R.C.C. raft and cut-off walls including necessary shuttering, laying, vibrating, ramming and curing complete.**

Measurement shall be taken and paid on Cum basis.

Item No. 51 : Providing and casting in situ controlled cement concrete M-250 for R.C.C. return as per drawings including centering, shuttering, scaffolding wherever necessary laying, vibrating, curing and finishing complete. (A) Height from 0.0 mt. to 5.0 mt. (1) Piers (2) Abutment (3) R.C.C. returns.

The work shall be executed as per specification of **Item No. 33** except the work is for **providing and casting in situ controlled cement concrete M-250 for R.C.C. return as per drawings including centering, shuttering, scaffolding wherever necessary laying, vibrating, curing and finishing complete. (A) Height from 0.0 mt. to 5.0 mt. (1) Piers (2) Abutment (3) R.C.C. returns.**

Measurement shall be taken and paid on Cum basis.

Item No. 52 : Providing and casting in situ controlled cement concrete M-250 for R.C.C. works in pier cap, abutment cap and dirt wall including controlled cement concrete M-300 bed block or pedestal of required size below bearing as per detailed drawing, centering, shuttering, scaffolding wherever necessary laying, vibrating, curing and finishing complete.

The work shall be executed as per specification of **Item No. 33** except the work is for **providing and casting in situ controlled cement concrete M-250 for R.C.C. works in pier cap, abutment cap and dirt wall including controlled cement concrete M-300 bed block or pedestal of required size below bearing as per detailed drawing, centering, shuttering, scaffolding wherever necessary laying, vibrating, curing and finishing complete..**

Measurement shall be taken and paid on Cum basis.

Item No. 53 : Providing and casting in situ controlled cement concrete M-250 for R.C.C. solid slab including centering, scaffolding, curing and finishing complete.

The work shall be executed as per specification of **Item No. 33** except the work is for **providing and casting in situ controlled cement concrete M-250 for R.C.C. solid slab including centering, scaffolding, curing and finishing complete.**

Measurement shall be taken and paid on Cum basis.

Item No. 54 :- Providing P.V.C. 100mm diameter water spout including necessary iron grating as per drawings.

2705 DRAINAGE SPOUTS

Drainage along longitudinal direction shall be ensured by sufficient number of drainage fixtures embedded in the deck slab. The spouts shall be of not less than 100 mm in diameter and shall be of corrosive resistant material such as galvanised steel with suitable cleanout fixtures. The spacing of drainage spouts shall not exceed 10 m. The discharge from drainage spout shall be kept away from the deck structure by means of suitable down pipes upto 500 mm above High Flood Level. In case of viaducts in urban areas, the drainage spouts should be connected with suitably located runners and down pipes to discharge the surface run-off into drains provided at ground level.

2705.1 Fabrication

The drainage assembly shall be fabricated to the dimensions shown on the drawings. All materials shall be corrosion resistant. Steel components shall be of mild steel conforming to IS:226. The drainage assembly shall be seam welded for water tightness and then hot-dip galvanised.

2705.2 Placement

The galvanised assembly shall be given two coats of bituminous paint before placement. The whole assembly shall be placed in true position, lines and levels as shown on the drawings with necessary cutouts in the shuttering for deck slab and held in place firmly. Where the reinforcements of the deck are required to be cut, equivalent reinforcements shall be placed at the corners of the cut out.

2705.3 Finishing

After setting of the deck slab concrete, the shrinkage cracks around the assembly shall be sealed with polysulphide sealant or bituminous sealant as per 18:1834 and the excess sealant trimmed to receive the wearing coat. After the wearing coat is completed, similar sealant shall be provided to cover at least 50 mm on the wearing coat surface all round the drainage assembly.

2708 MEASUREMENTS FOR PAYMENT

Drainage / water spouts shall be measured in **numbers**.

2709 RATE

The contract unit rate for drainage spout shall include the cost of all labour, material, tools and plant required for completing the work as per these specifications. It shall also include the cost of providing runners and down pipes with all fixtures upto 500 mm above high flood level or up to the drains at ground, as applicable or as shown on the drawings.

Item No. 55 :- Providing and fixing in position mild steel dowel bars (I.S.I. mark) in pier caps or abutments caps for anchorage in fixed end as per detailed drawing including cutting, bending and welding complete.

1. For Mild Steel, specifications for M.S. reinforcement as per **Item No. 8** shall be apply.
2. The I.S.I. Mark M.S. dowel bars shall be provided and anchored in pier caps / abutment caps for anchorage as per detailed drawings for fixed ends. G.I. Pipes and other materials such as mastic asphalt as directed by Engineer-in-charge or as per drawing shall be provided G.I. pipes shall as approved by Engineer-in-charge.
3. The payment shall be made per **number** of dowel bars in anchored condition.
4. Unit rate shall include cost of all materials, labour and equipments to complete the Job.

Item No. 56 :- Providing and fixing in position mild steel dowel bars (I.S.I. mark) in pier caps or abutments caps for anchorage in free end as per detailed drawing including cutting, bending and welding complete.

1. For Mild Steel, specifications for M.S. reinforcement as per **Item No. 8** shall be apply.
2. The I.S.I. Mark M.S. dowel bars shall be provided and anchored in pier caps / abutment caps and for anchorage as per detailed drawings for free ends. G.I. Pipes and other materials such as mastic asphalt as directed by Engineer-in-charge or as per drawing shall be provided G.I. pipes shall as approved by Engineer-in-charge.
3. The payment shall be made per **number** of dowel bars in anchored condition.
4. Unit rate shall include cost of all materials, labour and equipments to complete the Job.

Item No. 57 :- Reinforced cement concrete crash barrier (Provision of an Reinforced cement concrete crash barrier at the edges of the road, approaches to bridge structures and medians, constructed with M-400 grade concrete with TMT Corrosive Reinforcement Steel (CRS) conforming to IRC:21 and dowel bars 25 mm dia., 450 mm long at expansion joints filled with pre-moulded asphalt filler board, keyed to the structure on which it is built and installed as per design given in the enclosure to MOST circular No. RW/NH - 33022/1/ 94-DO III dated 24 June 1994 as per dimensions in the approved drawing and at locations directed by the Engineer, all as specified).

809. CONCRETE CRASH BARRIERS

809.1. General

809.1.1. This work shall consist of construction, provision and installation of concrete crash barrier at the edges of the road and median at locations and of dimensions as shown on the drawings or as directed by the Engineer.

809.1.2. Concrete barrier shall generally be located on approaches to bridge structures, at locations where the embankment height is more than 3 metres and at horizontal curves.

809.2. Materials

809.2.1. All materials shall conform to Section 1000 Materials for Structures as applicable and relevant clauses in Section 1600 shall govern the steel reinforcement. The concrete barriers shall be constructed either by the “cast-in-place with fixed forms” method or the “extrusion or slip form” method or a combination thereof at the contractor’s option with the approval of the Engineer. Where “extrusion or slip form” method is adopted, full details of the method and literature shall be furnished.

809.2.2. Concrete barriers shall be constructed with M-40 grade concrete and with Fe-TMT Corrosive Reinforcement Steel (CRS) conforming to IRC:21. The friction slab shall be cast in situ with crash barrier. The grade of concrete of friction slab shall be in M-40. The capping beam also in M-40 which is cast after Retaining wall fascia panel achieved desired height and desired longitudinal gradient.

809.2.3. An expansion joint with pre-moulded asphalt filler board shall be provided at the junction of crash barrier on structure and crash barrier on the fill. The crash barrier on the fill shall be constructed in pieces of length not exceeding 20 m, with pre-moulded asphalt filler board joints.

809.3. Construction Operations

809.3.1. The location of crash barrier shall be strictly adhered to as shown on the drawing and as directed by the Engineer. Concrete crash barriers shall present a smooth, uniform appearance in their final position, conforming to the horizontal and vertical lines shown on the plans or as ordered by the Engineer and shall be free of lumps, sags or other irregularities. The top and exposed faces of the barriers shall conform to the specified tolerances, as defined in Clause 809.4 when tested with 3 m straight edge, laid on the surface.

809.3.2. When concrete barriers are to be constructed on recently completed bridges, the height of the barriers shall be adjusted to compensate for the camber and dead load deflection of the superstructure. The amount of adjustment shall be determined by the Engineer and shall be ordered before the concrete is placed. Such barriers shall be placed after formwork has been released and as long after the superstructure construction as possible without hampering the progress of the work.

809.3.3 Back filling to the concrete barriers shall be compacted in layers to the compaction of the surrounding earthwork.

809.4. Tolerance - The overall horizontal alignment of rails shall not depart from the road alignment by more than ± 30 mm, nor deviate in any two successive lengths from straight by more than 6 mm and the faces shall not vary more than 12 mm from the edge of a 3 m straight edge. Barriers shall be at the specified height as shown in the plans above the edge of the nearest adjacent carriageway or shoulder, within a tolerance of ± 30 mm.

The reinforced cement concrete crash barrier at the edges of the road, approaches to bridge structures and medians, constructed with M-400 grade concrete with TMT Corrosive Reinforcement Steel (CRS) conforming to IRC:21 and dowel bars 25 mm dia., 450 mm long at expansion joints filled with pre-moulded asphalt filler board, keyed to the structure on which it is built and installed as per design given in the enclosure to MOST circular No. RW/NH - 33022/1/94-DO III dated 24 June 1994 as per dimensions in the approved drawing and at locations directed by the Engineer in charge.

809.5. Measurements for Payment

All barriers will be measured by linear metres of completed and accepted length in place, corresponding end to end along the face of concrete barriers including approach and departure ends.

809.6. Rate

The Contract unit rate shall include full compensation for furnishing all labour, tools, materials, equipment and incidental costs necessary for doing all work involved in constructing the concrete barrier complete in place in all respects as per these specifications.

The Rate shall be for unit of one **Running Meter**.

Item No. 58 :- Removal of NP2 - 900mm dia. pipe including stacking serviceable material on site of work as directed.

1. This work shall consist of removing of water supply fixtures like reinforced concrete heavy duty non pressure pipes of IS Class NP2 pipes of 900mm internal dia. etc. which are in place but interfere with the new construction or are not suitable to remain in place and of salvaging and disposing of the resulting materials and back filling the resulting trenches and pits.
2. Existing pipe of any dia. to wall, ceiling, floor which are within the C.D. works and which are designed to be removed shall be removed upto the limits and extent specified in the drawings or as indicated by the Engineer-in-charge.
3. Dismantling and removal operations shall be carried out with equipment and in such a manner as to leave undisturbed, adjacent pavement, C.D. works and any other work to be left in place.
4. All operations necessary for the removal of any existing C.D. works which might endanger new construction shall be completed prior to the start of new work.
5. The pipe of any dia., pipe, valve and water tank shall be dismantled carefully and the resulting materials so removed as not to cause any damage to the serviceable materials to be salvaged, the part of the C.D. works to be retained and any other properties.
6. Unless otherwise specified, the superstructure portion of C.D. works shall be entirely removed and other parts removed to below the ground level or as necessary depending upon the interference they cause to the new construction. Removal of overlying or adjacent materials if required in connection with the dismantling of the C.D. works shall be incidental to this item.
7. The payment shall be made on **Running meter** basis.

Item No. 59 :- Supplying and fixing reinforced concrete heavy duty non-pressure pipes with collars for culverts including setting and joining the pipes in C.M. 1:2 watering and laying (to level or slopes) of I.S. class NP-4 of 1200mm internal diameter.

The work shall be executed as per specification of **Item No. 9** except the work is for **supplying and fixing reinforced concrete heavy duty non-pressure pipes with collars for culverts including setting and joining the pipes in C.M. 1:2 watering and laying (to level or slopes) of I.S. class NP-4 of 1200mm internal diameter.**

Measurement shall be taken and paid on Rmt. basis.

Item No. 60 :- Providing, laying and rolling 25 mm thick open graded premixed bituminous carpet with B.T. aggregate as specified and using bitumen (VG-30) for mixing with aggregate at the rate of 3.36% i.e. 33.60 kg/M.T. of total mix including heating and mixing in drum mix plant and spreading the same with paver finisher and consolidation with vibratory roller as per MORTH specification including necessary firewood, oil, lubricants, labour charges etc. using contractor's own drum mix plant and equipment, tools etc. completed in accordance with the requirement of specification.

511.1 Open-graded Premix Surfacing using viscosity bitumen or Cutback.

511.1.1 Scope: This work shall consist of the preparation, laying and compaction of an open graded premix surfacing material of **25 mm thickness** composed of small sized aggregate premixed with a bituminous binder on a previously prepared base, in accordance with the requirements of these specifications, to serve as a wearing course.

511.1.2 Materials

511.1.2.1 Binder :- The binder shall be a bitumen of a suitable viscosity grade as specified in the Contract or as directed by the Engineer, and satisfying the requirements of IS:73.

Viscosity Grade (VG) Bitumen Specification as per IS 73 : 2013

Characteristics	VG - 10	VG-20	VG-30	VG-40
Absolute Viscosity 60°C, poises, min	800	1600	2400	3200
Kinematic Viscosity 135°C CSI, min	250	300	350	400
Flash point, C, min	220	220	220	220
Solubility in trichloroethylene, % min	99.0	99.0	99.0	99.0
Penetration at 25°C	80-100	60-80	50-70	40-60
Softening point, C min	40	45	47	50
Test on residue from thin film oven test / RTFOT :				
(A) Viscosity ration at 60°C, max	4.0	4.0	4.0	4.0
(B) Ductility at 25°C, cm, min after thin film over test	75	50	40	25

511.1.2.2 Aggregate - The aggregate shall conform to Clause 504.2.2 except that the water absorption shall be limited to a maximum of 1 percent. The Polished Stone Value, as measured by the test in BS 812-(Part 114), shall not be less than 55.

511.1.2.3 Proportioning of materials :- The materials shall be proportioned in accordance with Table 500-23.

511.1.3 Construction operations

511.1.3 Weather and seasonal limitations - Clause 501.5.1 shall apply.

511.1.3.2 Preparation of surface - The under lying surface on which the bituminous surfacing is to be laid shall be prepared, shaped and conditioned to the specified lines, grade and cross-section in accordance with Clause 501. A prime coat where needed shall be applied in accordance with Clause 502 as directed by the Engineer.

TABLE 500-23.

QUANTITIES OF MATERIALS REQUIRED FOR 10 M² OF ROAD SURFACE FOR 20 MM THICK OPEN GRADED PREMIX SURFACING USING VISCOSITY BITUMEN OR CUTBACK

Aggregates		
a.	Nominal Stone size 13.2 mm (passing 22.4 mm sieve and retained on 11.2 mm sieve)	0.18 m ³
b.	Nominal Stone size 11.2 mm (passing 13.2 mm sieve and retained on 5.6 mm sieve)	0.09 m ³
	Total	0.27 m³
Binder (quantities in terms of straight run bitumen)		
a.	For 0.18 m ³ of 13.2 mm nominal size stone at 52 kg bitumen per m ³	9.5 kg
b.	For 0.09 m ³ of 11.2 mm nominal size stone at 56 kg bitumen per m ³	5.1 kg
	Total	14.6 kg

511.1.3.3 Tack coat - A tack coat complying with Clause 503, shall be applied over the base preparatory to laying of the surfacing.

511.1.3.4 Preparation of premix :- Drum mix plant of appropriate capacity and type shall be used for the preparation of the mix material. The drum mix plant shall have separate dryer arrangement for heating aggregate.

The temperature of the binder at the time of mixing shall be in the range of 150°C to 163°C and that of the aggregate in the range of 155°C to 163°C provided that the difference in temperature between the binder and aggregate at no time exceeds 14°C. Mixing shall be thorough to ensure that a homogeneous mixture is obtained in which all particles of the aggregates are coated uniformly and the discharge temperature of mix shall be between 130°C and 160°C.

The mix shall be immediately transported from the mixer to the point of use in suitable vehicles or hand barrows. The vehicles employed for transport shall be clean and the mix being transported covered in transit if so directed by the Engineer.

511.1.3.5 Spreading and rolling - The pre mixed material shall be spread by suitable means to the desired thickness, grades and cross-fall (camber) making due allowance for any extra quantity required to fill up depressions, if any. The cross-fall should be checked by means of camber boards and irregularities leveled out. Excessive use of blades or rakes should be avoided. As soon as sufficient length of bituminous material has been laid, rolling shall commence with 8-10 tonne rollers, smooth wheel tandem type, or other approved equipment. Rolling shall begin at the edge and progress towards the centre longitudinally, except that on superelevated and uni-directional cambered portions, it shall progress from the lower to upper edge parallel to the centre line of the pavement.

When the roller has passed over the whole area once, any high spots or depressions, which become apparent, shall be corrected by removing or adding premixed materials. Rolling shall then be continued until the entire surface has been rolled and all the roller marks eliminated. In each pass of the roller the preceding track shall be overlapped uniformly by at least 1/3 width. The roller wheels shall be kept damp to prevent the premix from adhering to the wheels.

In no case shall fuel/lubricating oil be used for this purpose. Excess use of water for this purpose shall also be avoided.

Rollers shall not stand on newly laid material. Rolling operations shall be completed in every respect before the temperature of the mix falls below 100°C. Joints along and transverse to the surfacing laid and compacted earlier shall be cut vertically to their full depth so as to expose fresh surface which shall be painted with a thin coat of appropriate binder before the new mix is placed against it.

511.1.3.6 Seal coat - A seal coat conforming to Clause 513 of the type specified in the Contract shall be applied to the surface immediately after laying the surfacing.

511.1.4 Opening to traffic - No traffic shall be allowed on the road until the seal coat has been laid. After the seal coat is laid, the road may be opened to traffic according to Clause 513.4.

511.1.5 Surface finish and quality control of work - The surface finish of construction shall conform to the requirements of Clause 902. For control of the quality of materials supplied and the works carried out, the relevant provisions of Section 900 shall apply.

511.1.6 Arrangements for traffic - During the period of construction, arrangement of traffic shall be made in accordance with the provisions of Clause 112.

511.1.7 Measurement for payment - Open graded premix surfacing shall be measured as finished work, for the area instructed to be covered, in **M.T.** The area will be the net area covered, and all allowance for wastage and cutting of joints shall be deemed to be included in the rate.

511.1.8 Rate - The contract unit rate for open graded premix surfacing shall be payment in full for carrying out the required operations including full compensation for all components listed in Clause 501.8.8.2. (i) to (xi).

511.2 Open graded premix surfacing using cationic bitumen emulsion

511.2.1 Scope: This work shall consist of the preparation, laying and compaction of an open graded premix surfacing of 25 mm thickness composed of small sized aggregate premixed with a cationic bitumen emulsion on a previously prepared surface, in accordance with the requirements of these specifications, to serve as a wearing course.

511.2.2 Materials

511.2.2.1 Binder - The binder for premix wearing course shall be cationic bitumen emulsion of Medium Setting (MS) grade complying with I.S.8887 and having a bitumen content 65 percent minimum by weight. For liquid seal coat RS grade of Cationic bitumen emulsion shall be used. Where expressly specified in the Contract MS grade emulsion shall be used or otherwise directed by the Engineer. Slow Setting (SS) grade Cationic bitumen Emulsion shall be used for premix seal coat.

511.2.2.2 Aggregate: The requirements of Clause 511.1.2.2 shall apply.

511.2.3 Proportioning of materials

The materials shall be proportioned as quantities given in Tables 500-24 and 500-25.

TABLE 500-24. QUANTITIES OF AGGREGATE FOR 10 M² AREA

A)	Premix Carpet:	
a.	Coarse aggregate nominal 13.2 mm size; passing IS 22.4 mm sieve and retained on IS 11.2 mm sieve	0.18 m ³
b.	Coarse aggregate nominal 11.2 mm size; passing IS: 13.2 mm sieve and retained on IS 5.6 mm sieve	0.09 m ³
B.	For seal coat: Refer to clause 500.13	

TABLE 500-25. QUANTITIES OF EMULSION BINDER

		For 10 m² area
A)	For Premix Carpet	20 to 23 kg
B)	For Seal Coat:	
a.	For liquid seal coat	12 to 14 kg
b.	For premix seal coat	10 to 12 kg

511.2.4 Construction operations

511.2.4.1 Weather and seasonal limitations - Clause 501.5.1 shall apply except that the minimum air temperature for laying shall be 10°C. Cationic bitumen emulsions shall not normally be stored below 0°C

511.2.4.2 Preparation of surface - The underlying surface on which the premix surfacing is to be laid shall be prepared, in accordance with the requirements of Clause 504.3.2 for a newly primed surface and in accordance with Clause 507.4.2 where an existing bituminous surface is to be overlaid.

511.2.4.3 Preparation of binder - Before opening, the cationic bitumen emulsion drums shall be rolled at slow speed, to and fro, at least 5 times, for a distance of about 10 metres, to distribute any storage sedimentation.

~~**511.2.4.4. Tack coat:** A tack coat complying with Clause 503, shall be applied over the surface preparatory to laying of the surfacing where specified in the Contract, or directed by the Engineer.~~

511.2.4.5. Preparation of premix - Premixing of cationic bitumen emulsion and aggregates can be carried out in a suitable mixer such as cold mixing plant as per IS: 5435 (revised) or concrete mixer or by pay loaders in

exceptional cases where approved by the Engineer. Where specified in the contract continuous mixing operation shall be done either in batch or continuous drum mix plant suitable for emulsion mixes.

When using concrete mixer for preparing the premix, 0.135 cu.m (0.09 cu.m of 13.2 mm size and 0.045 cu.m of 11.2 mm. size) of aggregates per batch shall be used which quantity will cover 5 sq.m of road surface with 20 mm average thickness.

The aggregates required for one batch should be prepared adjacent to the mixer.

First the coarse aggregate of 13.2 mm size shall be placed into the mixer followed by 5 to 6.5 kg of cationic bitumen emulsion and then the 11.2 mm size aggregate shall be added, followed by 5 to 6.5 kg of cationic bitumen emulsion. After the materials have been mixed thoroughly, the mix shall be immediately transported to the laying site in suitable vehicles. Too much mixing shall be avoided.

When mixed manually by shovels, with the approval of the Engineer, 0.06 cum. of aggregates can be conveniently mixed in one heap, with appropriate quantity of emulsion. It is preferable to make the aggregates damp before mixing as it reduces the effort required for mixing and also helps to get better coating of aggregates. The 13.2 mm size aggregates and emulsion are mixed first and then the 11.2 mm size aggregates and remaining quantity of emulsion are added and mixed. Too much mixing shall be avoided.

511.2.4.6 Spreading and rolling: The premixed cationic bitumen emulsion and aggregates shall be spread within 10 minutes of applying the tack coat. All levelling, raking, etc. should be completed within 20 minutes of the time of mixing.

The mix should be spread uniformly to the desired thickness, grades and crossfall (camber) making due allowance for any extra quantity required to fill up depressions, if any. The cross fall should be checked by means of camber boards and irregularities leveled out. Too much raking is to be avoided.

The rolling shall start immediately after laying the premix. A smooth wheeled tandem roller of 8-10 tonnes shall be used, unless the Engineer, based on the results of laying trials approves other compaction methods, if necessary. While rolling, wheels of roller should be clean and kept moist to prevent the premix from adhering to the wheels. In no case shall fuel/lubricating oil be used for this purpose. Use of water for this purpose shall be strictly limited to an absolute minimum.

Rolling shall commence at the edges and progress towards the centre longitudinally except in the case of superelevated and uni-directional cambered sections where rolling shall be carried out from the lower edge towards the higher edge parallel to the centre line of the road.

After one pass of roller over the whole area, depressions or uncovered spots should be corrected by adding premix material. Rolling shall be continued until the entire surface has been rolled to maximum compaction and all the roller marks eliminated. In each pass of the roller the preceding track shall be overlapped uniformly by at least 1/3 width. Roller(s) shall not stand on newly laid material. Joints both longitudinal and transverse to the road sections laid and compacted earlier, shall be cut vertically to their full depth so as to expose fresh surface which shall be painted with a thin surface coat of binder before the new mix is placed against it.

511.2.4.7 Seal coat: A seal coat, conforming to Clause 510 or Clause 513, as specified in the Contract, shall be applied 4 to 6 hours after laying the premix carpet.

511.2.5 Opening to traffic: Traffic should not be allowed over the premix surface with or without seal coat, for 6 to 8 hours after rolling. In case of single lane roads, traffic shall be allowed onto the surface once it has reached ambient temperature, but speed must be rigorously restricted to not more than 16 km per hour. If any premix material is picked up by vehicle tyres, the spot shall be filled up by new mix. If traffic conditions permit, the road shall not be opened until a full 24 hours after laying.

511.2.6 Surface finish and quality control: The surface finish of construction shall conform to the requirements of Clause 902.

For control of the quality of materials supplied and the works carried out, the relevant provisions of Section 900 shall apply.

511.2.7 Arrangements for traffic: During the period of construction, arrangements for traffic shall be made in accordance with the provisions of Clause 112.

511.2.8 Measurement for payment:

Open graded premix carpet shall be measured as finished work, for the area specified to be covered, in square metres at the specified thickness, in cubic metres or in **tonnes** weight as specified in the contract. The area will be the net area covered, and all allowances for wastage and cutting of joints shall be deemed to be included in the rate.

511.2.9 Rate:

The contract unit rate for premix carpet and seal coat shall be payment in full for carrying out the required operations including full compensation for all components listed below :

- (i) Making arrangements for traffic to Clause 112 except for initial treatment to verge, shoulders and construction of diversion;
- (ii) Preparation of the surface to receive the material.
- (iii) Providing all materials to be incorporated in the work including arrangement for stock yards, all royalties, fees, rents where necessary and all leads and lifts;
- (iv) Mixing, transporting, laying and compacting the mix, as specified.
- (v) All labour, tools, equipment, plant including installation of drum mix plant, power supply units and all machinery, incidental to complete the work to these Specifications;
- (vi) Carrying out the work in part width of the road where directed;
- (vii) Carrying out all tests for control of quality and
- (viii) The rate shall cover the provision of bitumen at the rate specified in the contract, with the provision that the variation in actual percentage of bitumen used will be assessed and the payment adjusted accordingly.
- (ix) The rates for premixed material are to include for all wastage in cutting of joints etc.
- (x) The rates are to include for all necessary testing, mix design, transporting and testing of samples, and cores. If there is not a project specific laboratory, the Contractor must arrange to carry out all necessary testing at an outside Laboratory, approved by the Engineer, and all costs incurred are deemed to be included in the rate quoted for the material.
- (xi) The cost of all plant and laying trials as specified to prove the mixing and laying methods is deemed to be included in the Contractor's rates for the material.

Bitumen quantities are to be as stated in Table 500-23 for premix, 13 kg per 10 sq.m. for liquid seal coat and 11 kg per 10 sq.m. for premix seal coat. The rate will be adjusted according to actual material used.

Item No. 61 :- Providing and laying seal coat with B.T. aggregate as specified using aggregate at the rate of 0.18 cum/10 Sqmt and bitumen grade (VG-30) for mixing with aggregate at the rate of 4.50% i.e. 45.00 kg/M.T. of total mix including heating and mixing in drum mix plant, spreading the same with paver finisher and consolidation with vibratory roller including necessary firewood, oil, lubricants, labour charges etc. using contractor's own drum mix plant and equipment, tools etc. complete in accordance with the requirement of specification.

1. DESCRIPTION

The work shall consist of construction of premix seal coat as wearing course on a previously prepared base to the requirement of these specification.

2. MATERIALS

2.1 Binder: The binder shall be straight run bitumen of viscosity grade **VG-30** satisfying the requirement of IS:73. The actual grade of the binder to be used shall be decided by the Engineer-in-charge and it shall have to be brought by contractor to the site at his own cost unless otherwise specified in schedule 'A'.

Viscosity Grade (VG) Bitumen Specification as per IS 73 : 2013

Characteristics	VG - 10	VG-20	VG-30	VG-40
Absolute Viscosity 60°C, poises, min	800	1600	2400	3200
Kinematic Viscosity 135°C CSI, min	250	300	350	400
Flash point, C, min	220	220	220	220
Solubility in trichloroethylene, % min	99.0	99.0	99.0	99.0
Penetration at 25°C	80-100	60-80	50-70	40-60
Softening point, C min	40	45	47	50
Test on residue from thin film oven test / RTFOT :				
(A) Viscosity ration at 60°C, max	4.0	4.0	4.0	4.0
(B) Ductility at 25°C, cm, min after thin film over test	75	50	40	25

2.2 Coarse aggregates: The coarse aggregate shall consist of crushed stone or crushed gravel.

These shall be clean, durable, of cubical shape, free disintegrated pieces, organic or other deleterious matter and adherent coatings. The aggregates shall preferably be hydrophobic and of low porosity and shall satisfy the physical requirements set forth in Table given in Item No. 18 Para 2. Except that the upper limit for water absorption value shall be one percent.

2.3 Fine aggregates; The fine aggregates shall consist of crusher run screenings, natural sand or a mixture of both. These shall be clean, hard, durable, uncoated, dry and free from injurious, soft or flaky pieces and organic or deleterious substances.

2-4 Filter: The filler, where required, shall be an insert material the whole of which passes 600 micron sieve at least 90 percent passing 150 micron sieve and not less than 70 percent passing 75 micron sieve. The filler shall be cement, stone dust, hydrated lime, fly ash and other non-plastic mineral matter approved by the Engineer-in-charge.

2.5 Aggregate gradation : The mineral aggregates, including mineral filler shall be so graded or combined as to conform to gradings set forth in tables below:

Table : Aggregate gradation Pre-Mix Seal Coat

Sieve Designation	Percentage by wt passing through Sieve	
	For type 'A'	For Type 'B'
12.5 mm	-	100
10 mm	100	70-100
4.75 mm	40-85	20-40

2.35	5-20	5-20
75micron	0 - 4	0 - 4

2.6 Proportioning of materials : The binder content for premixing shall be 45.00 kg per M.T. (4.5% by weight) for mixing aggregate.

The quantities of aggregates shall be sufficient to yield the specified thickness after compaction. The contractor shall get the job-'mix formula for the mix approved by the Engineer-in-charge before starting the work.

2.7 Variation in Proportioning of material : The Contractor shall have the responsibility of ensuring proper proportioning of materials in accordance with the approved job mix formula and producing a uniform mix. A variation in binder content of ± 0.3 percent by weight of total mix shall, however be permissible in individual specimen taken for quality control tests vide MOST Specification Section 900.

3. CONSTRUCTION OPERATIONS

3.1 Weather and seasonal limitation : Premix seal coat shall not be laid during rainy weather or when the base course is damp or wet.

3.2 Preparation of base : The base on which premix seal coat is to be laid shall be prepared shaped and conditioned to the specified, lines, grade and cross section in accordance with MOST Specification Clause 601 as directed by the Engineer-in-charge. The surface shall be thoroughly swept" and scraped clean and free of dust and foreign matter.

3.3 Tack coat (if applied) : Application of binder : Binder shall be rapid setting emulsion shall be used and approved by the Engineer-in-charge and sprayed on the base at the rate specified hereafter. The rate of spread in terms of straight run emulsion shall be 2.5 kg per 10 square metre area for an existing bitumen treated surface. The binder shall be applied uniformly with the aid of sprayers. The tack coat shall be applied just ahead of the oncoming bituminous construction.

3.4 Preparation of the mix : Drum mix plant of adequate capacity and capable of producing a proper and uniform quality shall be used for preparing the mix. The plant should be continuous type having a co-ordinated set of essential units such as dryer for heating the aggregates, device for feeding by weight or volume the required quantities of aggregates, a binder heating and control unit for metering out the correct quantity of heated binder together with a paddle mixer for intimately mixing of the binder and aggregates. For details regarding Drum mix plant the Annexure 'A' may be referred.

The temperature of-binder at the time of mixing shall be in the range of 150° C - 177° C and aggregates in the range of 150° C -163° C provided also that at no time shall the difference in temperature of the aggregates and the binder exceed 14° C.

Mixing shall be throughout to ensure that a homogeneous mixture is obtained in which all the particles of the mineral aggregates are coated uniformly.

The mix shall be transported from the mixing .plant to the point of use in suitable vehicles. The vehicles employed for transport shall be clean and be covered over in the transit if so directed by the Engineer-in-charge.

3.5 Spreading : The mix, transported from the drum mix plant to the site, shall be spread by means of self propelled mechanical paver with suitable screens capable of spreading, tamping and finishing the mix, true to specified grade, line and cross sections. The temperature of mix at the time of laying shall be in the range of 121° C -163°C.

Longitudinal joints and edges shall be constructed true to the delineating lines parallel to the centre line of the road. Longitudinal joints shall be offset by at least 150 mm from those in the binder course. All joints

shall be cut vertical to the full thickness of the previously laid mix and the surface painted with hot bitumen before placing fresh material.

3.6 Rolling : Immediately after the spreading of mix, it shall be thoroughly compacted by rolling with a set of rollers moving at a speed not exceeding 5 km per hour. The initial or break-down rolling shall be with 8-12 tonne three wheeled rollers and the surface finished by final rolling with vibratory rollers or suitable pneumatic rollers. Rolling temperature shall not be less than 100°C in any case the rolling shall be completed the temperature of mix falls about 80° C.

The roller wheels shall be kept damp to prevent the mix adhering to them but in no case shall fuel lubricating oil be used for this purpose. Rolling shall commence longitudinally from the edge and progress towards the centre except that at super elevated portions, it shall progress from the lower to upper edges parallel to the centre line of the payment. The roller should proceed on the fresh material with rear or fixed wheel leading so as to minimize the pushing of the mix and each pass of the roller shall uniformly overlap not less than one third of the track made in the preceding pass Rolling shall continue until the entire surface has been rolled to compaction and all the roller marks eliminated.

4. OPENING TO TRAFFIC

Traffic may be allowed immediately after completion of the final rolling when the mix has cooled down to the surrounding temperature.

5. SURFACE FINISH AND QUALITY CONTROL OF WORK

The surface finish of construction shall conform to the requirements of most specification Clause 901. Control on the quality of material and works shall be exercised by the Engineer-in-charge in accordance with MOST Specification Clause 902.

6. ARRANGEMENT FOR TRAFFIC

The provision of MORTH Specification Clause 105 shall apply as regards the flow to traffic during construction.

7. MEASUREMENT FOR PAYMENT

The payment shall be made on the **tonnage basis** of the weight of mix of aggregates and bitumen. For this purpose the contractor shall have to install a weigh bridge of suitable capacity for the purpose of weighing of dumpers at suitable place at his cost as directed. Weight of empty dumper and weight of loaded dumper will be recorded in bound and numbered register on plant side.

Department will be free to get some loaded dumper test checked at other weigh bridge. Weigh bridge will be periodically got calibrated and verified from weight and measure authorities.

For the purpose of application of tack coat if the theoretical area as per sanctioned estimate for basis of tonne differs with the actual area of work done in the field, then the reduction in or addition to payment shall have to be effected to the contractor on proportionate basis depending upon the area reduced or exceeded respectively.

Weight of mix materials will be done in presence of responsible person, not less than the rank of supervisor of Department, Deputy Executive Engineer or Assistant Engineer or Addl. Assistant Engineer if so authorized.

Record of each dumper will be maintained separately in bound and numbered register which will be maintained by the departmental representatives and signed by the contractor. Proper gate pass system shall be established for the vehicles coming to the plant site and out going from the plant site. The location of the kilometer, hectometer in which individual dumper are unloaded will be recorded carefully.

8. RATE

The Contract unit rate for seal coat shall be for payment for carrying out the required operations including full compensation for all components listed in MORTH Specification Clause 503.7.

Item No. 62 :- Providing and laying evenly tack coat using rapid setting emulsion (RS-1) materials at the rate of 4.00 Kg / 10 Sq.M. on road surface using emulsion pressure sprayer including the cost of all labour, materials, heating, machinery & equipment etc. complete.

503 TACK COAT

503.1 Scope

This work shall consist of the application of a single coat of low viscosity liquid bituminous material to an existing bituminous, cement concrete or primed granular surface preparatory to the superimposition of a bituminous mix, when specified in the Contract or instructed by the Engineer. The work shall be carried out on a previously prepared surface in accordance with Clause 501.

503.2 Materials

503.2.1 Binder

The binder used for tack coat shall be Rapid Setting bitumen emulsion Grade RS-1 complying with IS:8887 or suitable low viscosity paving bitumen of VG-30 grade conforming to IS:73. The use of cutback bitumen (Medium Curing grade) as per IS:217 shall be restricted only for sites at sub-zero temperature or for emergency applications as directed by the Engineer. The type and grade of binder for tack coat shall be specified in the contract.

503.3 Weather and Seasonal Limitations

Bituminous material shall not be applied to a wet surface or during a dust storm or when the weather is foggy, rainy or windy or when the temperature in the shade is less than 10°C. Where the tack coat consists of emulsion, the surface shall be slightly damp, but not wet.

503.4 Construction

503.4.1 Equipment

The equipment used for tack coat shall be self-propelled or tractor towed bitumen pressure distributor equipped for spraying the material uniformly at a specified rate. Hand spraying of small areas, inaccessible to the distributor, or in narrow strips, shall be permitted with a pressure hand sprayer, or as directed by the Engineer.

503.4.2 Preparation of base

The surface on which the tack coat is to be applied shall be clean and free from dust, dirt, and any extraneous material, and be otherwise prepared in accordance with the requirements of Clause 501. Immediately before the application of the tack coat, the surface shall be swept clean with a mechanical broom, or by other means as directed by the Engineer.

503.4.3 Application of tack coat

The binder shall be sprayed on the base at the rate specified in Table 500.2. The normal range of spraying temperature for a bituminous emulsion shall be 20°C-70°C. Paving bitumen if used for tack coat shall be heated to an appropriate temperature in bitumen boilers to achieve viscosity less than 2 poise. The normal range of spraying temperature for a cutback shall be 50°C-80°C. It shall be the responsibility of the Contractor to carefully handle the inflammable bituminous cutback material so as to safeguard against any fire mishap. The binder shall be applied uniformly with the aid of either self-propelled tractor towed bitumen pressure distributor capable of spraying bitumen at specified rates and temperature so as to provide a uniformly unbroken spread of bitumen. Work should be planned so that no more than the necessary tack coat for the day's operation is placed on the surface. A spraying trial shall be carried out to demonstrate the efficacy of the equipment for uniformity of spread within specified tolerances.

Table 500.2 Rate of Application of Tack Coat

Type of Surface Emulsion		Rate of Spray of Binder
		(kg/m ²)
i	Normal bituminous surfaces	0.20 to 0.25
ii	Dry and hungry bituminous surfaces	0.25 to 0.30
iii	Granular surfaces treated with primer	0.25 to 0.30
iv	Cement Concrete Pavement	0.30 to 0.35

503.4.4 Curing of tack coat

The tack coat of emulsion shall be left to cure until all the volatiles have evaporated before any subsequent construction is started. No plant or vehicles other than essentially required for construction shall be allowed on the tack coat.

503.5 Quality Control of Work

For control of the quality of materials supplied and the works carried out the relevant provisions of Section 1800 shall apply.

503.6 Arrangements for Traffic

During the period of construction, arrangements for traffic shall be made in accordance with the provisions of Section 100.

503.7 Measurements for Payment

Tack coat shall be measured in terms of surface area of application **in square metres.**

503.8 Rate

The contract unit rate for tack coat shall be payment in full for carrying out the required operations including for all components listed in Clause 401.7 and as applicable to the work specified in these specifications.