



भारत सरकार
GOVT. OF INDIA
केन्द्रीय लोक निर्माण विभाग
CENTRAL PUBLIC WORKS DEPTT.



कार्यपालक अभियंता का कार्यालय/Office of the Executive Engineer(C)-I,
वडोदरा केन्द्रीय मंडल, डाक बंगला/Vadodara Central Division, Dak Bungalow,
फतेहगंज सर्कल, वडोदरा / Behind Post Office Fatehgunj, Vadodara-390 002
दूर भाष (0265)2784941, Fax-2787144, email : eevcd.cpwd@gov.in

No.67(1)/VCD/2026/599-1

Date:- 16/05/2026

NOTICE INVITING E- QUOTATIONS

The Executive Engineer(C)-I, CPWD, Vadodara invites on behalf of "The President of India" **Percentage rate sealed quotation** from NABL certified Testing Laboratories for the work noted below so as to reach to undersigned upto 03.00 PM on or before **25.05.2026**. The Quotations shall be opened on the same day at 3.30 PM in the presence of intending quotationers. The undersigned reserves the right of accepting or rejecting any or all of the quotations without assigning any reason thereof. The quotation can be seen and downloaded from website www.etender.gov.in or www.cpwd.gov.in free of cost or can be collected from this office on or before 25.05.2026 upto 1.00 pm.

NAME OF WORK:- Construction of school Building(G+1), Girls Hostel(G+2), Boys Hostel (G+2). Kitchen and Dining, Principal Quarter, Type-II Qtrs - 10 Nos (G+2), Type III Qtrs - 16 Nos (G+1), Warden Residence - 2 Nos, Compound Wall, Security room, Internal CC roads, Internal Water Supply, Sanitary Installation, Drainage, 2 Nos Bore well, UG sumps, Septic tank, Sport facilities and providing internal Electrical Installations, Street Lighting, Substation Equipment, DG sets & Fire Fighting System including Development and Bulk services for EMRS at Jhagadia, Village-Rupaniya, Dist-Bharuch (Gujarat).

SH:-Carrying out SOIL TESTING for Bearing Capacity of Soil.

Schedule of Quantity

Sr. No.	Item Serial No(s)	Description	Qty	Unit	Rate	Amount
1	M/R items	GEOTECHNICAL INVESTIGATION OF SOIL				
1.1	N.S -1	Mobilization Charges on account of transportation of Plants/ machinery, labourers and other materials at site of work to start the work and including demobilization of their withdrawal on completion of work for conducting Sub-Soil exploration.	1	job	30794	30794
1.2	N.S -2	Sub Soil investigation by Machine Drilling 100mm dia Bore-holes in all types of Soil and Rock strata, including collection of disturbed, Undisturbed soil sample, performing Classification of Soil. standard penetration test (SPT, as per IS 2131 & 2132) at 1.5m interval, performing various lab tests like triaxial test or direct shear test, liquid limit, plastic limit, plasticity index, grain size analysis, field density and moisture content, swelling pressure, free swell index, compression index, porosity, Water absorption, Specific Gravity, unconfined compressive strength test on collected soil/rock samples. (Soil Exploration for 11 Nos. Bore-holes to be carried out between 08 to 10 m depth of each Bore-holes).	110	Meter	3992	439120


	Remarks:- Whole job should also include the preparation and submission of detailed report (<u>In FIVE Copies</u>) on geotechnical investigation carried out along with the recommendation on <u>Type of foundation to be adopted.</u>				
		Total			4,69,914/-
		Rate to be quoted by Agency	____% Above/Below		
		Net amount			
Amount in Rupees					

List of Documents to be uploaded :

- 1) **Experience Certificate of conducting Soil Investigation works in CPWD**
(Copies of Minimum 3 Soil investigation works reports).
- 2) **GST registration Certificate.**

Terms & Condition:-

- 1) The work is to be carried out as per CPWD specifications and terms and condition and shall be followed as per annexure attached and as directed by Engineer-in-charge.
- 2) Payment will be made through PFMS.
- 3) Time for completion for the work is **20 days** which shall be reckoned from the date of issue of this work order.
- 4) No T & P and any other accessories will be supplied by the department.
- 5) The rates will be net and nothing extra shall be paid.
- 6) **Five (05)** No. copies of Soil Investigation Report are to be submitted alongwith the soft copy.
- 7) The Lab should be accredited with NABL.
- 8) Site shall be cleaned after completing the work.
- 9) The above Geo-Technical investigation i.e. Sub-Soil exploration to ascertain SBC and other engineering properties including preparing and submitting detailed report.
- 10) The location of point for borehole for soil testing to be decided by Engineer-in-charge.
- 11) Payment shall be made as first and final bill. No intermediate payment shall be made.
- 12) The Engineer-in-charge reserves the right to accept in full or in part or reject any bid and to annul the process and reject all bids at any time without assigning any reason or incurring any liability to the bidders. This notice may also be seen at website www.etender.cpwd.gov.in.


Executive Engineer(C)-I,
CPWD, Vadodara

- Copy to :-
- 1) The Superintending Engineer, CPWD, Vadodara
 - 2) to 5) All Assistant Engineer's under this Division.
 - 6) The Local contractors/Agencies
 - 7) Notice Board.
 - 8) e-tender website


Executive Engineer(C)-I