

BILL OF QUANTITIES

(A) Percentage Rate Tender (Up to INR 50 Cr.)

Name Of Work :		Constructing R.C.C. Box Culvert Near Survey No/ Block NO-1107, 1234 & 1235 (Old Survey No/ Block NO- 884/2/among 1) on 1L Bifercation 1L Sub Minor Of Chanvai Distry near Ch. 950.0 mt.					
:: Schedule B ::							
Item No.	Quantities estimated but may be more or less	Unit	Item Description	Tender Rates		Per	Amount
				In figures Rs. Ps.	In Words		
1	39.80	CM	ITEM NO : 1 Excavation for foundation in all sorts of soil including yellow, sandy, gravelly soil, soft & hard murrum, etc. dry condition including depositing the excavated stuff in uniform layers in banks or as directed etc. complete for lead up to 1.0 Km and all lifts. (By machinery)	81.50	Rupees Eighty One and Fifty Paisa	CM	3243.70
2	27.00	CM	ITEM NO : 2 Providing and filling rubbles including hand packing and filling interstices with quarry spalls behind abutments and between returns as directed.	1086.49	Rupees One Thousand Eighty Six and Forty Nine Paisa	CM	28749.60
3	14.00	CM	ITEM NO : 3 Providing and filling sand Below R.C.C Raft in Layers including Ramming and watering complete	552.22	Rupees Five Hundred Fifty Two and Twenty two Paisa	CM	6725.74
4			ITEM NO : 4 Providing & laying plain/reinforced Nominal Mix cement concrete of various grade with cement, sand and coarse aggregates including cantering, shuttering, batching, mixing, transporting, placing, vibrating, smooth finishing, curing etc. complete for all lead and lift. (Baching Plant Based, including dewatering)				
	15.00	CM	(B) Raft, Bottom slab of barrel, footing of columns, peirs, abutment and bottom slab of sump etc. (i) M - 15 Grade	4380.90	Rupees Four Thousand Three Hundred Eighty and Ninety Paisa	CM	65713.50
	2.00	CM	(C) Piers, abutment, wingwalls, headwall, returnwall etc. (ii) M-15 grade.	4499.60	Rupees Four Thousand Four Hundred Ninety Nine and Sixty Paisa	CM	8999.20
	9.00	CM	(C) Piers, abutment, wingwalls, headwall, returnwall etc. (iii) M-20 grade.	4976.90	Rupees Four Thousand Nine Hundred Seventy Six and Ninety Paisa	CM	44792.10
	18.00	CM	(B) Raft, Bottom slab of barrel, footing of columns, peirs, abutment and bottom slab of sump etc. (ii) M-20 grade.	4796.10	Rupees Four Thousand Seven Hundred Ninety Six and Ten Paisa	CM	86329.80

	13.00	CM	(B) Raft, Bottom slab of barrel, footing of columns, piers, abutment and bottom slab of sump etc. (iii) M - 25 Grade	4844.70	Rupees Four Thousand Eight Hundred Forty Four and Seventy Paise	CM	62981.10
	9.50	CM	(D) Walls of barrels, brestwall, staunching rings, pedestals of bearing, stoplog piers, well staining, transition wall etc (iii) M-25 grade.	5753.60	Rupees Five Thousand Seven Hundred Fifty Three and Sixty Paise	CM	54659.20
	10.00	CM	(E) Roadway slab, approach slab, chute floor slab, kerb, pier cap, abutment cap, hoisting platform, top slab of barrel etc. (ii) M-25grade.	5206.30	Rupees Five Thousand Two Hundred Six and Thirty Paise	CM	52063.00
5	79.64	SM	Item No.-5 Providing and laying 75mm wearing coat of ordinary portland cement concrete M-15 grade including laying on proper camber, tamping, screening, finishing, broomung or grooving etc. complete for all leds and lifts.	282.30	Rupees Two Hundred Eighty Two and Thirty Paise	SM	22482.37
6	40.70	Qtl	Item No.-6 Providing & Placing in position reinforcement bars including cutting, bending welding joints where necessary, hooking etc, complete as per drawing for all leads and lifts. (b) TMT	7194.00	Rupees Seven Thousand One Hundred Ninety Four	Qtl	292795.80
7	8.00	Rmt	Item No.-7 Providing & Fixing in position 110 mm dia. PVC pipes weep holes in abutment, wing wall and laying training etc. comp.	263.70	Rupees Two Hundred Sixty Three and Seventy Paise	Rmt	2109.60
8	58.50	SM	Item No.-8 White or colour wash in following coats including scrapping, scaffolding etc.comp. (13-B) For three coats	21.80	Rupees Twenty One and Eighty Paise	SM	1275.30
9	115.20	SM	Item No.-9 Providing and laying plain / Reinforced cement concrete lining of 1:2:4 praportion (Nominal mix) in bed, side slope and curveture including mixing transporting, placing, smooth finishing, curing including dewatering where required (Manually With Conventional Mixer Without Paver) a) 7.50 cm in Bed & slope (with water curing)	364.50	Rupees Three Hundred Sixty Four and Fifty Paise	SM	41990.40
10	2.00	Each	Item No.-10 Providing G.I. 100 mm diameter water spouts including necessary iron gratings as per drawing.	536.03	Rupees Five Hundred Thirty Six and Three Paise	Each	1072.06
11	1.00	Job	Item No.-11 Taking photography at site before starting the work,during execution & after completion of work.	500.00	Rupees Five Hundred	Job	500.00
					Total		776482.47

Rupees Seven lakh seventy six thousand four hundred eighty two rupees and forty seven paise only.

I/We am/are willing to carry out the work at.....% above/below percent (Should be written in figures and words) of the estimated rate mentioned above. Amount of my /our tender works out as under.

Estimated amount put to tender

Estimated amount put to tender

Deduct.....% below

Add.....% Above

Net

Net

In words

In words

Note:-GST as per prevailing rate shall be paid Extra.