




GWALIOR MUNICIPAL CORPORATION
ESTIMATE CONSTRUCTION OF CC ROAD

LOCATION- WARD 10 ZONE 02

वार्ड 10 अंतर्गत विभिन्न स्थानों पर सीसी रोड निर्माण कार्य

INTEGRATED STANDARD SCHEDULE OF RATES INTEGRATED [VOLUME - I] ROAD & BRIDGE WORKS - 2025-26

S.N o.	ITEM /	ITEM DETAIL	NUM BER	L	W	H	QTY.	UNIT	UNIT RATE	AMOUNT
1	2.5/17	Dismantling of Cement Concrete Pavement Dismantling of Cement Concrete pavement by mechanical means including breaking to pieces not exceeding 0.02 Cum in volume and stock piling at designated locations and disposal of dismantled materials up to a lead up to 1000 meters, stacking serviceable and unserviceable materials separately as per Section-200 of the specifications.	1	50	2.5	0.1	12.5	cum	643	8037.5
2	6.4/61	Providing and Laying Cement Concrete Grade M-20 with 20 mm graded crushed stone aggregate, mixing shall be in mechanical mixer, laying with paver compacting by use of pin, plate / screed vibrators including form work by strong steel girders fixed by spikes, separation membrane 125 micron thick, including cutting of joints @ 4 to 5 m interval and filling it with hot applied bituminous sealant (without dowel bars) (max. thickness 20 cm).	1	250	2.5	0.15	93.75	CUM	5251	492281.25
			1	19	13	0.15	37.05	CUM	5251	194549.55
TOTAL AMOUNT										694868.30
ADD 18% GST										125076.294
TOTAL AMOUNT WITH GST										819944.59
 SE MUNICIPAL CORPORATION GWALIOR			 AE MUNICIPAL CORPORATION GWALIOR			 EE MUNICIPAL CORPORATION GWALIOR				