

Name of work :-Construction of compound wall and wire fencing work at Lukhasan and Kahoda SHW, RCC Road and Land filling work At Lukhasan HW Under Dharoi RWSS. Ta: Siddhpur, Dist. :- Patan

SCHEDULE - 'A'

Sr. No.	Description of Materials	Qty. to be supplied	Rate	Unit	Place of Delivery
---------	--------------------------	---------------------	------	------	-------------------

NIL

NOTES :-

- | | |
|----|--|
| 1 | The contractor submitting the Tender shall see that the rate in Schedule-A are filled in by the Engineer in Charge at the time of issue tender. |
| 2 | The contractor while submitting the tender shall provide his own arrangement at his own cost for loading, unloading, and transporting safety to the site of work the cement stipulated in Schedule-A |
| 3 | Binding wire of 15 gauge of thinner gauge required for placing the reinforcement in position shall be provided at his own cost. |
| 4 | All the materials required for the items other than labour in Schedule-A but available with the dept. will be issued on request to the contractor. (for use in this contract only) at prevailing market rates or departmental issue rates whichever is higher. |
| 5 | All the surplus materials supplied by the deptt. As mentioned in schedule-A should be handed over to the Department by the contractor at the Govt. stores as directed. |
| 6 | The materials mentioned in schedule-A shall have to be checked for their correctness and soundness by the contractor before taking the delivery of the materials from the Government. |
| 7 | Necessary cement will be purchased by the agency at their own cost from open market. |
| 8 | The persons of firm submitting the Tender should see that rates in the above schedule are filled up by the Executive Engineer, on the issue of form prior to the submission of the Tender. |
| 9 | Carting of above materials should be done by contractor at his own cost. |
| 10 | Contractor should return the balance materials in good and acceptable condition, otherwise recovery at the double rates will be affected in view of Clause 12.4. |
| 11 | Those works will be executed which are found necessary at the time of execution, contractor will not be entitle for any claim for saving in any items as per site condition. |
| 12 | The sub contract, if any given by the contractor would not create any right against the Board. |
| 13 | The Amount Recoverable from the contractor by the Gujarat water supply and sewerage board on any account shall be liable to be recovered from the amount payable to the contractor / suppliers. |
| 14 | After passing the bill fund shall be demanded to higher authority payment shall be made after getting fund from higher authority. |

Signature of contractor

**Deputy Executive Engineer
Public Health Dharoi Proj. Sub.Division
Sidhapur**

**Executive Engineer
Public Health Dharoi Proj. Division
Mehsana**

SCHEDULE-B

Name of work :-Construction of compound wall and wire fancing work at Lukhasan and Kahoda SHW, RCC Road and Land filling work At Lukhasan HW Under Dharoi RWSS. Ta: Siddhpur, Dist. :- Patan

Sr No.	Decription	Qty	Unit	Rate in Rs.		Amount
				In figure	In Words	
1.0	Excavation for foundation up to 1.5 M. depth including sorting out and stacking of useful materials and disposing of excavated stuff up to 50 M. lead. in Loose or Soft soil	203.13	Cmt	128.79	Rupees One Hundred Twenty Eight & Paise Seventy Nine only	26161.11
2.0	Filling available excavated earth (excluding rock) in tranches, plinths, sides of foundations etc. in layers not exceeding 20 cm in depth consolidating each deposited layers by ramming and watering. in Loose or Soft soil Rate	98.03	Cmt	137.47	Rupees One Hundred Thirty Seven & Paise Forty Seven only	13476.18
3.0	P.C.C. M-10 leveling Course Providing and casting in situ mass cement concrete in grade M-10 (approx. corresp. to prop. 1:3:6) using granite quartzite trap metal of size 12 mm to 25 mm incl. consolidation curing etc. complete. 2.2 Without Forms Work	20.31	Cmt	3662.00	Rupees Three Thousand Six Hundred Sixty Two only	74375.22
4.0	Brick work using common burnt clay building bricks having crushing strength not less than 35 kg./Sq.Cm. in foundation and plinth in Cement Mortar 1:6 (1- Cement :6 -fine sand)(B) Conventional	213.48	Cmt	3708.98	Rupees Three Thousand Seven Hundred Eight & Paise Ninety Eight only	791793.05
5.0	Supplying cutting, bending, binding and placing in position steel as per plan and design and as per ISS 2502 including cost of steel and binding wire for reservoirs/structures only including lift up to 6 meter height or depth below G.L. for all diameters	1.490	MT	77504.00	Rupees Seventy Seven Thousand Five Hundred Four only	115480.96
6.0	Providing 15 mm. Thick cement plaster in single coat on rough (similar) side og single or half brick walls for interior plastering up to floor two level and finished even and smooth in cement Mortar 1:3 (1 cement : 3 Sand)	1239.49	Sq.Mt.	188.98	Rupees One Hundred Eighty Eight & Paise Ninety Eight only	234238.82
7.0	Finishing wall with weather proof exterior emulsion paint on wall surface (two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt and remains of loose powdered materials etc. Complete.	1239.49	Sq.Mt.	122.14	Rupees One Hundred Twenty Two & Paise Fourteen only	151391.31
8.0	Steel work, welded in built up sections framed work including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. (D) In trusses and trussed purlins, upto 25 M. span and 15 M. ovarall height.	3.36	Qtl	9818.27	Rupees Nine Thousand Eight Hundred Eighteen & Paise Twenty Seven only	32989.39

Sr No.	Decription	Qty	Unit	Rate in Rs.		Amount
				In figure	In Words	
9.0	Painting two coats (excluding priming coat) over new steel & other metal surface with enamel paint, brushing, interior to give an even shade including cleaning the surface of all dirt, dust and other foreign matter.	11.20	Sq.Mt.	96.59	Rupees Ninety Six & Paise Fifty Nine only	1081.81
10.0	Providing and casting in situ C.C. in grade M-15 (approx. corresp. to prop. 1:2:4) (proportions as per mix design or as per Table 9 of IS456 2000 in masses by weigh batching) using granite, quartzite trap metal of size 6 mm to 20 mm for RCC work, including scaffolding centering, form work, needle vibrated consolidation, curing comp. up to 6 meter depth or height (excluding cost of reinforcement and neat finishing) with centering and shuttering/deshuttering etc. comp. for structure for other than water retaining. (a) Footong for Column or Foundation (with Form Work)	23.82	Cmt	4906.00	Rupees Four Thousand Nine Hundred Six only	116860.92
11.0	Providing and fixing 1.20 Metre high fencing with 2.0 Metre long M.S. Angle posts 40mm x 40 mm x6 mm and oil painting 3 coats fixed at 2.5 Mt,C/c. with five Horizontan lines and two diagonals of galvanised steel barbed wire weighting 9.38 Kg. per 100 Metre, strained and fixed to posts with G.I,staples including fixing the postsin ground with 0.5 M x 0.5.M x 0.5 M. block in C.C1:5:10 etc complete.	267.00	Rmt	391.93	Rupees Three Hundred Ninety One & Paise Ninety Three only	104645.31
12.0	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50Mt.lead.	24.00	Cmt	114.44	Rupees One Hundred Fourteen & Paise Forty Four only	2746.56
13.0	Providing and laying cement concrete 1:4:8 (1- Cement :4- coarse sand : 8- hand broken stone aggregates 40 mm nominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth	18.00	Cmt	2660.31	Rupees Two Thousand Six Hundred Sixty & Paise Thirty One only	47885.58
14.0	Providing and laying controlled cement concrete M.200 and curing complete excluding the cost of formwork and reinforcement for reinforced concrete work in (A) Foundations, footings, Base of columns and Mass concrete	24.00	Cmt	3874.28	Rupees Three Thousand Eight Hundred Seventy Four & Paise Twenty Eight only	92982.72
15.0	Providing and fixing pre-cast concrete kerb stone of gray cement based concrete block 30 cm length, 30 cm ht and 15 cm thick of M-250 grade concrete as per approved design and including excavation for fixing in proper line and level, filling the join with C;M 1:3 (1 cement :3 Fine Sand) etc complete. (upto 10 Ton)	60.00	Rmt	374.92	Rupees Three Hundred Seventy Four & Paise Ninety Two only	22495.20
16.0	Earthwork for embankment including breaking clods, dressing with all lead and lift (excluding watering and consolidation)(E) From Borrow area within 3.0 Km. lead	2470.272	Cmt	177.34	Rupees One Hundred Seventy Seven & Paise Thirty Four only	438078.04
Total						2266682.18
Total of Schedule B						2266682.18

Sr No.	Decription	Qty	Unit	Rate in Rs.		Amount
				In figure	In Words	

I/We am /are withing to carry out the work at _____ % above / belwo (Should be written in figures and words) Above/ below the tendered rate mentioned and above amount of my tender as under

Estimated amount put to
 Total Rs. _____
 Below % _____
 Deducted Rs. _____
 Net Rs. _____

Estimated amount put to
 Tender Rs. _____
 Above % _____
 Add Rs. _____
 Net Rs. _____

Signature of contractor

**Executive Engineer
 Public Health Dharoi Proj. Division
 Mehsana**

**Deputy Executive Engineer
 Public Health Dharoi Proj. Sub.Division
 Sidhapur**