

Name of work :- Resurfacing of Jesada to Krushnanagar Road (VR-NP) Km.0/000 to 3/120
Ta.Dhrangadhra, Dist.; Surendranagar. (Under MMGSY-Khas Angbhut-2025-26)

BILL OF QUANTITIES

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
1	Clearing and grubbing of road land incl.uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth upto 300mm removal of stumps of trees cut earlier and disposal of unserviceable materials © By mechanical means in area of Light jungle.	0.82	One Hect.	28393.03	23282.28
2	Earthwork for embankment including breaking clods, dressing with all lead and lift (Excluding watering and consolidation) (A) Selected soil should be From borrow area with all lead and lift and should have CBR not less than 6.00%.	7063.50	One Cum	150.38	1062209.13
3	Scarifying graveled macadam or Bitumen macadam surface 6cm to 10cm depth including stacking useful materials on road side and disposing off remaining stuff.	3252.00	One Sqm	39.62	128844.24
4	WBM Grading-1 Providing, laying, spreading and compacting stone agg. Of 90mm to 45mm size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN in stage to proper grade and camber, applying and brooming, stone screening/binding material to fill-up the intersties of coarse agg., watering and compacting to the required density grading-1 as per Technical Specification Clasue.405 By manual means.	1097.60	One Cum	2167.96	2379552.90

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
5	WBM Grading-2 Providing, laying, spreading and compacting stone agg. Of 63mm to 45mm size to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN in stage to proper grade and camber, applying and brooming, stone screening/binding material to fill-up the intersties of coarse agg., watering and compacting to the required density grading-2 as per Technical Specification Clasue.405 By manual means.	823.90	One Cum	2010.10	1656121.39
6	Rolling and Watering of earthwork with vibratory roller including filling in depression which occur during the process and as directed.	6999.30	One Cum	22.48	157344.26
7	Providing and laying bitumenous grout 37.50mm thick using Emulsion RS1 for tack coat at the rate of 4.00kg/10sqm on W.B.M. and using BT chips for required gradation with the asphalt of grade (VG-30) at the rate of 1.99% i.e 19.90kg/MT by weight of mix including heating and mixing in drum mix plant , transporting the mix and spreading the same by paver finisher and consolidation as per MOST specification including cost of all materials fuel, labours, tools and plants etc. using contractor's own drum mix plant etc. complete.	766.00	One MT	2549.64	1953024.24

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
8	Providing, laying and rolling 37.50mm thick compacted bitumenous Macadam (B.M.) in one layer with B.T. aggregates as specified and using Emulsion RS1 for tack coat at the rate of 2.50kg/10sqm (As per IRC-16) and using bitumen for mixing with agg. at the rate of 3.40% i.e 34.00kg/MT of total mix including mixing in Drum mix plant and spreading the same by paver finisher and consolidation with vibratory roller including necessary including cost of hire charges, firewood, oil, lubricants, labour charges, etc. by using constructor's own Drum mix plant, machineries and equipment, tools etc. complete in accordance with the requirement of specification.	844.00	One MT	3118.47	2631988.68
9	Providing and laying and rolling of 20mm Compacted mix seal surface with B.T. and aggregate as specified using bitumen Grade VG-30 for mixing with aggregate at the rate of 5.10% i.e 51.00Kg/MT of total mix including heating and mixing in drum mix plant and spreading the same by paver finisher and consolidation with vibratory roller including necessary firewood, oil, lubricants, labour charges using contractor's own drum mix plant, machineries and equipment, tools etc including flushing of sand 0.27cum/10sqm etc. complete in accordance with the requirement of specification.	471.00	One MT	3713.16	1748898.36
10	Excavation for foundation upto 1.5m depth including sorting out and stacking of useful materials and disposing of the excavated stuff upto all lead. (B) Dense or hard soil.	404.20	One Cum	241.79	97731.52
11	Excavation for foundation upto 1.5m depth including sorting out and stacking of useful materials and disposing of the excavated stuff upto all lead. (C) Hard Murrum	275.20	One Cum	412.00	113382.40

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
12	Providing and casting in situ ordinary cement concrete M-150 mix and providing necessary pin headers including shuttering, scaffolding, laying vibrating, curing and finishing complete Without V-Grooves For all Hieght.	861.50	One Cum	3799.60	3273355.40
13	Providing and filling in foundation with ordinary cement concrete M-100 mix and providing necessary vertical pin headers incl. Formwork, vibrating, ramming and curing complete.	124.60	One Cum	3226.63	402038.10
14	Providing and casting in situ Orndinary cement concrete- M-200 for average 75/150mm thick wearing coat laid as directed incuding. tamping, vibrating, finishing, curring and filling in joints with bitumen complete.	45.60	One Cum	4183.48	190766.69
15	Providing and casting in situ Contolled cement concrete- M-200 for average 75/150mm thick wearing coat laid as directed incuding. tamping, vibrating, finishing, curring and filling in joints with bitumen complete.	60.90	One Cum	5101.10	310656.99
16	Providing and laying weep hole in Abutment and returns by using A.C pipe of 100mm. Incl. fixing in proper grade and jointing the complete as per detailed specification.	236.00	One No	53.44	12611.84
17	Providing and laying in Position FE - 500/500D TMT bar reinforcement including cutting, bending, hooking and tying complete as per detailed drawings for the following (A) Piers (B) Abutments (C) Returns (D) Walls etc.	5.230	One MT	73217.52	382927.63
18	Providing and Fixing in position FE-500/500D TMT bar reinforcement including cutting, bending, hooking, and tying complete as per detailed drawaing (A)RCC kerb (B) RCC Footpath (B) RCC Solid Slab/ App. Slab / Wearing coat.	2.010	One MT	72601.86	145929.74

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
19	Supplying and fixing reinforced concrete heavy duty non pressure pipes with collars for culverts carrying heavy traffic as per IS 458-1991 specification including setting and joining the pipes in C.M. 1:2 watering and laying (to level or slope) of I.S. Class NP-3 of following internal diameter with all lead and lift. (i) 900mm Dia.	45.00	One Rmt.	3685.88	165864.60
20	Dismantling the existing structure including removing and stacking the dismantled materials as and where directed. RCC Work.	120.20	One Cum	886.05	106503.21
21	Dismantling G.I. Pipes G.S.W. Pipes and A.C Rain water pipes with fitting and clamps including stacking the materials with all lead and lift (for any of pipe)	45.00	One Rmt.	73.02	3285.90
22	Providing and fixing Precast cement concrete Hectometer as per IRC type design incl. painting, lettering etc. fixing in C.C. 1:5:10.	12.00	One No	356.49	4277.88
23	Providing and fixing Precast cement concrete Guard stone as per I.R.C. type design including white washing etc. complete. Fixing in C.C.1:5:10.	300.00	One No	327.69	98307.00
24	Providing and fixing ordinary Kilometer stone of pre-cast C.C. 1:2:4 including necessary reinforcement as per I.R.C. type design in C.C. 1:4:8 including painting lettering etc. complete. (For ODR, VR)	4.00	One No	704.33	2817.32
25	Providing and fixing Indicator stone of approve stone as per I.R.C. type design in C.C. 1:4:8 including white washing etc. complete Fixing in Earth	140.00	One No	102.84	14397.60
26	Providing and fixing Road sign of M.S. plate and angle iron incl. painting, lettering etc. complete. fixing in C.C. 1:4:8 block with necessary excavation etc. complete as per IRC type design (i) Reflective Type.	10.00	One No	3072.98	30729.80
27	Providing and fixing Flood guage post mark of 'C' angle size 100mm x 50mm x 6mm thick (in head wall 0.500mt. And 1.50mt. Out side with painting and lettering with redeum color as directed.	4.00	One No	1134.23	4536.92

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
28	Village/Bump Ahead sign. : Providing and fixing sign boards made out of 2mm Aluminium sheet size 90x60 cms. Rectangle as per the design of IRC-67-1977 pre treated with phosphating process and acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint reflectorised with retro reflective sheeting as per latest MOST specification letter and numbers should be as per IRC:30-1968, 3.1 Mt. long (2 nos) stand post and frame fabricated from suitable size iron angle of 50x50x5mm, painted with best quality epoxy coating in black and white bends, the details of symbole on inscription/ numerals for each board shall be as per the instruction of the Engineer in charge. The fixing at site shall be in C.C 1:2:4 block of size 45x45x60cms. for each leg including excavation curing etc. complete under the supervision of engineer in charge (A) Engineer Grade.	5.00	One No	5045.36	25226.80
29	Hazard Marker sign : Providing and Fixing sign boards made out of 2mm aluminum sheet : size 90*30 cms. rectangle as per design / Drawing attached (IRC). Pretreated with phosphating process and acid etching : coated with one coat of epoxy primer and two coats of best quality epoxy paint: reflectorised with retro reflective sheeting as per latest M.O.S.T specification: 3.1 M. long (2 nos) stand post and frame fabricated from suitable size iron angle of 35*35*3mm and 50*50*5mm : painted with best quality epoxy coatings in black and white bends the details of symbole or inscription / numerals for each board shall be as per the instruction of engineer in charge the fixing at site shall be in 1:2:4 CC block of size 45*45*60 cms for each leg: including excvation curing etc. comp.under the supervision of engineer-in-charge.(B) Engineering Grade	4.00	One No	2423.73	9694.92

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
30	Direction sign (Junction board):-Providing and fixing sign boards made out of 2mm aluminium sheet; size 244 x 122cms. rectangle as as per the design of IRC-67-1977 pre treated with phosphating process & acid etching; coated with one coat of epoxy primer and two coats of best quality epoxy paint; reflectorised with retro reflective sheeting as per latest M.O.S.T. Specifications; Letters and numerals should be as per IRC-30-1968, 3.1m long (2 nos) stand post and frame fabricated from suitable size iron angle of 50 x 50 x 5mm 75x75x6mm as required; painted with best quality epoxy coatings in black and white bends. the details of symbol or inscription / numerals for each board shall be as per the instruction of engineer in charge. The fixing at site shall be in 1:2:4 CC block of size 45 x 45 x 60cms. for each leg. including excavation curing etc. complete under the supervision of engineer in charge.(A) Engineer Grade(VR)...	1.00	One No	14831.70	14831.70
31	Cautionary Warning Sign : Providing and fixing sign boards made out of 2mm Aluminium sheet size 90x90x90 cms. Equilateral triangle as per the design of IRC-67-1977 pre treated with phosphating process and acid etching coated with one coat of epoxy primer and two coats of best quality epoxy paint reflectorised with retro reflective sheeting as per latest MOST specification 3.1 Mt. long stand post and frame fabricated from suitable size iron angle of 35x35x3mm, 75x75x6mm. as required painted with best quality epoxy coating in black and white bends the details of symbole for each board shall be as per the instruction of Engineer in charge the fixing at site shall be in 1:2:4 CC block of size 45x45x60cms. for each leg including excavation curring etc. complete under the supervision of engineer in charge (A) Engineering Grade.	4.00	One No	3808.65	15234.60

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
32	Citizen's information Board. Providing and fixing of typical MMGSY information board as per instruction. Two MS sheets of 3 mm thick, of 900 mm x 750mm size fixed at top & bottom duly rivetted with MS angles of 25 x 25 x 5 mm thick M.S angle shall be welded by two vertical M.S angle of 5 mm thick to 75 mm x 75 mm of 12 SWG square tubes posts duly embedded in cement concrete M-15 grade blocks of 600mm x 600mm x 750mm, below ground level. The letters & figure of any shade reflectorised with High Intensity Prismatic Grade Retro Reflective Sheeting of Type-4 as per ASTM D-4956 and latest MORD specifications; All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paints as per drawing Clause 1701 and Annexure 1700.1 (10.16). (A) Class-B High intensity Grade Retro Reflective sheeting.	1.00	One No	7325.53	7325.53
33	Road Marking with Hot Applied paints with reflectorising glass beads on bitumin surface providing and laying a hot applied thermoplasting compound 2.5mm thick including reflectorising glass beads @250 gm per sq.mtr area, thickness of 2.5mm is excluding of surface applied glass beads as per IRC:35-2015 the finished surface to be level, uniform and free from streaks and holes, zebra patta/bump/centerline/edge line/ cut patta. the while color marking should provide liminance coefficient on cement road shall be min. 130 mcd/m2/lux and asphalt road shall be min 100 mcd/m2/lux during the survice life during the date the marking should meet the performanace criteria for night time reflectivity, wet reflectivity and skid resistance as mentioned in the section-15 of IRC 35-2015 warranty for retroreflectivity shall be two years.	687.00	One Sqm	367.72	252623.64

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
34	Cate eye / road stud/ RPM : Supplying Raised Pavement markers of polycarbonate and ABS moulded body and reflective panels with micro prismatic lens (No glass bead lens) capable of providing total internal reflection of the light entering the lens face and shall support a load of 13635 kgs. tested in accordance to ASTM D 4280 type H and complying to specification of category A of MORTH circular No RW/NH/33023/10-97-DO III Dt. 11-06-1997. the height, width and length shall be exceed 20mm, 130mm and 130mm and with minimum reflective area of 13sqcm on each side and the slope to the base shall be 35+/-5 degree. the body of the marker should having finger grip for easy and accurate placement and application with epoxy /bituminous adhesive as recommended by the manufacturer of the marker. the colour of the marker should be as per the IRC:35-2015 and as directed by Engineer-in-charge.	447.00	One No	326.23	145824.81
Rupees One Crore Seventy Five Lakh(s) Seventy Two Thousand One Hundred Forty Eight And Paise Two Only					17572148.02

I \ We am \ are willing to carry out the work at % above \ bellow percent (Should be written in figures and words) of the estimated rate mentioned above. Amount of My \ Our tender works put as under.

* Estimated Amount
Put to tender **Rs**.....
Deduct.....%
Net **Rs**.....
In words.....

* Estimated Amount
Put to tender **Rs**.....
Add.....%
Total **Rs**.....
In words.....

Item No.	Description of Item (With brief specification and reference to book of Specification)	Quantity	Unit	Rate	Amount
----------	---	----------	------	------	--------

1.The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.

2.The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.

3.GST and Income tax TDS will be deducted at a source while making payments of bills

4.In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C Date:11/05/2017 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.

NOTE: Amount Rs.22810/- Of Dismantled materials shall be recovered from 1st R.A. bill of Contractor at once.

Signature of Contractor.

Deputy Executive Engineer
Panchayat R&B Sub Division
Dhrangadhara

Executive Engineer
Panchayat R&B Division
Surendranagar