

**SCHEDULE - B**

Name of work		Flood Damage Restoration work to Existing Checkdam on Gauvav River Near Village: Goral,Ta: Idar,Dist: S.K, JOB No. 03				
MEMORANDUM SHOWING THE DETAILS OF ITEM OF WORK TO BE CARRIED OUT						
Item No.	Quantity estimated but may	Item of Work	Approved Rate		Unit	Amount
			In Figure	In words		
			Rs. Ps.			
1		3		5	6	7
1	98.00	Excavation for foundation in all sorts of soil including yellow sandy gravelly soils ,soft & hard murrum etc. in dry condition including depositing the excavated stuff in uniform layers in banks or as and where directed etc. complete for lead up to 500m and all lift. (BY MACHINERY) Including dewatering.	107.8	One Hundred seven PS Eighty	Cmt	10564.40
2	40.00	Dismantling the existing foundation concrete including sorting out the dismantled stuff and stacking the useful material, removing the debris and making good the damages etc. complete as and where directed. Cement Concrete	1155.20	One Thousand One hundred FiftyFive PS Twenty	Cmt	46208.00
3	2.60	Providing & Placing in position reinforcement bars including cutting, bending, welding joints where necessary, hooking etc. complete as per drawing for all lead and lifts. TMT / CRS (FE 500 D)	82019.00	EightyTwo Thousand Ninteen	M.T	213249.40
4	394.00	Providing & Laying in position "NOMINAL MIX" cement concrete using cement, sand and crushed aggregate by mass and machine mix for C.C./R.C.C work incl. necessary formworks centering, scaffolding, compaction by vibrator, curing as directed with all lead & lift etc complete Without Dewatering and excluding cost of steel reinforcement.(A) For Foundation concrete / General purpose (c) C. C. Nominal Mix, M-15 and MSA-20 mm	3935.00	Three Thousand Nine Hundred ThirtyFive	CM	1550390.00
<b>Total Tendered Amount Rs.</b>						<b>1820411.80</b>

Signature of the Contractor

Deputy Executive Engineer  
Dharoi Irrigation Sub Division  
Idar