

Prise Adjustment

Name of Work : Flood Damage Restoration work to Existing Checkdam on Gauvav River Near Village: Goral,Ta: Idar,Dist: S.K, JOB No. 03

Item No.	Description of Item	Quantity	Unit	Rate in Figures	Amount	Wt. %	Price Adjustment												
							labour		Cement		Steel		Bitumen	POL		Plant and Machinery spares		Other Materials	
							Wt. in item	Wt. in project %	Wt. in item	Wt. in project %	Wt. in item	Wt. in project %	Wt. in item	Wt. in item	Wt. in project %	Wt. in item	Wt. in project %	Wt. in item	Wt. in project %
1	ITEM NO 1 Excavation for foundation in all sorts of soil including yellow sandy gravelly soils ,soft & hard murrum etc. in dry condition including depositing the excavated stuff in uniform layers in banks or as and where directed etc. complete for lead upto 500 m and all lift. (BY MACHINERY) including dewatering.	98.00	Cmt	107.8	10564.4	0.5803	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.5000	0.2902	0.5000	0.2902	0.0000	0.0000
2	ITEM NO 2 Dismantling the existing foundation concrete including sorting out the dismantled stuff and stacking the useful material, removing the debris and making good the damages etc. complete as and where directed. Cement Concrete	40	Cmt	1155.2	46208	2.5383	0.9901	2.5132	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0099	0.0251
3	Item No 3 Providing & Placing in position reinforcement bars including cutting, bending, welding joints where necessary, hooking etc. complete as per drawing for all lead and lifts. TMT / CRS (FE 500 D)	2.6	MT	82019	213249.40	11.7143	0.1057	1.2386	0.0000	0.0000	0.8943	10.4758	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000	0.0000
4	ITEM NO 4 Providing & Laying in position "NOMINAL MIX" cement concrete using cement, sand and crushed aggregate by mass and machine mix for C.C./R.C.C work incl. necessary formworks centering, scaffolding, compaction by vibrator, curing as directed with all lead & lift etc complete Without Dewatering and excluding cost of steel reinforcement. (A) For Foundation concrete / General purpose (c) C. C. Nominal Mix, M-15 and MSA-20 mm	394	Cmt	3935	1550390	85.1670	0.1725	14.6936	0.4891	41.6563	0.0000	0.0000	0.0000	0.0692	5.8902	0.0692	5.8902	0.2000	17.0366
					1820411.80	100.0000	Total PL %	18.4453		41.6563		10.4758			6.1804		6.1804		17.0618

