

Estimate Draft Report for Project Number: 752302

Report Run Date: 19-02-2026 13:28:31

Project Number	: 752302	Estimate Number	: 78-001-211007-24-29142	Version	: Draft
Project Type	: Deposit	Project Organization	: O/o E.E.(O&M DN.) SAUSAR	Distribution Centre	: O/o J.E. SAUSAR
Scheme Code	: 001	Scheme Name	: DEPOSIT WORK FOR GOVT INSTITUTIONS	Area Store	: Area Store Chhindwara
Project Start Date	: 01-SEP-23	Completion Date	: 01-SEP-26	Project Status	: Approved
Total Cost	: 184119.73	Item Cost	: 154060.9	Supervision Amount	: 8767.61
Consumer Name	: CMO NAGAR PALIKA SAUSAR	Deposit Amount	: 0		

Estimate Prepared By : Mr. Neeraj Holkar

Name of Work : PROJECT FOR THE FEEDER LT POLE WORK wrd no. 07,(504/01.06.2023)AND FEEDER ID 375733 (SB_PROJECT_ID:5118869) (Dt 21-AUG-23)

History & Scope : PROJECT FOR THE FEEDER LT POLE WORK wrd no. 07,(504/01.06.2023)AND FEEDER ID 375733 An application have been recieved from cmo nagar palika sausar for LT pole work at ward no. 07 sausar vide letter no. 504/01.06.2023

Technical Viability : The voltage regulation at tail end is ...% which is in permission at per supply code 2013

Certificate : The schedule and quantity is as per minimum requirement of quantity with guidelines of SOR

Nature of Work:

New, Augmentation and Conversion of 11 KV, 33 KV and LT Line


Junior Engineer
M.P.P.K.V.V.Co.Ltd. Sausar
Page 1 of 4



Funding Source:

Code	Name	Percentage	Loan No.
CCF	Consumer Contributed Fund	100	NOT APPLICABLE

Allocation No.:

OHL-11 KV LINE	: 140816
OHL-LT LINE CABLE	: 740107

Estimate Schedule/ Technical Aspects:

Task Number	Schedule No.	Schedule Qty	UOM	Schedule Description	Centage (%)	Labor & Trans. Chg. (%)	Item Cost
Charges							0
Labor							0
Miscellaneous-Capital					11.50	10.00	0
N-D-1.3 Material	N-D-1.3	.277	Kilometer	L.T.LINES 3 PHASE 5 WIRE ON RS JOIST SUPPORTS USING AERIAL BUNCHED XLPE CABLE(III) 3X95 + 1X16 + 1X50 SQ MM. (INSULATED NUETRAL MASSENGER)(SPAN OF 40 MTR)	0	13.82	154060.9 1753
Overheads							0
Returnable Material							0
Supervision							0
Total:							154060.9 184

Item Details:

Task Number : N-D-1.3 Material Task Name : N-D-1.3 Material

Item Code	Item Description	UOM	Remarks	Expenditure Type	Company Provided (DW)	Qty	Rate	Item Cost	Total Cost
11000002	R B JOINT 83 MILLER 175X8MM	Number		OHL-11 KV LINE		2	13891	27782	31621.47
11000004	TENSION CLAMP FOR DEAD END FOR LT A B CABLE	Set		OHL-11 KV LINE		8	434	3470	2480.88
11000001	SUSPENSION CLAMP FOR LT AB CABLE	Set		OHL-11 KV LINE		6	347	2082	2389.73
11000008	CLAMPS FOR NEUTRAL PIERCING CONNECTOR TYPE	Set		OHL-11 KV LINE		10	34	340	386.99
11000002	PIERCING CONNECTOR TYPE L 10 3/4" (MAIN 16 800MM TAP OFF 16 800MM)	Number		OHL-11 KV LINE		30	100	3000	3414.6
11000003	PIERCING CONNECTOR TYPE R (MAIN 16 80 80MM TAP OFF 16 80 80MM)	Number		OHL-11 KV LINE		20	54	1080	1229.26
11000004	LT A/B AIR BUNCH CABLE 5X80 80MM + 1X80 80MM INSULATED NEUTRAL CUM AN INSULATOR 1X16 80MM STAY SFT WITH/OUT STAY WIRE 16 MM (PAINTED)	Kilomet er		OHL-11 KV LINE		25	380510	95127.5	108274.12
10100001	STAY WIRE 16 16MM (170 MM)	Number		OHL-11 KV LINE		18	572	4481.6	5078.19
10100002	STAY WIRE 16 16MM (170 MM)	Kilogram m		OHL-11 KV LINE		18	76	592.8	674.72
10100004	STAY CLAMP A TYPE FOR RE JOINT 175X8MM 2X3 INCH BLANK BUNCH ROD BARE	Number		OHL-11 KV LINE		32	258	825.6	939.7
10000010	PLATE BOLT 40X40X20MM 10 NO PER STAY AND 1 NO PER TYPE 1 END NO 1 END 1 END 2 4" & 48	Number		OHL-11 KV LINE		2	300	600	738.45
10100001	CONCRETING (1.36) OF FOR PINS OF 83MM TYPE ONE (BASE PAINTING + BITTING)	cube meter		OHL-11 KV LINE		10	5145	3754.4	4216.35
10100002	CONCRETING (1.36) OF STAY OF 22 CM PER STAY (1.36)	cube meter		OHL-11 KV LINE		4	5145	2058	2362.82
10000010	M 8 BOLT WITH NUT 16X30	Number		OHL-11 KV LINE		3	23	70	317.6

	MM	m							
I2123002	EARTHING COIL OF 115 TURNS OF 50 MM.DIA AND 2.5 MTR LEAD OF 4.0 MM G.I WIRE	Number		OHL-11 KV LINE		2	142	284	323.25
I2123036	POLE MOUNTED DEEP DRAWN METAL LT DISTRIBUTION BOX FOR AB CABLE FOR 1 INCOMING 8 OUTGOING 1-PHASE CIRCUIT	Number		OHL-11 KV LINE		8	904	7232	8231.48
I2123037	POLE MOUNTED DEEP DRAWN METAL LT DISTRIBUTION BOX FOR AB CABLE FOR 1 INCOMING 4 OUTGOING 3-PHASE CIRCUIT	Number		OHL-11 KV LINE		2	1201	2402	2733.96
Total:								154060.9	175352.72

Task Number : Supervision **Task Name** : Supervision

Item Code	Item Description	UOM	Remarks	Expenditure Type	Company Provided (DW)	Qty	Rate	Item Cost	Total Cost
Supervision	Supervision Charges			OHL-LT LINE CABLE		5	0	0	8767.81
Total:								0	8767.81



कार्यालय कमिष्ठ अभियंता
मध्य प्रदेश पूर्ण श्रेण विधुत वितरण कम्पनी लिमिटेड सौसर
(ISO 9001:2015 Standard CERTIFIED)

राज्य रोड, सौसर, 490106 जिला- पाण्डुरा, मध्य प्रदेश कर्मांक-07165-20027 Email Id: jrsasusar@gmail.com

कर्मचारी अभिसौसर 504 सौसर/दिनांक- 19/02/2026

✓ श्री.एच.ओ. नगर पालिका अधिकारी
नगर पालिका परिषद् सौसर
सौसर (जिला - पाण्डुरा म.प्र.)

वेषक- वाई कर्मांक 07 में निर्युत पोल लगाने बाबत ।

संदर्भ- आपका पत्र कर्मांक-504/लौ.वि.न.पा.प./2023 सौसर दिनांक - 01.06.2023 ।


उपरोक्त निषयान्तर्गत लेख है कि, आपके द्वारा वाई कर्मांक 07 में विद्युत पोल लगाने हेतु प्रेषित पत्र के माध्यम से पाककलन/प्रोजेक्ट की मांग की गयी थी । जिस हेतु सर्वे उपरांत प्राककलन / प्रोजेक्ट कर्मांक 752302 तैयार कर आपकी ओर प्रेषित किया जा रहा है । आप से निवेदन है कि, इस प्राककलन/ प्रोजेक्ट का कार्य प्रदान हेतु आप "अ" श्रेणी विधुत सविदाकार को कार्यदेश कर सूचित करे । एवं सुपरविजन राशी का भुगतान करने में अभिम कार्यवाही हेतु आपकी ओर सादर प्रेषित है ।

अतः आप से निवेदन है कि, प्राककलन / प्रोजेक्ट कर्मांक - 752302 कार्य करवाने हेतु आप "अ" श्रेणी विधुत सविदाकार निर्धारित करने की आवश्यक कार्यवाही कर सूचित करे ।

ACCOUNT DETAIL FOR PAYMENT
ACCOUNT NO. 30988555055
FSC CODE- SBIN0005940
NAME - RAO MPPKVCO.LTD, CHHINDWARA
BRANCH- SBI, GANJ AREA, CHHINDWARA.

संदर्भ- 01 नं. पाककलन एवं डीग्रांड नोट की मूल छायापति ।

ज्याककनी.अभि/सौसर/
तिथि- 1) कार्यपालन अभियंता(सं/स),म.प्र.पू.शे.वि.वि.कं.लिमि.,सौसर संभाग ।


कमिष्ठ अभियंता
म.प्र.पू.शे.वि.वि.कं.लिमि.सौसर
सौसर/दिनांक-

कमिष्ठ अभियंता
म.प्र.पू.शे.वि.वि.कं.लिमि.,सौसर

कार्यालय नगर पालिका परिषद साँसर जिला छिंदवाड़ा(म.प्र.)

Email: cmosonsar@mpurban.gov.in


Phone No.: 07165-220043,220004

क्रमांक / 504 / लो.नि.वि. / न.पा.प. / 2023

साँसर, दिनांक : 01 / 06 / 2023

प्रति,

कनिष्ठ यंत्री,
म.प्र.पू.क्षे.वि.वि.कं. लिमिटेड,
साँसर।




विषय:- वार्ड क्र. 07 में विद्युत पोल लगाने बाबद।

-----000-----

उपरोक्त विषयांतर्गत लेख है कि, वार्ड क्र. 07 में निम्न स्थानों पर विद्युत तार हटाकर विद्युत केबल जाने का कार्य किया जाना है।

1. श्री सचिन हेयर सेलून के पास 1 नग
2. श्री दर्शन झाडे के मकान के पीछे 1 नग
3. श्री संदीप हिवरकर के मकान के पास 1 नग
4. गौरी निबुलकर के दुकान के पास 1 नग
5. विवेक टेम्बे के घर के पास 1 नग

अतः उक्त स्थल का निरीक्षण कर कार्य का प्राक्कलन तैयार कर इस कार्यालय को भेजने का कष्ट करेंगे।


नगर पालिका परिषद साँसर
जिला छिंदवाड़ा(म.प्र.)

ole

