

कार्यालय अधिशासी अभियंता लिफ्ट सिंचाई खण्ड-गोरखपुर

पत्रांक-459लिसिखगो/टेण्डर/गोरखपुर दिनांक 18-05-2026

मैनुअल अल्पकालीन निविदा सूचना संख्या-16/अ.अ.लि.सि.ख.गो./2026-27

महानिर्माण राज्यपाल जी उम्रो शासन की ओर से अधोहस्ताक्षरी द्वारा नीचे अंकित निम्नलिखित कार्य हेतु मोहरबन्द निविदा आमंत्रित की जाती है। निविदा अधोहस्ताक्षरी के कार्यालय से किसी भी कार्य दिवस में निर्धारित मूल्य देकर दिनांक 29.05.2026 से 04.06.2026 तक प्राप्त किये जा सकते हैं। सभी प्रकार से पूर्ण निविदायें दिनांक 05.06.2026 को अपरान्ह 12.00 बजे तक इस खण्ड में प्राप्त की जायेंगी तथा दिनांक 05.06.2026 को अधोहस्ताक्षरी/समिति द्वारा अपरान्ह 2.00 बजे उपस्थित निविदादाताओं के समक्ष खोली जायेगी।

क्र० सं०	कार्य का विवरण	मात्रा	कार्य पूर्ण करने की अवधि	कार्य की अनुमानित लागत जी०एस०टी० सहित (रु० लाख में)	निविदा प्रपत्र का मूल्य+जी०एस०टी० +स्टीमर चार्ज (रु० में)	धरोहर धनराशि (रु० में)	पंजीकृत श्रेणी
1	2	3	4	5	6	7	8
Lot. 01	Construction of Pumping Station near village Siuria, at KM 10 of Maniram Domingarh Bund on right Bank of river Rohin, Dist- Gorakhpur. Supply, Installation, Testing and Commissioning of Earthing system for protection of electrical equipment's situated at pump house as per requirement of site at Siuria Pumping Station, Gorakhpur.	As per BOQ	120 Days	9.58	Rs. 300.00+18%G.S.T. +500.00	Rs. 19160.00	"ए" मैकेनिकल अथवा उच्च
Lot. 02	Supply, Installation, Testing and Commissioning of Indoor lighting system which have different specified lights as per requirement for pump house of pumping station at Siuria Pumping Station, Gorakhpur.	As per BOQ	120 Days	6.38	Rs. 300.00+18%G.S.T. +500.00	Rs. 12760.00	"ए" मैकेनिकल अथवा उच्च
Lot. 03	Supply, Installation, Testing and Commissioning of Fire extinguisher and fire bucket to prevent fire hazards at Siuria Pumping Station, Gorakhpur.	As per BOQ	60 Days	2.68	Rs. 300.00+18%G.S.T. +500.00	Rs. 5360.00	"ए" मैकेनिकल अथवा उच्च
Lot. 04	Supply, Installation, Testing and Commissioning of outdoor lighting system which have different specified lights as per requirement for pumping station compound at Siuria Pumping Station, Gorakhpur.	As per BOQ	150 Days	9.58	Rs. 300.00+18%G.S.T. +500.00	Rs. 19160.00	"ए" मैकेनिकल अथवा उच्च
Lot. 05	Fabrication of MS delivery pipe for pump set No-10 which have 25 mtr pipeline (approx.) of 700 mm Dia by 10 mm thick MS plate with fixing of MS Flange, MS Stiffener on both ends properly including all required fabrication process as gas cutting, bending, welding, handling and painting by PU coating as per std. directed by Engineer in charge at site with all cost of material, labor and T&P etc. Pump no-10 at Siuria Pumping Station, Gorakhpur.	As per BOQ	30 Days	6.98	Rs. 300.00+18%G.S.T. +500.00	Rs. 13960.00	"ए" मैकेनिकल अथवा उच्च
Lot. 06	Fabrication of MS delivery pipe for pump set No-09 which have 25 mtr pipeline (approx.) of 700 mm Dia by 10 mm thick MS plate with fixing of MS Flange, MS Stiffener on both ends properly including all required fabrication process as gas cutting, bending, welding, handling and painting by PU coating as per std. directed by Engineer in charge at site with all cost of material, labor and T&P etc. Pump no-09 at Siuria Pumping Station, Gorakhpur.	As per BOQ	30 Days	6.98	Rs. 300.00+18%G.S.T. +500.00	Rs. 13960.00	"ए" मैकेनिकल अथवा उच्च
Lot. 07	Fabrication of MS delivery pipe for pump set No-08 which have 25 mtr pipeline (approx.) of 700 mm Dia by 10 mm thick MS plate with fixing of MS Flange, MS Stiffener on both ends properly including all required fabrication process as gas cutting, bending, welding, handling and painting by PU coating as per std. directed by Engineer in charge at site with all cost of material, labor and T&P etc. Pump no-08 at Siuria Pumping Station, Gorakhpur.	As per BOQ	30 Days	6.98	Rs. 300.00+18%G.S.T. +500.00	Rs. 13960.00	"ए" मैकेनिकल अथवा उच्च
Lot. 08	Fabrication of MS delivery pipe for pump set No-07 which have 25 mtr pipeline (approx.) of 700 mm Dia by 10 mm thick MS plate with fixing of MS Flange, MS Stiffener on both ends properly including all required fabrication process as gas cutting, bending, welding, handling and painting by PU coating as per std. directed by Engineer in charge at site with all cost of material, labor and T&P etc. Pump no-07 at Siuria Pumping Station, Gorakhpur.	As per BOQ	30 Days	6.98	Rs. 300.00+18%G.S.T. +500.00	Rs. 13960.00	"ए" मैकेनिकल अथवा उच्च
Lot. 09	Fabrication of MS delivery pipe for pump set No-06 which have 25 mtr pipeline (approx.) of 700 mm Dia by 10 mm thick MS plate with fixing of MS Flange, MS Stiffener on both ends properly including all required fabrication process as gas cutting, bending, welding, handling and painting by PU coating as per std. directed by Engineer in charge at site with all cost of material, labor and T&P etc. Pump no-06 at Siuria Pumping Station, Gorakhpur.	As per BOQ	30 Days	6.98	Rs. 300.00+18%G.S.T. +500.00	Rs. 13960.00	"ए" मैकेनिकल अथवा उच्च
Lot. 10	Fabrication of MS delivery pipe for pump set No-03 which have 25 mtr pipeline (approx.) of 500 mm Dia by 10 mm thick MS plate with fixing of MS Flange, MS Stiffener on both ends properly including all required fabrication process as gas cutting, bending, welding, handling and painting by PU coating as per std. directed by Engineer in charge at site with all cost of material, labor and T&P etc. Pump no-03 at Siuria Pumping Station, Gorakhpur.	As per BOQ	30 Days	5.73	Rs. 300.00+18%G.S.T. +500.00	Rs. 11460.00	"ए" मैकेनिकल अथवा उच्च
Lot. 11	Erection and commissioning of 700 mm MS pipe line (Delivery side) including expender, reducer, bell mouth, spool piece with proper clamping/support, Nut-Bolt, Washer, Rubber packing etc as required for all 07 no. of 40 cusec pump set as directed by Engineer in charge at Siuria Pumping Station, Gorakhpur.	As per BOQ	90 Days	7.45	Rs. 300.00+18%G.S.T. +500.00	Rs. 14900.00	"ए" मैकेनिकल अथवा उच्च
Lot. 12	Supply, Installation, Testing and Commissioning of cable trays having different size/specification as per requirement of pumping station at Siuria Pumping Station, Gorakhpur.	As per BOQ	120 Days	8.94	Rs. 300.00+18%G.S.T. +500.00	Rs. 17880.00	"ए" मैकेनिकल अथवा उच्च
Lot. 13	Supply, Installation, Testing and Commissioning of Dewatering pump set (10 HP Capacity, 3-Phase LT supply) for eject the water collected at pump house floor with required pipeline, foundation and other arrangement as per site at Siuria Pumping Station, Gorakhpur.	As per BOQ	120 Days	6.70	Rs. 300.00+18%G.S.T. +500.00	Rs. 13400.00	"ए" मैकेनिकल अथवा उच्च
Lot. 14	Under the scope of the pumping station project, construction and fabrication work is being undertaken for a CGI sheeted shed to be used as store/godown intended for material/equipment's storage. This involves the construction of a 15m X 15m godown with a height of 5 meters, featuring a structural framework comprising eight columns- Fabricated by 100mm X 10mm X 4mm square MS pipe and trusses by square MS pipe of suitable size as per std. Requirements and securely fixed to RCC pedestals and incorporating provisions for stress management and other technical specification at Lacchipur Tub well Construction Division Store, Gorakhpur.	As per BOQ	30 Days	9.91	Rs. 300.00+18%G.S.T. +500.00	Rs. 19820.00	"ए" मैकेनिकल अथवा उच्च

- नोट-
- निविदा के साथ निर्धारित धरोहर धनराशि केवल राष्ट्रीय बचत-पत्र अथवा अन्य निर्धारित राष्ट्रीयकृत बैंक की सी०डी०आर०/एफ०डी०आर० के रूप में स्वीकार होगी जो अधिशासी अभियंता लिफ्ट सिंचाई खण्ड, गोरखपुर के नाम से बंधक होगी। निविदा के साथ धरोहर धनराशि तथा रु० 100.00 का नान-जुडि०यल स्टैम्प पेपर रु० 1.00 के रेवेन्यू टिकट के निविदा केंद्रता की अवधि अंकित कर संलग्न करना होगा। ठेकेदार के निविदा दस्तों की वैधता 90 दिन तक होगी।
 - निविदा स्वीकृत अथवा अस्वीकृत करने का अधिकार बिना कारण बताये अधोहस्ताक्षरी/समिति को सुरक्षित होगा। ठेकेदार को सुझाव दिया जाता है कि निविदा देने के पूर्व कार्य स्थल पर कार्य का मूली-भौती निरीक्षण कर लें।
 - निविदादाता को रु० 100.00 के स्टैम्प पेपर पर स्वघोषणा शपथ-पत्र संलग्न करना होगा।
 - प्रत्येक लाट हेतु अलग-अलग निविदा प्राप्त की जायेंगी।
 - सिदिल संगठन द्वारा साईट के उपलब्धता के उपरान्त ही कार्य प्रारम्भ की तिथि निर्धारित की जायेगी।