

**GOVERNMENT OF INDIA**  
**MINISTRY OF RAILWAYS**

**TECHNICAL SPECIFICATION**

**CONTROL AND DISTRIBUTION PANEL  
FOR COLOUR LIGHT SIGNALLING SUPPLY  
IN 25 kv AC. TRACTION SYSTEM.**

**SPECIFICATION No.**

**TI/SPC/PSI/CLS/0020**

**ISSUED BY**

---

**RESEARCH DESIGNS AND STANDARDS ORGANISATION  
LUCKNOW - 226011.**

---

Signature Not  
Verified

Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05'30  
Reason: IREPS-CRIS  
Location: New Delhi

A&C SLIP NO. 1 - August 2003 TO TECHNICAL SPECIFICATION  
NO. T/SFC/PS/CLS/0020 FOR CONTROL AND DISTRIBUTION  
PANEL FOR COLOUR LIGHT SIGNALLING SUPPLY IN 25 kV AC  
TRACTION SYSTEM

- (i) Clause 5.1 - Replace the existing matter " Panel: the panel shall comprise the following." by the following matter.

" Panel :- The capacity of control & distribution panel for supply to CLS installations shall be 30A, 60A, 155A and 300 A when used with 5 kVA, 10 kVA, 25 kVA and 50 kVA auxiliary transformers ( ATs) respectively. The panel shall comprise the following."

- (ii) Clause 5.1 (iv) : Add the following matter after table No. (iv).

" Note - The current capacity of Rotary selector switch, Air break contactor indicated above as 30A, 60A, 155A & 300 A have been arrived at the lowest voltage 165 volts of the ATs of 5 kVA, 10k VA, 25 k VA & 50 k VA. However in case of the normal voltage of 240 V, the current ratings works out to be 21 A, 42 A, 104 A, 208 A. Based on this, it should be ensured that the max. load connected to these panels for CLS installations including other loads should not exceed 21 A, 42 A, 104 A & 208 A at the rated voltage of 240 V."

Signature Not  
Verified

Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05:30  
Reason: I am PS-CRIS  
Location: New Delhi

Specification No. TI/SPC/PSI/CLS/0022 for Technical Specification control and distribution panel for colour light signaling supply in 25 kV AC Traction system.

Amendment Number - 2

Reason of Revision - i) Modification in the schematic arrangement and logic circuit based on Southern Railway letter No. E. 219/6/1 dated 16-08-2005.

Date of issue - 03<sup>th</sup> April 2006

Please correct the specification No. TI/SPC/PSI/CLS/0020 with A&C slip No.1, with following corrections:

S.No.	Page & Clause No. & description	As amended			
1	Page 5, 5.1(ii)-Air break Contactors	S No	AT rating	Rating of air break contactors	quantity
		1	5 KVA	240 V ac,50 Hz,2 Pole,30 A with 6 set of auxiliary contacts 3NO and 3NC.	3
		2	10 KVA	240 V ac,50 Hz,2 Pole,60 A with 6 set of auxiliary contacts 3NO and 3NC.	3
		3	25 KVA	240 V ac,50 Hz,2 Pole,155 A with 6 set of auxiliary contacts 3NO and 3NC.	3
		4	50 KVA	240 V ac,50 Hz,2 Pole,300 A with 6 set of auxiliary contacts 3NO and 3NC.	3
2	Page 6&7,Clause No.5.2.1-Panel (last Para)	The interior of CLS panel shall be adequately lighted by 60 Watt, 240 V AC lamp with a door operated switch. The wiring shall be capable to ON/OFF the lamp through door operated switch if any one power supply is available on the panel.			
3	Page 8,Clause 7.0-Painting	<p>The supporting frame and panel shall be properly treated and then under coated suitably to serve as base and binder for the finishing coat applied. The exterior &amp; interior surface and the supporting frame of the panel shall be epoxy powder coated of VELLUM colour in a shade No. 365 of IS:5.</p> <p>If any painting surface gets damaged during transit, the surface finish shall be restored at site after erection.</p>			
4	Page 15, Annexure-II	Existing Annexure-II ( Drawing No.ETI/PSI/035-2) replaced herewith attached Annexure-II (ETI/PSI/035-3).			

Signature Not Verified

Digitally signed by AKASH KUMAR  
Date: 2026.04.06 18:38:57 +05'30'  
Reason: IREPS-CRIS  
Location: New Delhi



Revisions of technical specification of control and distribution panel for color light signaling supply in 25 kV AC traction system.

**Specification No. TI/SPC/PSI/CLS/0023** for Technical Specification for control and distribution panel for color light signaling supply in 25 kV AC Traction system.

Amendment Number - 3

Reason of Revision - i) Modification in Painting process based on CORE, Allahabad letter No. ELCORE/ ALD/FIT/656/09/06 dated 08-09-2006.  
ii) Provision of MCCB for higher rating currents for which MCB are not available.  
iii) Addition of wiring details like size of power and control cables etc.

Date of issue - 21-3-2007

Please correct the specification No. TI/SPC/PSI/CLS/0020 with A&C No. 1&2 (i.e. TI/SPC/PSI/CLS/0022) with following corrections:

S. No.	Page & Clause No. & description	Existing				As amended			
		Sr. No	AT rating	Rating of rotary selector switch	Quantity	S. No	AT rating	Rating of rotary selector switch	Quantity
1	Page 5 Clause 5.1 (i) Rotary selector switch	1	5KVA	4 Pole, 5 way, 240 V a.c. 50 Hz, 30 A	1	1	5KVA	4 Pole, 6 way, 240 V a.c., 50 Hz, 30 A	1
		2	10KVA	4 Pole, 5 way, 240 V a.c. 50 Hz, 60 A	1	2	10KVA	4 Pole, 6 way, 240 V a.c., 50 Hz, 60 A	1
		3	25KVA	4 Pole, 5 way, 240 V a.c. 50 Hz, 155 A	1	3	25KVA	4 Pole, 6 way, 240 V a.c., 50 Hz, 150 A	1
		4	50KVA	4 Pole, 5 way, 240 V a.c. 50 Hz, 300 A	1	4	50KVA	4 Pole, 6 way, 240 V a.c., 50 Hz, 300 A	1
2	Page 5 Clause 5.1 (ii) and amendment No. 2 Air break contactors	1	5KVA	240 V a.c., 50 Hz, 2 Pole, 30 A with 6 set of auxiliary contacts 3 NO and 3 NC	3	1	5KVA	240 V a.c., 50 Hz, 2 or 3 Pole as commercially available, 30 A with 2 NO and 2 NC auxiliary contacts	3
		2	10KVA	240 V a.c., 50 Hz, 2 Pole, 60 A with 6 set of auxiliary contacts 3 NO and 3 NC	3	2	10KVA	240 V a.c., 50 Hz, 2 or 3 Pole as commercially available, 60 A with 2 NO and 2 NC auxiliary contacts	3
						3	25KVA	240 V a.c., 50 Hz, 2 or 3 Pole as commercially	3

Signature Not Verified

Digitally signed by AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05'30'

Reason: IREPS-CRIS  
Location: New Delhi

		3	25KVA	240 V a.c., 50 Hz, 2 Pole , 155 A with 6 set of auxiliary contacts 3 NO and 3 NC	3		available, 150 A with 2 NO and 2 NC auxiliary contacts		
		4	50KVA	240 V a.c., 50 Hz, 2 Pole , 300 A with 6 set of auxiliary contacts 3 NO and 3 NC	3		240 V a.c., 50 Hz, 2 or 3 Pole as commercially available, 300 A with 2 NO and 2 NC auxiliary contacts	3	
3	Page 5, Clause No.5.1 (iii)- Miniature circuit breakers on input side	Heading "Miniature circuit breakers on input side"				"Miniature circuit breakers as per IS: 8828/ Moulded case circuit breaker as per IS:13947 – 1&2 or IEC: 60947-2, for higher current ratings for which MCB's are not available, on input side". Add the following matter below existing table: Note: 3 pole commercially available MCCB may be used if 2 Pole MCCB not available.			
4	Page 5, Clause No.5.1 (iv)- Miniature circuit breakers on out put side	Heading "Miniature circuit breakers on output side"				"Miniature circuit breakers as per IS: 8828/ Moulded case circuit breaker as per IS:13947 –1&2 or IEC: 60947-2, for higher current ratings for which MCB's are not available, on output side". Add the following matter below existing table: Note: 3 pole commercially available MCCB may be used if 2 Pole MCCB not available.			
5	Page 6, clause 5.2.1 –Panel - In ninth & tenth line of first para	"and 4 out going cables 6 mm sq. each through suitable cable glands"				"and 4 out going cables of suitable size as per field requirement each through suitable cable glands". <i>Add the following Para, after last sentence:</i>  "The priority / sequence of power supply selection, mentioned in the specification may be changed by purchaser according to power supply source reliability and the same shall be furnished at the time of tender finalization and inspecting authority clearing the panel for dispatch shall check the same as per priority approved by tenderer".			
6	Page 7 Clause 5.2.2 - Rotary selector switch	The Rotary selector switch shall be of flush type. The contacts shall be of robust design and have ample cross-section for carrying continuously 30 A for 5KVA AT, 60A for 10 KVA AT, 155A for 25KVA AT, 300A for 50KVA AT and be of positive make type to avoid any sparking. The rotary switch shall be enclosed with a transparent cover to prevent accidental/inadvertent/interference to circuit. The selector switch shall have five positions: - <ul style="list-style-type: none"><li>(i) Off</li><li>(ii) Main supply</li><li>(iii) Standby one supply</li><li>(iv) Standby two supply</li><li>(v) Auto</li></ul>				The Rotary selector switch shall be of flush type. The contacts shall be of robust design and have ample cross-section for carrying continuously 30 A for 5KVA AT, 60A for 10 KVA AT, 150A for 25KVA AT, 300A for 50KVA AT and be of positive make type to avoid any sparking. The rotary switch shall be enclosed with a transparent cover to prevent accidental/ inadvertent/ interference to circuit. The selector switch shall have the following six positions: - <ul style="list-style-type: none"><li>(i) Off</li><li>(ii) Main supply</li><li>(iii) Standby one supply</li><li>(iv) Standby two supply</li></ul>			

			(v) Off (vi) Auto
7	Page 7 Clause 5.2.3 - Contactor	The contactors shall be of electromagnetic air break type of robust design having a continuous rating of 240 V a.c. 50 Hz, 30 A for 5 KVA AT, 60 A for 10 KVA AT, 155 A for 25 KVA AT, 300 A for 50 KVA AT with 6 sets of auxiliary contacts, 3 of them normally open and the other 3 normally closed. The contacts shall be silver plated, bounce proof and have ample cross section for carrying the rated current continuously without exceeding the permissible temperature rise.	The contactors shall be of electromagnetic air break type of robust design having a continuous rating of 240 V a.c. 50 Hz, 30 A for 5 KVA AT, 60 A for 10 KVA AT, 150 A for 25 KVA AT, 300 A for 50 KVA AT with 2 number normally open and 2 number normally closed auxiliary contacts. The contacts shall be silver plated, bounce proof and have ample cross section for carrying the rated current continuously without exceeding the permissible temperature rise.
8	New clause 5.2.8 added - <u>Panel Wiring</u>		<b>5.2.8 - Panel wiring</b> (i) All panel wiring shall be done with 1100 V grade PVC insulated single core, tinned annealed stranded copper conductors for service in extremely tropical climate. The PVC wires shall conform to latest version/revision of IS: 694 and duly tested for flammability test as per IS: 10810 (Part 53)-1984. The wiring shall also not be prone to attack by vermin, i.e. mice, white ants, cockroaches etc. (ii) The size of cable for Power circuits shall be of 10 sq. mm for 5 KVA, 16 sq. mm for 10 KVA, 50 sq. mm for 25 KVA and 120 sq. mm for 50 KVA rating. The wire size for control circuits shall not be less than 2.5 sq.mm. (iii) The terminal ends of all wires shall be provided with numbered interlock type ferrules, which are of PVC or other durable material with marking either engraved or punched so as to be indelible. The ferrules shall be of white or yellow color with black lettering thereon. The ends of all wires and cables shall be provided with suitable lugs/spades, which shall be crimped/soldered into the wires. All wiring shall be neatly bunched with PVC tape or laced by thread or PVC/Nylon wiring tags. No joints shall be permitted in the wiring.
9	New clause 5.2.9 added - Termination/ Connection of incoming and out going power cables in the panel		<b>5.2.9 – Termination / Connection of incoming and out going power cables in the panel</b> All the incoming and out going power cables shall be connected to the respective MCBs through suitable terminal connectors which should be provided inside the panel. It shall be of suitable size to terminate/connect the corresponding incoming and out going cables. The size and numbers of incoming cable and size of cables for Panel wiring for power and control circuits are mentioned in clause No. 4.1 and 5.2.8 (ii) respectively. The terminal connectors shall be

Signature Not Verified

Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05'Reason: IREPS-CRIS  
Location: New Delhi

			fixed in a manner to facilitate adequate gap of at least 20 mm between them and corresponding 2-pole MCB of each supply source to avoid short circuit and to facilitate ease of maintenance/replacement of cables. Adequate vacant space below the terminal connectors inside the panel should also be available to accommodate the each incoming and out going cables.
10	New clause 5.2.10 added - Lay out of equipments		<b>5.2.10- Lay out of equipments</b> Layout of the various equipments inside the panel shall be made in such a manner to facilitate adequate working clearance within the various equipments during maintenance/ replacement. The details of working clearance among various equipments in side the panel must be indicated in design drawings, which shall be finalized by CORE/Prototype approving authority at the time of drawings approval prior to prototype testing. Drg. No. ETI/PSI/035 – 4 is for reference, the size of panel and detailed drawings shall be finalized by CORE/Prototype approving authority at the time of design & drawings approval of the manufacturer.
11	Page 8 clause 7.0 (Painting) & Amendment No. 2	The supporting frame and panel shall be properly treated and then under coated suitably to serve as base and binder for the finishing coat applied. The exterior & interior surface and the supporting frame of the panel shall be epoxy powder coated of VELLUM colour in a shade No. 365 of IS:5.  If any painting surface gets damaged during transit, the surface finish shall be restored at site after erection.	The supporting frame and panel shall be properly treated to avoid rusting. The manufacturer shall use the following pretreatment through seven tank process: <ul style="list-style-type: none"> <li>▪ Degreasing</li> <li>▪ Rinsing (water wash)</li> <li>▪ Pickling (Acid pickling)</li> <li>▪ Rinsing (water wash)</li> <li>▪ Zinc Phosphating</li> <li>▪ Rinsing (water wash)</li> <li>▪ Drying</li> <li>▪ Powder coating &amp; Curing</li> </ul> The exterior & interior surface and the supporting frame of the panel shall be epoxy powder coated of Siemens Grey shade/color. If any painting surface gets damaged during transit, the surface finish shall be restored at site after erection.
12	Page 8 Clause 8.1 - Name plate	Suitable marking for identification of circuits and position of selector switch shall be engraved on the panel. The schematic diagram, generally as per the drawing attached to this specification, shall be made by engraving on a plate of durable quality and fixed on the inside of the cover of the panel. The engraved portion should be filled with Black/Red colour.	Suitable marking for identification of position of selector switch shall be indicated on the switch or panel. The schematic circuit diagram, generally as per the drawing attached to this specification and terminals block details of incoming and out going cable connection and inter panel wiring made of good quality acrylic sheet (or any other superior long lasting/durable material) with suitable lamination or coating for long life, shall be provided on inner side of panel door.
1	Drawings and	Lay out and general arrangement drawing of	Layout dimensional detail drawings of various

Signature Not Verified

Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05'Reason: IREPS-CRIS  
Location: New Delhi

3	technical details Page 11, clause No. 10.2 (a)	the panel showing mounting details of various equipments.	equipments inside and out side of the panel, over all size the panel, mounting arrangement drawings of the panel, control and power circuit in details etc.
1 4	Annexure –II (drg. No. ETI/PSI/035- 3) of amendment No.2	-	Existing Annexure-II (Drawing No. ETI/PSI/035-3) replaced herewith-attached Annexure-II (Drawing No. ETI/PSI/035-4)

Signature Not  
Verified

Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05'30  
Reason: IREPS-CRIS  
Location: New Delhi



Revisions of technical specification No. TI/SPC/PSI/CLS/0020 with amendment No. 1 to 3 of control and distribution panel for colour light signaling supply in 25 kV ac traction system

Amendment Number: 4

Reason of Revision:

- SECR letter No. SECR/ELECT/264/RDSO/1660 dated 04.05.2010 cable between auxiliary transformer & distribution panel.
- RDSO letter No. TI/PSI/PROT/CL/CT/S/03 dated 21.03.2003 advised to Railway regarding size and type of cable between auxiliary transformer & distribution panel.
- Clause 6.2.9 of RDSO specification No. ETI/PSI/12 (8/2003) for A1.

Date of issue: 05.07.2010

Please correct the specification No. TI/SPC/PSI/CLS/0020 with amendment No. 1 to 3 with following corrections:

S.N.	Page & clause	Existing	As amended
1.	Page 1 Clause 4.1	The arrangement caters for three sources of 240 V a.c. 50 Hz power supply at each station, with a provision for automatic changeover, forming a reliable source of supply for colour light signalling installations and other emergency loads. The main source of supply shall be the local supply from the Electricity Board if available, the two standby supplies being from the 5KVA or 10 KVA or 25KVA or 50KVA. 25 kV/240Vauxiliary Transformer (AT) one each installed at UP & Down track connected to the 25 kV a.c. 50 Hz single phase traction overhead equipment of UP & Down tracks at the station/BB/level crossing gate. However in exceptional cases where local supply is un-reliable, one of the ATs may be used as the main source of supply the other AT being the standby supply. The power supply to the panel shall be brought by means of 2x25 sq. mm aluminium conductor for 5KVA AT, 3 x 70 sq. mm	The arrangement caters for three sources of 240 V a.c. 50 Hz power supply at each station, with a provision for automatic changeover, forming a reliable source of supply for colour light signalling installations and other emergency loads. The main source of supply shall be the local supply from the Electricity Board if available, the two standby supplies being from the 5KVA or 10 KVA or 25KVA or 50KVA. 25kV/240Vauxiliary Transformer (AT) one each installed at UP & Down track connected to the 25 kV a.c. 50 Hz single phase traction overhead equipment of UP & Down tracks at the station/BB/level crossing gate. However, in exceptional cases where local supply is un-reliable, one of the ATs may be used as the main source of supply the other AT being the standby supply. The power supply to the panel shall be brought by means of 1100V grade, two core XLPE insulated armoured PVC sheathed with

Signature Not Verified

Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05'30  
Reason: I am PS-CRIS  
Location: New Delhi

	<p>aluminium conductor for 10 KVA AT, 2 x 185 sq. mm aluminium conductor for 25 KVA AT and 2x300 sq. mm aluminium conductor for 50 KVA AT. PVC insulated, PVC sheathed, 1100 V grade, armoured power cable conforming to IS: 1554 Part-I (latest version) from each of the sources.</p>	<p>aluminium conductor XLPE cable conforming to IS: 7098 (Part-I), 25 sq. mm for 5KVA AT, 70 sq. mm for 10 KVA AT, 150 sq. mm for 25 KVA AT and 300 sq. mm for 50 KVA AT from each of the sources.</p>
<p>Page 6 Clause 5.2.1</p>	<p>The panel shall be made of sheet steel not less than 1.6 mm thick suitable for wall mounting. It shall be of the totally enclosed type so as to be completely dust, weather and vermin proof. It shall be provided with a hinged cover and suitable locking arrangements. Access to components inside the panel shall be possible only after opening the cover. Provision shall be made for entry of 3 incoming cables each of 2x25 sq. mm aluminium conductor for 5KVA AT or 2 x 70 sq. mm aluminium conductor for 10 KVA AT or 2 x 185 sq. mm aluminium conductor for 25 KVA AT or 2x300 sq. mm aluminium conductor for 50 KVA AT. PVC insulated, PVC sheathed, 1100 V grade, armoured power cable and 4 outgoing cables 6 mm sq. each through suitable cable glands. The terminals shall be of tinned copper. The operating knobs/handles of the rotary switches and the miniature circuit breakers shall project outside the cover of the panel, for easy operation. The interior of C.I.S panel shall be adequately lighted by 60 Watt, 240 V AC lamp with a switch. The switch/wiring shall be capable to ON &amp; OFF the lamp if any one incoming power supply source is available in the panel.</p>	<p>The panel shall be made of sheet steel not less than 1.6 mm thick suitable for wall mounting. It shall be of the totally enclosed type so as to be completely dust, weather and vermin proof. It shall be provided with a hinged cover and suitable locking arrangements. Access to components inside the panel shall be possible only after opening the cover. Provision shall be made for entry of 3 incoming 1100V grade, Two core XLPE insulated armoured PVC sheathed with aluminium conductor XLPE cables each of 25 sq. mm for 5KVA AT or 70 sq. mm for 10 KVA AT or 150 sq. mm for 25 KVA AT or 300 sq. mm for 50 KVA AT, and 4 outgoing cables of suitable rating as per field requirement each through suitable cable glands. The terminals shall be of tinned copper. The operating knobs/handles of the rotary switches and the miniature circuit breakers shall project outside the cover of the panel, for easy operation. The interior of C.I.S panel shall be adequately lighted by 11 Watt, 240 V AC CFL lamp with door operated a switch. The wiring shall be capable to ON / OFF the lamp through door operated switch if any one power supply is available on the panel.</p>

Signature Not Verified

Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05:30  
Reason: I am PS-CRIS  
Location: New Delhi

**SPECIFICATION FOR** Technical Specification for Control & Distribution panel for colour light signalling supply in single Phase 25 kV AC 50 Hz Traction System.

**SPECIFICATION No. TI/SPC/PSU/CLS/0020**

Amendment Number	Amendment /Revision	Total pages including drawings	Date of Issue

	PREPARED BY	CHECKED BY	APPROVED BY
<b>SIGNATURES</b>	<i>[Signature]</i>	<i>P. K. Sarfari</i>	<i>[Signature]</i>
<b>DATE</b>	10.12.02	10.12.02	10.12.2002
<b>DESIGNATION</b>	ADE/TI-III	Dir/TI-III	EDTI

COPY NUMBER

ISSUED BY ..... SIGNATURE ..... DATE .....

ISSUED TO .....

\*This Specification is the property of RDSO. No reproduction shall be done without the permission of DG (TI) RDSO.

Signature Not Verified  
Digitally signed by AKASH KUMAR  
Date: 2026.04.06 18:38:57 +05'30  
Reason: IIR PS-CRIS  
Location: New Delhi

---

## INDEX

---

ITEM No	HEADING	PAGE
1	SCOPE	3
2	SERVICE CONDITIONS	3
3	GOVERNING SPECIFICATIONS	3
4	GENERAL REQUIREMENT	4
5	RATING & DESIGN FEATURES	5
6	EARTHING	8
7	PAINTING	8
8	NAME PLATE	8
9	TESTS	8
10	DRAWING AND TECHNICAL DETAILS	11
11	OPERATION, MAINTENANCE INSTRUCTIONS & TRAINING	12
12	WARRANTY	12

---

## ANNEXURES

---

ANNEXURES - I	SCHEDULED OF GUARANTEED AND TECHNICAL PARTICULARS	13
ANNEXURES - II	OUT LINE GENERAL ARRANGEMENT FOR CONTROL AND DISTRIBUTION PANEL FOR COLOUR LIGHT SIGNALLING SUPPLY WITH AUTOMATIC CHANGEOVER FACILITY (3 SOURCE) FOR 25 KV AC TRACTION SYSTEM	15

Signature Not Verified

Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05'30  
Reason: IREPS-CRIS  
Location: New Delhi

## 1.0 SCOPE

- 1.1 This specification covers design, manufacture, testing and supply of 240 V a.c. 50 Hz power supply control and distribution panel for supply to colour light signalling installations. This specification supersedes specification No. ETI/PSI/43 (10/90). The panel to be installed either in the station master's room or signalling cabin at Railway stations, will have provision for automatic changeover from main source of supply, in case it fails, to either of the two standby sources of supply and back again to the main source when it is restored.
- 1.2 The equipment offered shall be complete in all respects and shall include all accessories and materials which are necessary for the efficient operation of the control and distribution panel. Such accessories and materials shall be deemed to be within the scope of this specification whether specifically mentioned herein or not.

## 2.0 SERVICE CONDITIONS

- 2.1 The distribution panels are intended for use in moist tropical climate with the following atmospheric conditions.

1.	Max. temperature of air	50 ° C
2.	Min. temperature of air	0° C
3.	Max. temperature attainable by an object exposed to Sun	65° C
4.	Max. relative humidity	100%
5.	Max. wind pressure	200 kgf/sq.m.
6.	Altitude	> 1000 m
7.	Average annual rainfall.	1750 to 6250 mm.
8.	Number of thunderstorm days per annum.	85 days.
9.	No. of rainy days per annum	120 days (Max.)
10.	Average No. of dust storm days	35 days per annum.
11.	Vibrations	Max: 350 micron Average : 30 – 150 micron time duration : rapidly varying time duration 15 - 70 ms.

## 3.0 GOVERNING SPECIFICATIONS

- 3.1 The panel and its main components shall comply with the following specifications which shall be applied in the manner altered, amended or supplemented by this specification and the Indian Electricity Rules where-ever applicable:-
- (i) Busbar-IS: 2673- 1979.
  - (ii) Contactors- IS: 2959- 1985.
  - (iii) H.D. Switches (Rotary)- IS: 4064 (Part I & II)-1978.

- (iv) The general requirement for LT switchgear-IS: 4237-1982.
- (v) Miniature air break circuit breaker-IS: 8828-1978
- (vi) Electrical buzzer-IS: 2268-1984.
- (vii) Panel wiring – IS 5578 & 11353.
- (viii) Control switches / Push button – IS 6875.
- (ix) Cables : IS 1554 Part – I ( latest version )

Any deviation from this specification calculated to improve the performance, utility and efficiency of the equipment proposed by the tenderer will be given due consideration provided full particulars with justification thereof are furnished.

#### 4.0 GENERAL REQUIRMENT

- 4.1 The arrangement caters for three sources of 240 V a.c 50 Hz power supply at each station, with a provision for automatic changeover, forming a reliable source of supply for colour light signalling installations and other emergency loads. The main source of supply shall be the local supply from the Electricity Board if available, the two standby supplies being from the 5KVA or 10 KVA or 25KVA or 50KVA, 25 kV/240Vauxiliary Transformer (AT) one each installed at UP & Down track connected to the 25 kV a.c. 50 Hz single phase traction overhead equipment of UP & Down tracks at the station/IBH/level crossing gate. However, in exceptional cases where local supply is un-reliable, one of the ATs may be used as the main source of supply the other AT being the standby supply. The power supply to the panel shall be brought by means of 2x25 sq. mm aluminium conductor for 5KVA AT, 2 x 70 sq. mm aluminium conductor for 10 KVA AT, 2 x 185 sq. mm aluminium conductor for 25 KVA AT and 2x300 sq. mm aluminium conductor for 50 KVA AT, PVC insulated, PVC sheathed, 1100 V grade, armoured power cable conforming to IS: 1554 Part-I (latest version)from each of the sources.
- 4.2 The circuits shall normally be fed from the main source of supply. When the main source of supply fails, the changeover to either of the two standby sources shall be effected automatically through suitable contactors in the panel. On restoration of the main source of supply, the circuits shall be connected back to the main source of supply automatically. Whenever an automatic change over occurs in the event of main supply going off (or whenever the main supply is again restored) an alarm buzzer will sound which can be silenced by pressing alarm reset microswitch. The typical / tentative schematic general arrangement of the panel is indicated in Drg. No. ETI/PSI/035 -2 enclosed (Annexure – II).

- 4.3 Provision shall be made, in the event of defects/maintenance of the contactors, to connect the main or either of the standby supplies to the out going bus directly, so as to permit the contactor assembly being taken out without affecting continuity of supply to the load, supply from only one of the sources shall be connected to the outgoing bus at a time. Four outgoing circuits are connected to the 240 V busbar through individual miniature circuit breakers.
- 4.4 Provision shall be made that in case main supply voltage goes below 165V, main supply will be cut off and standby one supply shall be put on automatically, similarly this shall be applicable to stand by supply one and two also. However if main supply voltage become normal, standby supply one or two will automatically be cut off and main supply will feed the load.
- 4.5 Provision shall be made that in case main supply voltage goes above 270 V +5%-0%, the main supply shall be cut off and standby one supply shall be put on automatically similarly this shall be applicable to standby supply one and two also. However if main supply voltage become normal, standby one or two will automatically be cut off and main supply will feed the load.
- 4.6 The changeover time from one supply to other supply shall be less than 100 m sec.

#### 5.0 RATING & DESIGN FEATURES

5.1 **Panel:** The panel shall comprise the following.

(i) Rotary selector switch

S. No.	AT rating	Rating of rotary selector switch	Quantity
1	5KVA	4 Pole, 5 way, 240 V a.c. 50 Hz, 30 A	1
2	10KVA	4 Pole, 5 way, 240 V a.c. 50 Hz, 60 A	1
3	25KVA	4 Pole, 5 way, 240 V a.c. 50 Hz, 155 A	1
4	50KVA	4 Pole, 5 way, 240 V a.c. 50 Hz, 300A	1

(ii) Air break contactors

S. No.	AT rating	Rating of air break contactors	quantity
1	5KVA	240 V a.c., 50Hz, 30 A with 6set of auxiliary contacts 3 NO and 3 NC	3
2	10KVA	240 V a.c., 50Hz, 60 A with 6set of auxiliary contacts 3 NO and 3 NC	3
3	25 KVA	240 V a.c., 50Hz, 155 A with 6set of auxiliary contacts 3 NO and 3 NC	3
4	50 KVA	240 V a.c., 50Hz, 300 A with 6set of auxiliary contacts 3 NO and 3 NC	3

(iii) Miniature circuit breakers on input side

Signature Not Verified

Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05:30  
Reason: IREPS-CRIS  
Location: New Delhi

S. No.	AT rating	Rating of miniature circuit breaker	quantity
1	5KVA	240 V a.c. 2 Pole, 50 Hz, 32 A	3
2	10KVA	240 V a.c. 2 Pole, 50 Hz, 63 A	3
3	25KVA	240 V a.c. 2 Pole, 50 Hz, 150 A	3
4	50KVA	240 V a.c. 2 Pole, 50 Hz, 315 A	3

(iv) Miniature circuit breakers on out put side

S. No.	AT rating	Rating of miniature circuit breaker	quantity
1	5KVA	240 V a.c. 2 Pole, 50 Hz, 32 A	2
2	10KVA	240 V a.c. 2 Pole, 50 Hz, 63 A	2
3	25KVA	240 V a.c. 2 Pole, 50 Hz, 150 A	2
4	50KVA	240 V a.c. 2 Pole, 50 Hz, 315 A	2

(v) Miniature circuit breakers 240 V, a.c 2 pole 50 Hz, 1A and 6 A . 1 each

(vi) Lighting Emitting diodes (LED) for indication for incoming , outgoing and auto mode 10

(vi) Alarm buzzer 240 V, a.c. 50 Hz 1

(vii) Alarm reset micro switch 1

## 5.2 DESIGN FEATURES

### 5.2.1 PANEL

The panel shall be made of sheet steel not less than 1.6 mm thick suitable for wall mounting. It shall be of the totally enclosed type so as to be completely dust, weather and vermin proof. It shall be provided with a hinged cover and suitable locking arrangements. Access to components inside the panel shall be possible only after opening the cover. Provision shall be made for entry of 3 incoming cables each of 2x25 sq. mm aluminium conductor for 5KVA AT or 2 x 70 sq. mm aluminium conductor for 10 KVA AT or 2 x 185 sq. mm aluminium conductor for 25 KVA AT or 2x300 sq. mm aluminium conductor for 50 KVA AT, PVC insulated, PVC sheathed, 1100 V grade, armoured power cable and 4 outgoing cables 6 mm sq. each through suitable cable glands. The terminals shall be of tinned copper. The operating knobs/handles of the rotary switches and the miniature circuit breakers shall project outside the cover of the panel, for easy operation.

Signature Not Verified

Digitally signed by AKASH KUMAR  
Date: 2026.04.06 18:38:57 +05'30  
Reason: IREPS-CRIS  
Location: New Delhi

The interior of CLS panel shall be adequately lighted by 60 Watt, 240 V AC lamp with a switch . The switch/wiring shall be capable to ON & OFF the lamp if any one incoming power supply source is available in the panel.

### 5.2.2 ROTARY SELECTOR SWITCH:-

The Rotary selector switch shall be of flush type. The contacts shall be of robust design and have ample cross-section for carrying continuously 30 A for 5KVA AT, 60A for 10 KVA AT, 155A for 25KVA AT, 300A for 50KVA AT and be of positive make type to avoid any sparking. The rotary switch shall be enclosed with a transparent cover to prevent accidental / inadvertent / interference to circuit.

The selector switch shall have five positions:-

- (i) Off
- (ii) Main supply
- (iii) Standby one supply
- (iv) Standby two supply
- (v) Auto

### 5.2.3 CONTACTOR

The contactors shall be of electro-magnetic air break type of robust design having a continuous rating of 240 V a.c 50 Hz, 30 A for 5KVA AT, 60A for 10 KVA AT, 155A for 25KVA AT, 300A for 50KVA AT with 6 sets of auxiliary contacts, 3 of them normally open and the other 3 normally closed. The contacts shall be silver plated, bounce proof and have ample cross-section for carrying the rated current continuously without exceeding the permissible temperature-rise.

### 5.2.4 MINIATURE CIRCUIT BREAKER

Miniature circuit breakers shall be suitable for operation on 240 V ac. 50 Hz and shall have a breaking capacity of 100 kVA. Miniature circuit breakers shall be enclosed in clear acrylic cover to prevent un-authorized operation / interference.

### 5.2.5 BUS BAR

Bus bar shall be made of high conductivity electro-lytic tinned copper supported on LT porcelain insulator. The section of the bus bar shall be of adequate capacity for carrying 30 A for 5KVA AT, 60A for 10 KVA AT, 155A for 25KVA AT, 300A for 50KVA AT continuously.

### 5.2.6 LIGHT EMITTING DIODES (LEDs)

The LEDs shall be provided on the cover of the panel to indicate the availability of supplies. They shall be housed in screwed translucent unbreakable covers moulded from heat resisting material and provided with chromium plated bazels.

3 Nos of LED shall be provided on the panel to indicate as on which supply ( that is on main or standby 1 or standby 2 supply) load is connected.

### 5.2.7 CABLE GLAND

The entry of all wires / cables in to the panel shall be only through suitable glands which shall not allow ingress of vermin , insects etc. in to the panel. For out going wires / cables also, the suitable such cable glands shall be provided by the tenderer.

## 6.0 EARTHING

Earthing of the panel and equipment there shall be as per IS: 3043 (latest edition).

## 7.0 PAINTING

The supporting frame and panel shall be rust-proof and shall be given a primer coat of zinc chromate and two coats of VELLUM colour paint to shade No. 365 of IS:5, while the interior surfaces shall be sprayed with a finishing coat of white paint.

## 8.0 NAME PLATES

8.1 Suitable markings for identification of circuits and position of selector switch shall be engraved on the panel. The schematic diagram, generally as per the drawing attached to this specification, shall be made by engraving on a plate of durable quality and fixed on the inside of the cover of the panel. The engraved portion should be filled with Black/ Red colour.

8.2 Black plastic plate 15 mm wide bearing suitable captions with 3 mm high engraved letters in white colour shall be mounted on top of the panel.

## 9.0 TESTS

### 9.1 GENERAL

9.1.1 Only after all the design and drawings have been approved and clearance given by Research Design and Standards Organization (RDSO)/Chief Electrical Engineer (CEE) to this effect, the manufacturer shall take up manufacture of the prototype unit for RDSO inspection. It is to be clearly understood that any changes required to be done in the prototype unit shall be done expeditiously.

- 9.1.2 Before giving the call to RDSO/CEE for inspection and testing of the prototype of the equipment, the manufacturer shall submit a detailed test schedule consisting of schematic circuit diagrams for each of the tests and nature of the test, venue of the test and the duration of the test and the total number of the days required to complete the tests at one stretch.
- 9.1.3 Once schedule is approved, the tests shall be done accordingly. However, during the process of type testing or even later, RDSO representative reserves the right to conduct any additional test(s) besides those specified therein, on any equipment/sub-system or system so as to test the equipment to his satisfaction or for gaining additional information and knowledge. In case of dispute or any disagreement arises between the manufacturer and RDSO/CEE during the process of testing as regards the type test results, it shall be brought to the notice of the Director General (Traction Installation), RDSO/ CEE as the case may be, whose decision shall be final and binding.
- 9.1.4 In the event of the tests not being carried through to completion at one stretch for any reason attributable to the successful tenderer/ manufacturer and it is required for the representative of the purchaser/ Director General (Traction Installation), Research Designs and Standards Organization, Lucknow, to go again or more number of times to the works of the successful tenderer/ manufacturer or other place(s) for continuing and/or completing the test on the prototype(s) of the equipment, the successful tenderer/ manufacturer shall reimburse to the purchaser/ Director General ( Traction Installation), Research Designs & Standards Organization, Lucknow. The cost of the representative having to visit the works or other place(s) for the test more than once. The cost as claimed by the purchaser/ Director General (Traction Installations), Research Designs & Standards Organisation, Lucknow shall be paid through demand draft to the concerned accounts officer of the Purchaser/Director General (Traction Installation), Research Designs and Standards Organization, Lucknow, shall be advised to the successful tenderer manufacturer.
- 9.2 Type routine and acceptance tests on various equipments shall be carried out as per the following schedule.

#### 9.2.1 **ROTARY SWITCH**

The following tests shall be carried out as per IS:4064 (Part I&II) 1978: In case these tests have already been carried out at a Govt. recognised labs, the test certificates shall be submitted to RDSO/Zonal Rlys for scrutiny & approval.

##### **TYPE TESTS**

- (i) General.
- (ii) Verification of temperature-rise limit.
- (iii) Verification of Dielectric properties.
- (iv) Verification of rated making and breaking capacities.
- (v) Verification of ability to carry the rate short time withstand current.

- (vi) Verification of rated fused short circuit current.
- (vii) Verification of rated short circuit making capacity.
- (viii) Verification of Mechanical endurance.

### **ROUTINE TESTS**

As per provision of Clause 8.3 of IS: 4064, Part I, 1978.

#### **9.2.2 CONTACTOR**

The following tests shall be carried out as per IS: 2959-1985: In case these tests have already been carried out at a Govt. recognised labs, the test certificates shall be submitted to RDSO/Zonal Rlys for scrutiny & approval.

### **TYPE TESTS**

- (i) Verification of temperature-rise limit.
- (ii) Verification of Dielectric properties.
- (iii) Verification of rated making and breaking capacities.
- (iv) Verification of short circuit making and breaking capacities.
- (v) Verification of Mechanical endurance.
- (vi) Verification of operating limits.
- (vii) Verification of ability to withstand over load currents.

### **ROUTINE TESTS**

- (i) Operating tests
- (ii) Dielectric tests

#### **9.1.3 MINIATURE CIRCUIT BREAKERS:-**

The following tests shall be carried out as per IS: 8828-1978: In case these tests have already been carried at a Govt. recognised labs, the test certificates shall be submitted to RDSO/Zonal Rlys for scrutiny & approval.

### **TYPE TESTS**

#### **(a) TEST DUTY -I**

- (i) High voltage test.
- (ii) Over current device calibration test.
- (iii) Temperature rise test.
- (iv) Over load performance test.
- (v) Endurance test.

**(b) TEST DUTY-II**

- (i) Short Circuit capacity test.

**(c) TEST DUTY-III**

- (i) Time/current characteristic test.
- (ii) Flexible Cord test.
- (iii) Shock test.

**ROUTINE TESTS**

- (i) High Voltage test.
- (ii) Over current device calibration test.

**9.2 TESTS ON THE COMPLETE PANEL**

The following checks and tests shall be carried out on the complete panel:-

- (i) Visual & dimensional check.
- (ii) Checking the wiring for correctness and continuity.
- (iii) Voltage test on the panel and the wiring for withstand voltage of 2000V rms to earth for 1 minute.
- (iv) Insulation resistance of the complete wiring with 1000V meggar.
- (v) Endurance / Operation / functional tests on the rated load current: during this test, a rated load shall be connected to the out put terminals for 10 Hours and the function/operation for changeover facility in manual as well as in auto mode of the panel shall be checked for 100 times. This test shall be carried out only one panel at the time of Proto type testing.
- (vi) Measurement of changeover time from one supply to another supply.

**10.0 DRAWINGS AND TECHNICAL DETAILS**

10.1 The tenderer shall furnish schedule of guaranteed performance particulars, for the panel offered in the Performa attached as Annexure-I.

10.2 The following drawings shall be furnished as per Indian Rlys standard in sizes of 210x297 mm are any integral multiple there of for the approval of the purchaser:

- (a) Lay out and general arrangement drawing of the panel showing mounting details of various equipments.
- (b) A sectional view of the rotary switch, together with plan showing mounting details and knob handle position.

- (c) A sectional view of the contactor, together with the plan showing mounting details.
- (d) A sectional view of the miniature circuit breaker together with the plan showing mounting details.

The tenderer shall furnish technical details, name of the manufacturer , country of origin and make of the equipment offered alongwith the drawings.

One soft copy of approved drawings shall be submitted to DG/TI/RDSO/Lucknow/CEE, core, Allahabad.

After the drawings are approved a prototype panel shall be got approved after the test out lined above before taking up the bulk manufacture.

## **11. OPERATION , MAINTENANCE INSTRUCTIONS & TRAINING**

**11.1** The panel shall be a maintenance free relay generally not needing any maintenance, however the tenderer shall mention a maintenance schedule which shall be detailed enough to guarantee failure free service of the relay to the tenderer. The supplier shall supply free of cost 2 copies to the consignee of the Instruction Manuals for operation and maintenance of the equipment. The manuals shall contain full particulars of various components, full dimensioned drawings and circuit diagrams.

**11.2** The Successful tenderer shall develop a maintenance schedule and a trouble shooting chart for effective , reliable and trouble free operation of the panel. The basic maintenance schedule along with the troubleshooting , diagnostic chart shall be submitted to RDSO and approved by RDSO prior to commissioning of the panel for the first time at the site.

## **12.0 WARRANTY**

**12.1** The panel supplied against a purchase order/contract in which this specification is quoted, irrespective of origin individual equipment ( imported / indigenous ) shall be guaranteed for trouble - free and satisfactory performance for a period of 18 months from the date of supply or 12 months from the date of commissioning, whichever period is earlier, details of warranty clause, the extent of responsibility and other relevant aspects shall be included in the purchase order or the contract. The tenderer shall furnish detailed terms and conditions in this regard in his offer.

# ANNEXURE - I

## SCHEDULED OF GURANTEED AND TECHNICAL PARTICULARS

S . N O	Description	Manufacturer details	Unit of measurement
<b>1.0</b>	<b>Particulars of control and distribution panel.</b>		
1.1	Name of the manufacturer		
1.2	Governing RDSO specification		
1.3	Rated control voltage with variation		Volt
1.4	Power consumption.		Watts
1.5	Lower and upper limits of 240 V on which the changeover from one supply to another supply occur.		Volts
1.6	Power frequency withstand voltage for 1 minute		Kv rms
1.7	Dimensions:      Length Width breath		mm mm mm
1.8	IR value of complete wiring		
1.9	Switching time for switching one supply to another supply.		Sec.
<b>2.0</b>	<b>MINIATURE CIRCUIT BREAKER</b>		
2.1	Name of manufacturer		
2.2	Rated voltage		volts
2.3	Rated current		Amp.
2.4	Rated making and breaking capacity of the contact		Amp.
2.5	Short time current carrying capacity of the contacts for 1 sec.		Amp.
2.6	Operating duty.		
<b>3.0</b>	<b>ROTARY SWITCH</b>		
3.1	Name of manufacturer		
3.2	Rated voltage		volts
3.3	Rated current		Amp.
3.4	Rated making and breaking capacity of the contact		Amp.
3.5	Short time current carrying capacity of the contacts for 1 sec.		Amp.
<b>4.0</b>	<b>Air break contactors</b>		

Signature Not  
Verified


Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05'30  
Reason: IREPS-CRIS  
Location: New Delhi

4.1	Name of manufacturer		
4.2	Rated voltage		volts
4.3	Rated current		Amp.
4.4	Rated making and breaking capacity of the contact		Amp.
4.5	Short time current carrying capacity of the contacts for 1 sec.		Amp.
4.6	Operating duty.		
4.7	Nos of NO & NC contacts provided with main contact.		Nos
<b>5.0</b>	<b>BUZZER</b>		
5.1	Name of manufacturer		
5.2	Operating voltage		volts
5.3	Power consumption at rated voltage		watts
5.4	Whether continuously rated for operating voltage		
<b>6.0</b>	<b>CABLE GLAND</b>		
6.1	Name of manufacturer		
6.2	Out side & in side diameter of cable gland.		mm
6.3	Whether protection against ingress of vermin, insects etc ensured		


Signature Not Verified

Digitally signed by  
AKASH KUMAR  
Date: 2026.04.06  
18:38:57 +05'30  
Reason: IREPS-CRIS  
Location: New Delhi

Signature Not Verified

 Digitally signed by AKASH KUMAR  
Date: 2026.04.06 18:38:57 +05'30  
Reason: IREPS-CRIS  
Location: New Delhi

Signature Not Verified

 Digitally signed by AKASH KUMAR  
Date: 2026.04.06 18:38:57 +05'30  
Reason: IRLPS-CRIS  
Location: New Delhi