

OFFICE NAGAR PANCHAYAT MOHAMMDABAD GOHANA- MAU

कार्य का नाम:- वार्ड नं० ६ मु०. सैदपुर में मेन हाइवे से रव पप्पू मारवाडी के मकान तक 700 मीटर 7 मी० ओक्टोगोनल सिंगल आर्म के साथ स्ट्रीट लाइट भूमिगत पाइप केवल के माध्यम से अविष्ठापन का कार्य।

S.I.	Description	Qty.	No.
1	Supply and fixing of 7Mtr. GI octagonal pole of approved make (top dia 70mm, Bottom dia130mm and base plate12mm thick) having 3mm thickness withsingalarm bracket (1 Mtr length each) on RCC foundation including the cost of foundation, foundation bolts, excavation & back filling and Required T&P complete in all respect .(U.P PWDEle S.I NO-641)	35	No.
2	Supply and laying Aluminum conductor P.V.C. insulated armed served sheathed cable 1100 volts grade size 16sqmm. 4 core at a depth of 750mm below ground level over a cushion of 75mm thick sand all around of protected with burnt brick on sides sand on top. Suitable sizeor as directed by engineer incharge complete in respect .(U.P PWD Ele S.I NO-5011)	875	mtr
3	Supply and laying of HDPE pipe 1.5" black for the protection of the cable.(CPWD E&M 2022 S.I NO-14.16.1)	700	mtr
4	Supply and fixing of LED street light fitting having dia cost aluminum body and diffuser with driver setsuitable for110to130 wat confirming to IP /66 with high voltage protection complete in all respects CAT-AAA (U.P PWD Ele S.I NO-1426)	35	No.
5	Supply and fixing making connection of power supply LED fitting 1no 05 Amp MCB 10KA lugs 2.5sqmm 3 core multi standard copper wire fiber plate MCB Tray etc.Complete inallrespects.(U.P PWD Ele S.I NO-1001-289,504f)	35	No.
6	Supply and burying of 600mm dia x 600 meters G.I. plate vertically for earthing with its topat least 3 meters below ground level complete with 20mm dia G.I. pipe and funnel for watering and one earthing lead of one no. 8 to 10 SWG G.I. wire in 15 mm dia G.I. pipe up to switch board (from pronto switch board the cost of G.I. pipe and G.I. wire will be extra) 30cm square C.I. frame with hinged cover masonry housing alternate layers of charcoal/coke and salt at least 150mm thick around etc as per direction of engineer in charge complete in all respect as per drawing (This will apply fo earthing of poles also). (U.P PWD Ele S.I NO-702)	5	No.
7	Supply and erection or factor fabricated and wired metal clad dust and vermin proof floor mount 63 amp TPN-2 NO capacity of automatic street light cubical control pannet double door painted with CTS etccomplete in all respect.(U.P PWD Ele S.I NO-801a(ii))	1	No.
8	S&F of 200 A. 415 V Heavy Duty Double Break HRC fuse type metal clad TPN complete with HRC fuse etc. on angle Iron frame complete in all respect.(U.P PWD Ele S.I NO-347	1	No.
9	Supply & Fixing of electric streep rope light driverNational Flag colour (each length 18M.)Bajaj,Philips,Havells and other Brand with all material labour T&P.	630	mtr

Rate Checked

J. E. (T) . .

P.D.P.W.D. Mau

अधिसासी अधिकारी

नगर पंचायत मुहम्मदाबाद गोहना
जनपद-मऊ

इम्पुद्वी

अध्यक्ष

नगर पंचायत मुहम्मदाबाद गोहना
जनपद-मऊ

अवर अभियन्ता (जल)
नगर पालिका परिषद
मऊनाथ भंजन-मऊ

अधिसासी अभियन्ता,
प्रा०ख०स्व०नि०वि०, मऊ

Scanned with OKEN Scanner