

Validate

Print

Help

**Percentage BoQ**

Tender Inviting Authority:

Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar

Contract No:

Bidder Name :						
<b>PRICE SCHEDULE</b>						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )						
NUMBE	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	53	55
1	<b>SubWork: Source Well</b> Excavation in general in soft material comprising of soft soil, soft murum, sand, hard murum with boulders in wet or dry condition for Head Works i.e. Intake Well, Connecting Pipe, Jack Well, Pump House, Supply Well, etc. for lift 0 to 1.5 M and lead of 150 M including baricating, gurading, disposing off surplus excavated stuff within a radius of 0.5 km. as directed by Engineer-in- charge, etc. complete excluding refilling. Soft Strata Lift 0.00 to 6.00 m	0.00	Cubic Meter	322.30	<b>0.00</b>	INR Zero Only
2	B) Hard Strata Lift 7.00 to 12.00 M.	147.80	Cubic Meter	777.70	<b>114944.06</b>	INR One Lakh Fourteen Thousand Nine Hundred & Forty Four and Paise Six Only
6	Lift 9.00 to 10.50 M.	36.95	Cubic Meter	178.20	<b>6584.49</b>	INR Six Thousand Five Hundred & Eighty Four and Paise Forty Nine Only
7	Lift 10.50 to 12.00 M.	36.95	Cubic Meter	207.90	<b>7681.91</b>	INR Seven Thousand Six Hundred & Eighty One and Paise Ninety One Only
8	Lift 12.50 to 13.50 M.	36.95	Cubic Meter	237.60	<b>8779.32</b>	INR Eight Thousand Seven Hundred & Seventy Nine and Paise Thirty Two Only
9	Lift 13.50 to 15.00 M.	36.95	Cubic Meter	267.30	<b>9876.74</b>	INR Nine Thousand Eight Hundred & Seventy Six and Paise Seventy Four Only

**Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar**

**Contract No:**

Bidder Name :						
10	Dewatering the excavated trenches and pools of water in the building trench/ pipe line trenches, well works by using pumps and other lifting devices including desposing of water to safe distance as directed by engineer-in-charge ( incl. cost of machanary, labour, fuel ) etc. comp.	500.00	Bhp.	84.70	<b>42350.00</b>	INR Forty Two Thousand Three Hundred & Fifty Only
11	Desiting the supply Well, Intake well/ head wors sump of water supply/ sewerage works etc. in wet or dry cindition including lifts upto 9M and lead upto 150 M as required beyond the work site stacking spreading including necessary guarding etc. comp.	12.32	Cubic Meter	818.40	<b>10082.69</b>	INR Ten Thousand &Eighty Two and Paise Sixty Nine Only
12	:Providing and casting in situ C. C. of trap/granite/quartzite/ gneiss metal of approved quality for RCC work as per detailed drawings and designs or as directed by Engineer-in-charge including normal dewatering, plywood form work,bully/steel prop ups, compaction, finishing the formed surfaces with CM 1:3 of sufficient minimum thickness to give a smooth and even surface wherever necessary or roughening if special finssh is to be provided and curing, etc. complete. (By weigh batching and mix design for M-250 and M-300 only. Use fo L&T, A.C. C., Ambuja, Birla Gold, Manikgad, Rajashree, etc. cement is permitted .) For RCC M-200 grade vertical wall	4.52	Cubic Meter	9132.60	<b>42092.95</b>	INR Forty Two Thousand &Ninety Two and Paise Ninety Five Only
13	Providing and fixing in position steel bar reinforcement of various diameters for RCC piles, caps, footings, foundation, slabs, beams, columns, canopies, staircases. newels, chajjas, lintels, pardies, copings, fins, arches, etc. as per detailed designs, drawings and schedules; including cutting, bending, hooking the bars, binding with wires or tack welding and supporting as required, etc. complete. (including cost of binding wire)	0.18	MT	73502.00	<b>13230.36</b>	INR Thirteen Thousand Two Hundred & Thirty and Paise Thirty Six Only

Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar

Contract No:

Bidder Name :						
14	Providing structural steel work in single stanchions composed of RSJ, channel, etc, with caps, bases, mild steel plates, angles, brackets, cleats, gusset plates, anchor bolts, etc. as per detailed design and drawing or as directed by Engineer-in-charge including cutting, fabrication, hoisting, erecting, fixing in position, making riveted/ bolted / welded connections and one coats of anticorrosive paint and over it two coats of oil painting, etc. complete.	0.47	MT	70017.00	<b>32907.99</b>	INR Thirty Two Thousand Nine Hundred & Seven and Paise Ninety Nine Only
15	Providing and Drilling Horizontal Bore for increasing storage capacity including all transportation charges of Ridge with labour charges etc.150mm	120.00		375.10	<b>45012.00</b>	INR Forty Five Thousand & Twelve Only
16	Giving Yeild Test ..... etc.comp. and Designing of Well	1.00		3311.00	<b>3311.00</b>	INR Three Thousand Three Hundred & Eleven Only
17	<b>Subwork: Swich Room</b> Excavation in soft material such as ablack cotton soil, Sand, soft and murum in dry or wet condition with all leads and lifts with lighting, guarding disposing of the surplus excavated stuffs as directed.	6.91	Cubic Meter	165.00	<b>1140.15</b>	INR One Thousand One Hundred & Forty and Paise Fifteen Only
18	Providing and laying in situ P.C.C.( 1:2:4 ) with 12 mm. to 20 mm. guage trap metal with all leads and lifts etc. comp. with ramming and curring etc.comp.	1.17	Cubic Meter	6204.00	<b>7258.68</b>	INR Seven Thousand Two Hundred & Fifty Eight and Paise Sixty Eight Only
19	Providing U.C.R. Masonary in II nd sort in C.M. 1:6 for foundation & plinth with 45 % mortar cement pointing in C.M. 1 : 3 to out side exposed from with scaffolding and curring etc comp.	7.08	Cubic Meter	5232.70	<b>37047.52</b>	INR Thirty Seven Thousand & Forty Seven and Paise Fifty Two Only
20	Providing and constructing B.B. Masonary IInd sort in C.M. 1:6 with all leads and leafs for super mstructure incl. racking outjoints watering scaffolding and curring etc.	5.95	Cubic Meter	8327.00	<b>49545.65</b>	INR Forty Nine Thousand Five Hundred & Forty Five and Paise Sixty Five Only
21	Providing and fixing Mild steel Grilled door of verious sizes as per detailed drawing with or without ventilators incl. fabrication, glazing with plain / obscured glass panes and approved type and quality kick plates all fixtures and fastning.(Double leaf panl Door)	1.62	Square meter	5941.00	<b>9624.42</b>	INR Nine Thousand Six Hundred & Twenty Four and Paise Forty Two Only

**Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar**

**Contract No:**

Bidder Name :						
22	Providing and fixing steel Window of verious sizes as per detailed derawing with or without ventilators incl. fabrication, glazing with plain / obscured glass panes and approved type and quality kick plstes all fixtures and fastning.	1.08	Square meter	4668.40	<b>5041.87</b>	INR Five Thousand &Forty One and Paise Eighty Seven Only
23	Providing and filling plinth bellow flooring with hard murum brought out side in layer of 22 mm. incl. watering ramming etc. comp.as directed.	1.89	Cubic Meter	605.00	<b>1143.45</b>	INR One Thousand One Hundred & Forty Three and Paise Forty Five Only
24	Providing and laying rough shahabad stone for flooring of 40-50 mm. th. in plain pattern on a bed of 1:4 C.M. ( 20 mm. Th. ) incl. cement float for mortar bedding cement pointing in cement mortar 1 :3 stricking joints, curring etc. comp.	5.15	Square meter	763.40	<b>3931.51</b>	INR Three Thousand Nine Hundred & Thirty One and Paise Fifty One Only
25	Providing and placing R.C.C. In 1:1.5:3 proportional for 12 mm. to 19 mm. guage trap metal with all lead and leifts incl. form work ramming , curring, watering etc. comp. RCC Work M 20 ( beam & landiq )	0.09	Cubic Meter	8673.50	<b>780.62</b>	INR Seven Hundred & Eighty and Paise Sixty Two Only
26	RCC Work M 20 ( Chajjas)	0.14	Cubic Meter	9273.00	<b>1298.22</b>	INR One Thousand Two Hundred & Ninety Eight and Paise Twenty Two Only
27	RCC Work M 20 ( Slab)	1.08	Cubic Meter	9312.60	<b>10057.61</b>	INR Ten Thousand &Fifty Seven and Paise Sixty One Only
28	Providing and fabricating tor steel. reinforcement for RCC work as per design and drawing incl cutting , binding wire etc. comp. (MJP DSR-2021-22)	0.086	Metric Tonne	73502.00	<b>6321.17</b>	INR Six Thousand Three Hundred & Twenty One and Paise Seventeen Only
29	Providing and applying cement plaster 20 mm. th. In c m 1:4 with smooth finishing from inside and out side faces of the room incl. watering curring, scaffolding etc. comp.in two coat For Inside	27.24	Square meter	503.80	<b>13723.51</b>	INR Thirteen Thousand Seven Hundred & Twenty Three and Paise Fifty One Only
30	Providing and applying cement plaster 20 mm. th. In c m 1:4 with smooth finishing from inside and out side faces of the room incl. watering curring, scaffolding etc. comp.in two coat For Outside	47.54	Square meter	503.80	<b>23950.65</b>	INR Twenty Three Thousand Nine Hundred & Fifty and Paise Sixty Five Only

Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar

Contract No:

Bidder Name :						
31	Providing and applying color washing of approved quality to ceiling thr three coats incl. scaffolding, brushing cleaning etc. comp.	5.15	Square meter	12.10	<b>62.32</b>	INR Sixty Two and Paise Thirty Two Only
32	Pro. and applying two coats oil bound distemper of approvedd quality and shed in three coats from inside faces of the room incl. cleaning the surface scaffolding brushing etc comp. Outside	24.24	Square meter	56.10	<b>1359.86</b>	INR One Thousand Three Hundred & Fifty Nine and Paise Eighty Six Only
33	Pro. and applying two coats oil bound distemper of approvedd quality and shed in three coats from inside faces of the room incl. cleaning the surface scaffolding brushing etc comp. Outside	45.00	Square meter	47.30	<b>2128.50</b>	INR Two Thousand One Hundred & Twenty Eight and Paise Fifty Only
34	Electrification charges for switch room.	1.00	Job.	2000.00	<b>2000.00</b>	INR Two Thousand Only
35	<b>Subwork: Pumping Machinery</b> Providing , errecting giving test & trial of submercibale pump sets and allied equipments as under the rate are inclusive of follwing items. Monoblock Pump Set 5 HP ( PM-2-1-2)	2.00	Number	23006.16	<b>46012.32</b>	INR Forty Six Thousand & Twelve and Paise Thirty Two Only
36	Panel Board	1.00	Square meter	2264.00	<b>2264.00</b>	INR Two Thousand Two Hundred & Sixty Four Only
37	Switch	1.00	Number	322.00	<b>322.00</b>	INR Three Hundred & Twenty Two Only
38	ELCB	1.00	Number	2833.00	<b>2833.00</b>	INR Two Thousand Eight Hundred & Thirty Three Only
39	Pilot Lamp	1.00	Number	597.00	<b>597.00</b>	INR Five Hundred & Ninety Seven Only
40	Volt meter	1.00	Number	1310.00	<b>1310.00</b>	INR One Thousand Three Hundred & Ten Only
41	Ammeter	1.00	Number	1366.00	<b>1366.00</b>	INR One Thousand Three Hundred & Sixty Six Only

**Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar**

**Contract No:**

Bidder Name :						
42	Cabel 3 Core 4 SQM	35.00	Number	128.00	<b>4480.00</b>	INR Four Thousand Four Hundred & Eighty Only
43	Earthing	1.00	Number	4238.00	<b>4238.00</b>	INR Four Thousand Two Hundred & Thirty Eight Only
44	Drop Pipe 50 mm medium	20.00	Meter	330.00	<b>6600.00</b>	INR Six Thousand Six Hundred Only
45	Supply Labour Charges	20.00	Meter	79.20	<b>1584.00</b>	INR One Thousand Five Hundred & Eighty Four Only
46	Capacitor 2x KVAR	1.00	KVAR	343.00	<b>343.00</b>	INR Three Hundred & Forty Three Only
47	Starter F.A.S.D Supplying and erecting Fully Automatic Star Delta starter to operate squirrel cage induction motor working on 380- 440 Volt, 3 phase, 50 Hz with no volt coil, over load element, and ON - OFF push buttons, with necessary material and connected to supply, etc complete. Starter with original sheet steel encloser	1.00	Number	1858.00	<b>1858.00</b>	INR One Thousand Eight Hundred & Fifty Eight Only
48	MSEB Provision	0.00	Job.	150000.00	<b>150000.00</b>	INR One Lakh Fifty Thousand Only
49	<b>Subwork: Rising Main</b> Providing and supplying in standard length Polyethylene pipe conforming with IS specification no. 4984/14151/ 12786/ 13488 with necessary jointing material like mechanical connector i.e. thread/ insert joint/ quick release coupler joints/ compression fitting joint or flanged joint excluding coupler/ specials incl. All , transportation, freight charges, inspection charges, loading, conveyance to the Depatmental stores/site and stacking the same in closed shade daily protected from sun rays and rain including cost of jointing material i.e. solvent cement, etc.complete. 110 MM ( 6 kg / Sqcm ) HDPE Pipe	335.00	Running Meter	295.00	<b>98825.00</b>	INR Ninety Eight Thousand Eight Hundred & Twenty Five Only

**Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar**

**Contract No:**

Bidder Name :						
50	Providing and supplying HDPE special suitabale for HDPE pipes including cost of all taxes transformation to site of work, loading, unloading, stacking, etc. compd. 5% cost of pipes.	0.00	Running Meter	4941.25	<b>4941.25</b>	INR Four Thousand Nine Hundred & Forty One and Paise Twenty Five Only
51	Providing and supplying Air valve as per MJP standered specifications of approved make and quality of follwing dimeter incl. All taxes (central and local )railway frieght,insepection charges, unloading from railway wagons loading in to trucks transportation up to departmental store/site unloading ans stacking etc compd. Air valves Singal Ball Flanged/Screwed Type -PN-1 AIR VALVE 25 MM	1.00	Number	1054.00	<b>1054.00</b>	INR One Thousand & Fifty Four Only
52	Providing and supplying ISI mark C.I.D.F.Sluice valves and butterfly valves of incl. All taxes (central and local )railway frieght,insepection charges, unloading from railway wagons loading in to trucks transportation up to departmental store/site unloading and stacking etc compd. Sluice valves as per IS-780and 2906-1984.--- 100 MM Dia. Non Return Valve PN1	1.00	Number	5713.00	<b>5713.00</b>	INR Five Thousand Seven Hundred & Thirteen Only
53	Exavation for pipe trenches in follwing types of srata incl. removing the excavated material up to a distance of 50 m.and lift as bellow, stacking and spreading, as directed, normal dewatering, preparing the bed for foundation and excluding back filling etc. compt. a) Soils of all types sand, gravel and soft murum	60.30	Cubic Meter	165.00	<b>9949.50</b>	INR Nine Thousand Nine Hundred & Forty Nine and Paise Fifty Only
54	b) In Hard murum	60.30	Cubic Meter	187.00	<b>11276.10</b>	INR Eleven Thousand Two Hundred & Seventy Six and Paise Ten Only
55	c) In HMB	40.20	Cubic Meter	211.20	<b>8490.24</b>	INR Eight Thousand Four Hundred & Ninety and Paise Twenty Four Only
56	d) In SR	20.10	Cubic Meter	629.20	<b>12646.92</b>	INR Twelve Thousand Six Hundred & Forty Six and Paise Ninety Two Only

**Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar**

**Contract No:**

Bidder Name :						
57	Lowering and laying, jointig with PVC pipes and specials of follwing class and diameter incld. Cost of conveyance from stores from stores to site of works incld. Cost of all labour, material, except cement solvent, rubber rings giving saticefactory hydralic testing as per IS code,etc.comptd.(with solvent cement joints.) 110mm (6kg/sqcm) HDPE Pipe	335.00	Running Meter	77.00	<b>25795.00</b>	INR Twenty Five Thousand Seven Hundred & Ninety Five Only
58	Lowering, laying and jointing in position follwing C.I.D.F. Sl. Valves incl. Cost of all labour, jointing material, incl. nut bolt and giving saticefactory hydralic testing etc. comp. (Rate of all classes of valves.) 100 MM Dia Non Return Valve PN1	1.00	Number	2499.20	<b>2499.20</b>	INR Two Thousand Four Hundred & Ninety Nine and Paise Twenty Only
59	Providing and constucting Brick Bat Masonary chember with 15 cm. Thick. 1:3:6 pro. P.C.C.bedding, excluding excavation, B.B.Masonry chember in cm.1:5,-100 mm.Tk. Precast RCC.frame and cover etc. compld. As directed by engineer a) Size 60 X 45 X 90 cm.	1.00	Number	7254.50	<b>7254.50</b>	INR Seven Thousand Two Hundred & Fifty Four and Paise Fifty Only
60	Providing and fixing in position Air valevs Shaft incld. Providing and fixing G.I.medium class or 6 mm.tk.M.S. pipe shart 2.7M. c.c. 150 mm. Tk. arround the air valves tee incl. encasing of vertical shaft in PCC.M-150 as shown in pipe design togather with providing and making glanged joints where required and fixing of air valves over the shaft excluding cost of air valves and branch flanged air valves tee etc.compt.as per type design and as directed by Engineer-in-charge for following dimeter of pipe lines.	1.00	Number	6135.80	<b>6135.80</b>	INR Six Thousand One Hundred & Thirty Five and Paise Eighty Only
61	Refilling the trenches with soft material first over pipe line and then hard material in 15 cm.layers with all leads and lifts including consilidation, surcharging etc.	177.72	Cubic Meter	92.40	<b>16421.33</b>	INR Sixteen Thousand Four Hundred & Twenty One and Paise Thirty Three Only

**Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar**

**Contract No:**

Bidder Name :						
62	<b>Subwork: Distribution System</b> Providing and supplying in standerd length ISI mark rigid unplasticised PVC-pipes suitable for potable water with solvent cement joints incl. Cost of couplers, as per ISI specification no. 4985/1988 incl. All local and central taxes, transportation, freight charges, inspection charges, loading, conveyance to the depatmental stores/site and stacking the same in closed shade daily protected from sun rays and rain including cost of jointing material i.e. solvent cement, etc.complete.(selffit type to be jointed with cement solvent ) 90 mm dia PVC 4 Kg/Sqcm	630.00	Running Meter	146.00	<b>91980.00</b>	INR Ninety One Thousand Nine Hundred & Eighty Only
63	75 mm dia PVC 4 Kg/Sqcm	1035.00	Running Meter	105.00	<b>108675.00</b>	INR One Lakh Eight Thousand Six Hundred & Seventy Five Only
64	Providing and supplying PVC special suitabale for PVC pipes including cost of all taxes transformation to site of work, loading, unloading, stacking, etc. comp. 10% of Item No. 1	1.00	Job.	20065.50	<b>20065.50</b>	INR Twenty Thousand & Sixty Five and Paise Fifty Only
65	Providing and supplying ISI mark C.I.D.F.Sluice valves and butterfly valves of incl. All taxes (central and local )railway frieght,insepection charges, unloading from railway wagons loading in to trucks transportation up to departmental store/site unloading and stacking etc compd. Sluice valves as per IS-780and 2906-1984.-- 65 MM Dia. C I D F SI. Valve Valve PN1	1.00	Number	4977.00	<b>4977.00</b>	INR Four Thousand Nine Hundred & Seventy Seven Only
66	80 mm C.I.D.F. SI. Valves PN1	2.00	Number	5132.00	<b>10264.00</b>	INR Ten Thousand Two Hundred & Sixty Four Only
67	Exavation for pipe trenches in follwing types of srata incl. removing the excavated material up to a distance of 50 m.and lift as bellow, stacking and spreading, as directed, normal dewatering, preparing the bed for foundation and excluding back filling etc. compt. a) Soils of all types sand, gravel and soft murum	299.70	Cubic Meter	165.00	<b>49450.50</b>	INR Forty Nine Thousand Four Hundred & Fifty and Paise Fifty Only
68	b) In Hard murum	299.70	Cubic Meter	187.00	<b>56043.90</b>	INR Fifty Six Thousand & Forty Three and Paise Ninety Only

**Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar**

**Contract No:**

Bidder Name :						
69	c) In HMB	199.80	Cubic Meter	211.20	<b>42197.76</b>	INR Forty Two Thousand One Hundred & Ninety Seven and Paise
70	c) In S.R.	99.90	Cubic Meter	629.20	<b>62857.08</b>	INR Sixty Two Thousand Eight Hundred & Fifty Seven and Paise
71	Lowering and laying, jointig with PVC pipes and specials of folling class and diameter incld. Cost of conveyance from stores from stores to site of works incld. Cost of all labour, material, except cement solvent, rubber rings giving saticefactory hydraulic testing as per IS code,etc.comptd.(with solvent cement joints.) 90 mm dia PVC 4 Kg/Sqcm	630.00	Running Meter	34.10	<b>21483.00</b>	INR Twenty One Thousand Four Hundred & Eighty Three Only
72	75 mm dia PVC 4 Kg/Sqcm	1035.00	Running Meter	27.50	<b>28462.50</b>	Twenty Eight Thousand Four Hundred & Sixty Two and Paise Fifty Only
73	Lowering, laying and jointing in position follwing C.I.D.F. Sl. Valves incl. Cost of all labour, jointing material, incl. nut bolt and giving saticefactory hydraulic testing etc. comp. (Rate of all classes of valves.) 65 MM Dia Non Return Valve PN1	1.00	Number	1376.10	<b>1376.10</b>	INR One Thousand Three Hundred & Seventy Six and Paise Ten Only
74	80 MM Dia Non Return Valve PN1	2.00	Number	1911.80	<b>3823.60</b>	INR Three Thousand Eight Hundred & Twenty Three and Paise Sixty Only
75	Providing and constucting Brick Bat Masonary chember with 15 cm. Thick. 1:3:6 pro. P.C.C.bedding, excluding excavation, B.B.Masonry chember in cm.1:5,-100 mm.Tk. Precast RCC.frame and cover etc. compld. As directed by engineer a) Size 60 X 45 X 90 cm.	3.00	No	7254.50	<b>21763.50</b>	INR Twenty One Thousand Seven Hundred & Sixty Three and Paise Fifty Only
76	Rifilling the trenches with available excavated stuff with soft material in 15cm.over the pipe line and thene hard murum in15cm. Layer with all lead and lifts incl.consolidation, etc.compt.	890.52	No	92.40	<b>82284.05</b>	INR Eighty Two Thousand Two Hundred & Eighty Four and Paise Five Only

Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar

Contract No:

Bidder Name :						
77	<p><b>Subwork: R.C.C E.S.R.</b>                      Designing ( aesthetically ) and constructing RCC elevated survice resorvoirs of follwing capacity with RCC standing consisting of columns, internal bracings spaces vertically not more than 4.50 m. c/c. for ESR having capacity above 500 m3 and more than 6.00 m c/c. for ESR having capacity above 500 m3 including excavation in all types of strata, foundation, concreat, cement plaster with water proofing compound to the inside face of the container including refilling depositing of the surplus stuff within a lead of 50 m. all labour and material charges incl. lowering, laying, errecting , hosting, and jointing of pipe assembly of inlet, outlet, washout, overflow and bypass arrangement as per providing and fixing accessories such as M.S. ladder, C.I. Manhol covers and frame, water level indicator, lightning conductor, G.I. pipe ralling arround walk way and top slab, providing spiral stair case from ground level to roof level, M.S.Grill gate of 2.00m. ht. with locking arrangement, B.B. Masonary chember for all valves, ventilating shafts. ENTIRE STRUCTURE IN M300 MIX ONLY For 24000 Lits. Work Completed Slab Level</p>	1.00	Job.	240175.00	<b>240175.00</b>	INR Two Lakh Forty Thousand One Hundred & Seventy Five Only
78	<p>providing and supplying ISI standerd CI Doubel Flanged pipes includeall taxes (central and local ) railway freight, insurance, unloading from railway wgon, loading into the truck transport to store / site, unloading, etc.completed as-directions of Engineer-in- charge. G.I.pipe 100 SI Valves</p>	12.00	RMT	785.00	<b>9420.00</b>	INR Nine Thousand Four Hundred & Twenty Only
79	G.I.pipe 80 SI Valves	24.00	RMT	551.00	<b>13224.00</b>	INR Thirteen Thousand Two Hundred & Twenty Four Only
80	<p>Providing and supplying ISI standerd markes C.I.D.F. valves of follwing dia. Including all taxes(Central and local ) railway freight, inspection charges-unloading from railway wagon, loading into the truck, transportation upto depart-mental stores/site, unloading, stacking, etc. complete. 100 mm dia SI Valves</p>	1.00	No.	6835.00	<b>6835.00</b>	INR Six Thousand Eight Hundred & Thirty Five Only

**Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar**

**Contract No:**

Bidder Name :						
81	80 mm dia SI Valves	2.00	No.	5132.00	<b>10264.00</b>	INR Ten Thousand Two Hundred & Sixty Four Only
82	Providing and supplying CI. Flanged (ISI mark ) S and S special incl. all taxes (central and local )railway freight, inspection charges insurance frome railway vagon, loading into the truck, transportation to store/ site, unloading stacking etc. complet. (Upto 150 mm.)	40.00	kg	64.00	<b>2560.00</b>	INR Two Thousand Five Hundred & Sixty Only
83	Royalty	1.00	No	10000.00	<b>10000.00</b>	INR Ten Thousand Only
84	Flow Meter	1.00	No	15532.00	<b>15532.00</b>	INR Fifteen Thousand Five Hundred & Thirty Two Only
85	<b>Sub Work-ESR Repairing</b> Providing internal cement plaster 6mm thick in a single coat in cement mortar 1:3 eithout neeru finish to concrete surface in all position incl. scaffolding and curing etc.	67.71	Square meter	215.60	<b>14598.28</b>	INR Fourteen Thousand Five Hundred & Ninety Eight and Paise Twenty Eight Only
86	Providing and aaplying epoxy oaint of approved make to concrete surface of RCC ESR any other structure incl cleaning the surface be scrapping and air blowers to the satisfaction of engineer in charge necesarry scaffolding etc.	42.59	RMT	829.00	<b>35308.77</b>	INR Thirty Five Thousand Three Hundred & Eight and Paise Seventy Seven Only
87	Providing and fixing in position M.S. ladder 0.50 M wide consisting of 75X10 mm M.S. flats as stringers and 16mm dia M.S. bars in double rows as steps placed at 25 cm/ c incl. cost of material and labour involved welding, anchoring and applying 3 coat of anti- corrosive paint etc.	18.00	RMT	1493.00	<b>26874.00</b>	INR Twenty Six Thousand Eight Hundred & Seventy Four Only
88	Providing pressure grouting at a pressure of 0.56 kg/sqcm in required row/zigzag fashion as specified at 1.5 M inreval as per site conditions to stop leakages through water retaining structures to the entire satisfaction of the engineer in charge incl. material compund hardening materials compressor equipment incl. scaffolding smooth finishing etc.	60.00	Bag	1023.00	<b>61380.00</b>	INR Sixty One Thousand Three Hundred & Eighty Only

**Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar**

**Contract No:**

Bidder Name :						
89	Providing and supplying ISI standard CI double flanged pipes include all taxes (central and local) railway, freight, insurance, unloading from railway wagon, loading into the truck transport to store /site unloading etc. completed as directions of engineer in charge	30.00	Rmt	640.80	<b>19224.00</b>	INR Nineteen Thousand Two Hundred & Twenty Four Only
90	Providing and fixing G.I. pipe railing having 1.0 M height consisting 50x50x6 mm M.S. angles as verticals at 1.5 M c/c and additional posts at every corner with 3 rows of 25 mm dia G.I. pipes of medium class variety as horizontal and painting 3 coats oil paint over 1 coat at anticorrosive paint of approved colour shade incl. cost of all labour transporting bends to curved shape etc. comp.	45.00	Rmt	916.00	<b>41220.00</b>	INR Forty One Thousand Two Hundred & Twenty Only
91	Providing and supplying double flange sluice valve conforming for IS 2906 / 14846 incl. worm gear arrangement as per test pressure stainless steel spindle cap including all statutory duties and taxes such. 80 mm dia sl valve	3.00	No	5132.00	<b>15396.00</b>	INR Fifteen Thousand Three Hundred & Ninety Six Only
92	Lowering and laying and joining in position following CIDF Reflux, butterfly valves and sluice valves incl. cost all all labours jointing material incl. nutbolts and giving satisfactory hydraulic testing etc copm. 80 mm dia sl valve	3.00	No	1911.80	<b>5735.40</b>	INR Five Thousand Seven Hundred & Thirty Five and Paise Forty Only

Name of Work: Constructing Rural Water Supply Scheme at village Udepur Mothe Tal: Akkalkuwa Dist: Nandurbar

Contract No:

<b>Bidder Name :</b>						
93	Providing and constructing chamber of clear inside size as below in B.B. masonry II nd sort in CM (1:6), 15 mm thick wall with 100 mm thick cemnet plaster	3.00	No	7254.50	<b>21763.50</b>	INR Twenty One Thousand Seven Hundred & Sixty Three and Paise Fifty Only
94	Providing appyilng colour wash of approved colour and shade in two coats to new surface incl. scaffolding brushing and brooming down	196.81	Sq.M	15.40	<b>3030.87</b>	INR Three Thousand &Thirty and Paise Eighty Seven Only
95	Trial Run For 3 Months	3.00	Months	78732.00	<b>78732.00</b>	INR Seventy Eight Thousand Seven Hundred & Thirty Two Only
<b>Total in Figures</b>					<b>2185054.69</b>	INR Twenty One Lakh Eighty Five Thousand &Fifty Four and Paise Sixty Nine Only
<b>Quoted Rate in Figures</b>			<b>Select</b>		<b>2185054.69</b>	INR Twenty One Lakh Eighty Five Thousand &Fifty Four and Paise Sixty Nine Only
<b>Quoted Rate in Words</b>			<b>INR Twenty One Lakh Eighty Five Thousand &amp;Fifty Four and Paise Sixty Nine Only</b>			