



भारत सरकार
Government of India
केन्द्रीय लोक निर्माण विभाग
Central Public Works Department



कार्यपालक अभियंता का कार्यालय - कण्णूर
अभिलाश पर्यटक गृह भवन,
रेलवे स्टेशन रोड
कण्णूर, केरल - 670 001

O/o Executive Engineer-Kannur
CPWD, 2nd Floor Bldg No.CB-40/1143,
Abhilash Tourist Home Building,
Railway Station Road, Kannur, Kerala - 670 001

PH : 0497-2967449	E mail: eekannur@gmail.com	NIC mail knree.cpwd@gov.in	Web:www.cpwd.nic.in
सं: 54(1)/ क. के. म. /2026/ 799 (हि)			दिनांक: 16 /07/2026

NOTICE RE - INVITING QUOTATION

Sealed quotations are re-invited by the Executive Engineer-Kannur, Central PWD, Kannur, 2nd Floor Bldg, No.CB-40/1143, Abhilash Tourist Home Building, Railway Station Road, Kannur, Kerala - 670 001 on behalf of the President of India for the following work from eligible contractors. The quotations can be collected from the O/o Undersigned on all working days up to 11 am on 22.07.2026. The quotations will be received upto 3.00 pm on 22.07.2026 and shall be opened at 3.30 pm on 22.07.2026.

Name of Work:- Providing Pre-coated Galvanized iron profile colour sheet roofing, Interior & Exterior paint work including repairs etc at Kendriya Vidyalaya, Keltron Nagar, Mangattuparamba, Kannur. SH: Providing glass windows in Staircase as per Fire norms in KV Keltron Nagar, Kannur.


Sl. No	Description	Quantity	Unit	Rate in Rs.	Amount Rs.
-----Separate Schedule attached-----					
Total					

TERMS AND CONDITIONS:

1. The undersigned reserves the right to cancel this work order without assigning any reason and the agency/ contractor shall not have any claim over such cancellation.
2. The intending quotationer shall have to submit an earnest money deposit (EMD) amounting to Rs.5,000/- (Rupees Twenty Thousand only) by way of demand draft/FDR drawn in favour of the Executive Engineer, CPWD, Kannur from Nationalized / Scheduled Bank payable at Calicut, Should be remitted along with the sealed quotation in a separate cover. The quotation and EMD shall be placed in

- separate sealed cover marking "Quotation" and "EMD" and both shall be placed in another sealed cover. Quotations without EMD amounting to Rs.5,000/- (Rupees Twenty Thousand only) will be summarily rejected and will not be opened.
3. Deposit made by unsuccessful quotationers will be refunded immediately after opening.
 4. The EMD of the lowest quotationer will be refunded only after satisfactory completion of the work. The decision of the Engineer-in-charge regarding completion of the work shall be final.
 5. The time of completion of work shall be 20 days from the date of issue of work order.
 6. The contractor shall make his own arrangement for water and electricity if necessary.
 7. The quotationer shall be liable to pay statutory taxes as applicable.
 8. The work shall be carried out during night time/on holidays for which nothing extra shall be payable.
 9. Condition for work order CPWD-11 shall be applicable to the extent of its relevance.
 10. No labourers shall be allowed to stay in the camp after the working hours.
 11. No damage shall be caused to the existing structures, public amenities, electrical lines etc. If any damage occurs the quotationer shall rectify the same at his risk and cost.
 12. The quotationer shall be responsible for the safety of the work men engaged.
 13. The quotationer shall be responsible for any mishap during the execution of the work.
 14. The payment shall be made through PFMS by Executive Engineer- Kannur, CPWD, Kannur.
 15. Power and water supply shall be arranged by the quotationer for doing the work.
 16. The EMD of the lowest quotationer shall be forfeited by the Executive Engineer if the progress of the work is slow or if the work is not completed within the stipulated period of completion.

Quotationer


Executive Engineer

Copy to:

1. All eligible contractors
2. The Assistant Engineer, KaCSD III, CPWD, Kannur for information w.r.to. letter No.23(151)/KaCSD-III/2026/322 dated 01.06.2026.
3. Accounts Branch.
4. Notice Board /<https://etender.cpwd.gov.in>


Executive Engineer

SCHEDULE OF QUANTITY

Name of Work: Providing Pre-coated Galvanized iron profile colour sheet roofing, Interior & Exterior paint work including repairs etc at Kendriya Vidyalaya, Keltron Nagar, Mangattuparamba, Kannur. SH: Providing glass windows in Staircase as per Fire norms in KV Keltron Nagar, Kannur.

SL. No	Description	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	WOOD AND P.V.C. WORK				
1.1	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete :				
1.1.1	100x10 mm	6.00	Each		
1.2	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete:				
1.2.1	100 mm	6.00	Each		
2	FINISHING				
2.1	12 mm cement plaster of mix :				
2.1.1	1:6 (1 cement: 6 fine sand)	4.00	Sqm		
2.2	15 mm cement plaster on the rough side of single or half brick wall of mix:				
2.2.1	1:6 (1 cement: 6 fine sand)	4.00	Sqm		
2.3	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade:				
2.3.1	New work (Two or more coats applied @ 1.43 Itr/10 sqm over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm)	4.00	Sqm		

2.4	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.				
2.4.1	Two coats	4.00	Sqm		
3	DISMANTLING AND DEMOLISHING				
3.1	Demolishing stone jali manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.				
3.1.1	In cement mortar	6.00	Cum		
4	ALUMINIUM WORK				
4.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :				
4.1.1	For fixed portion				
4.1.1.1	Powder coated aluminium (minimum thickness of powder coating 50 micron)	36.00	Kg		

4.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)				
4.1.2.1	Powder coated aluminium (minimum thickness of powder coating 50 micron)	36.00	Kg		
4.2	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item):				
4.2.1	With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm)	6.00	Sqm		
5	Stone work with neatly dressed laterite stone of size 30 x 20 x 20cm in Superstructure above plinth level upto floor V level in cement mortar 1:6 (1 cement :6 coarse sand)	0.40	Cum		
	Total				

Quotationer


Executive Engineer