

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/ICE(Engg)/IIIID/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.	GETCO STANDARD APPROVAL	Rev. No	Date	Page No
GETCO/MQP/20-21/TOWER&SS STRUCTURES	STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV	0	20.11.2020	1 of 13

1. RAW MATERIAL INSPECTION

S.No	Component / Operation & Description of Test	Sampling Plan with basis	Ref. Doc & Acceptance norm	Record Format	Testing Agency			Remarks
					M	C	TPIA	
1	Raw Materials							
1.1	Structural Steel (Angles, Flats, Plates, Channels and Bars) as per IS 2062 Pipe – IS 1161 /1239		IS 2062 E-350 For HT IS 2062 E-250 A For MS					Steel to be procured from prime producers such as SAIL, TISCO, RINL, JINDAL etc. or GETCO approved retailer.
1.1.1	Physical Properties/ Mechanical properties		IS 2062 : 2011					
(a)	Tensile strength	1 Sample/ 40 MT for each type.	Annexure-A	MTC	P	R	-	MTC review at the time of final inspection
(b)	Test For Yield Stress	- Do -	- Do -	MTC	P	R	-	- Do -
(c)	Percentage Elongation	- Do -	- Do -	MTC	P	R	-	- Do -
(d)	Bend Test	- Do -	- Do -	MTC	P	R	-	- Do -
(e)	Impact Test	- Do -	For HT Material(BR, B0 and C Grades) as per GETCO approved Structure Drawing/BOM or GETCO approval Letter.	MTC	P	R	-	Min 27J.at Room Temp.25 ±2°C as per IS 2062-2011
1.1.2	CHEMICAL COMPOSITION (Product Analysis)		Annexure-A	MTC	P	R	P*	MTC review at the time of final inspection
1.1.3	ZINC Chemical composition of Zinc Ingot		IS 209 Zinc purity min 99.99%	TC	P	R	P*	MTC to be reviewed at the time of Final Inspection (Zinc Procured from Prime producer or prior approval from GETCO is required)
1.1.4	VISUAL CHECKS FOR SURFACE FINISH	IS 2500, Level II, AQL-1.5	Material shall be reasonably free from surface flaws; laminations; rough/jagged and imperfect edges and all other harmful defects	IR	P	R	-	MTC review at the time of final inspection
1.1.5	DIMENSIONAL CHECKS	IS 2500 Level II, AQL-1.5	IS 1852, IS 808	IR	P	R	-	MTC review at the time of final inspection

Signature of the Manufacturer: Name: Designation: Date : Authorised common rubber Stamp / seal of the Manufacturer:	Signature of the Contractor: Name: Designation: (Only Furnish if Applicable i.e. GETCO PROJECT/DEPOSIT WORK) Authorised common rubber Stamp / seal of the Contractor:
LOA-AT No/Estimate No:	
Tender/Project Specific Stamp :	

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/ICE(Engg)/IIII/D/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.		GETCO STANDARD APPROVAL		Rev. No	Date	Page No		
GETCO/MQP/20-21/TOWER&SS STRUCTURES		STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV		0	20.11.2020	2 of 13		
S.No	Component / Operation & Description of Test	Sampling Plan with basis	Ref. Doc & Acceptance norm	Record Format	Testing Agency			Remarks
					M	C	TPIA	
1.1.6	TOLERANCES FOR LEG LENGTH OF ANGLES EQUAL / UN EQUAL	IS 2500 Level II, AQL-1.5.	For $\leq 45\text{mm} = \pm 1.5\text{mm}$ For 45 to 100 = $\pm 2.0\text{mm}$ For $> 100 = \pm 2.0\%$ of leg length For unequal leg: $+2, -1.5\text{mm}$ for longer leg length for shorter leg length as per 1.1.7	IR	P	R	-	MTC review at the time of final inspection
1.1.7	OUT OF SQUARE NESS	IS 2500 Level II, AQL-1.5.	Perpendicular to each other $\pm 1^\circ$	IR	P	R	-	
1.1.8	CAMBER or SWEEP	IS 2500 Level II, AQL-1.5.	For $< 100 = \pm 0.3\%$ of length For $\geq 100 = \pm 0.2\%$ of length Max.	IR	P	R	-	
1.1.9	WEIGHT TOLERANCE FOR ANGLE SECTIONS & FLAT	1 Sample/ 40 MT for each type.	For $< 3\text{mm}$ thick $\pm 5\%$ For $> 3\text{mm}$ thick $+5\% / -3\%$	IR	P	R	-	
1.2.0	WEIGHT TOLERANCE FOR PLATES	1 Sample/ 40 MT for each type.	$+5/-2.5\%$	IR	P	R	-	
1.2.1	THICKNESS TOLERANCE FOR PLATES	IS 2500 Level II, AQL-1.5.	$< 8\text{ mm}$ thick : $+ 12.5\%$, $- 5\%$ $8\text{ mm} - 12\text{ mm}$: $+ 7.5\%$, $- 5\%$ over 12 mm : $\pm 5\%$	IR	P	R	-	
1.2.2	ROOT RADIOUS	IS 2500 Level II, AQL-1.5.	IS 808 (As per Table 5.1)	IR	P	R	-	
1.2.3	WIDTH TOLERANCE FOR FLAT	IS 2500 Level II, AQL-1.5.	IS 1730/1852 $< 50\text{mm}$ $\pm 1.0\text{mm}$, $> 50 < 75\text{mm}$ $\pm 1.5\text{mm}$, $> 75 < 100\text{mm}$ $\pm 2.0\text{mm}$, $> 100 < \pm 2.0\%$, Max 6.0mm Thickness Upto & including $12\text{mm} \pm 5\text{mm}$, Over $12\text{mm} \pm 4\%$ Max. 1.5mm .	IR	P	R	-	
THIS DOCUMENT IS PROPERTY OF GETCO AND SHALL NOT BE USED OR PASSED ON TO OTHERS WITHOUT WRITTEN CONSENT OF GETCO								

Signature of the Manufacturer: Name: Designation: Date : Authorised common rubber Stamp / seal of the Manufacturer:	Signature of the Contractor: Name: Designation: (Only Furnish if Applicable i.e. GETCO PROJECT/DEPOSIT WORK) Authorised common rubber Stamp / seal of the Contractor:
LOA-AT No/Estimate No:	
Tender/Project Specific Stamp :	

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/CE(Engg)/III/D/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.	Rev. No	Date	Page No
GETCO/MQP/20-21/TOWER&SS STRUCTURES	0	20.11.2020	3 of 13
GETCO STANDARD APPROVAL			
STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV			

S.No	Component / Operation & Description of Test	Sampling Plan with basis	Ref. Doc & Acceptance norm	Record Format	Testing Agency			Remark
					M	C	TPIA	
1.2.4	ROUND BARS a. Diameter(d) Tolerance b. Ovality & out-of-Square *THIS DOCUMENT IS PROPERTY OF GETCO AND SHALL NOT BE USED OR PASSED ON TO OTHERS WITHOUT WRITTEN CONSENT OF GETCO* c. Weight Tolerance	IS 2500 Level II, AQL-1.5. - Do - - Do -	IS 1852 d<25mm ±0.5mm, 25<d<35mm ±0.6mm, 35<d<50mm ±0.8mm, 50<d<80mm ±1.0mm, 80<d<100mm ±1.3mm, 100<d< ±1.6 % of Diameter or side width. IS 1852 The permissible ovality for round bars measured as the difference between the maximum and minimum diameters and the out-of-square of square bars measured as the distance between parallel faces across any cross section shall be 75% of total tolerance (plus & minus) specified on the size. IS 1852 Up to and including 10mm ±7%, above 10 to 16mm ±5% & above 16mm ±3%	IR	P	R	-	MTC review at the time of final inspection

2. IN PROCESS INSPECTION

S.No	Component / Operation & Description of Test	Sampling Plan with basis	Ref. Doc & Acceptance norm	Record Format	Testing Agency			Remark
					M	C	TPIA	
(a)	INPROCESS INSPECTION FABRICATION OF TOWER PARTS	100%	IS 802 Part II/ IS 7215/ approved Drwg.,	Routine Sheet	P	R	-	
(b)	STRAIGHTENING	1st Piece and every 40th Piece	Length Tolerance ± 2 mm The cut surface to be clean, reasonable square & free from distortion	Routine Sheet	P	R	-	
(c)	CROPPING (CUTTING TO LENGTH)	1 piece at random for each item	IS 802 Part II/ IS 7215/ approved Drwg.,	Routine Sheet	P	R	-	
	SECTION SIZE			Routine Sheet	P	R	-	

Signature of the Manufacture: Name: Designation: Date : Authorised common rubber Stamp / seal of the Manufacturer:	Signature of the Contractor: Name: Designation: (Only Furnish if Applicable i.e. GETCO PROJECT/DEPOSIT WORK) Authorised common rubber Stamp / seal of the Contractor:
	LOA-AT No/Estimate No:
	Tender/Project Specific Stamp :

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/CE(Engg)/III/D/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.		GETCO STANDARD APPROVAL				Rev. No	Date	Page No
GETCO/MQP/20-21/TOWER&SS STRUCTURES		STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV				0	20.11.2020	4 of 13
S.No	Component / Operation & Description of Test	Sampling Plan with basis	Ref. Doc & Acceptance norm	Record Format	Testing Agency			Remark
					M	C	TPIA	
(d)	STAMPING / MARKING	1st Piece and every 40th Piece	9X16 MM & 0.45 MM Depth (Easily to be seen) Punching to be done for thickness up to 12 mm and Drilling to be done for thickness more than 12 mm. Holes near bends to be punched/ drilled after bending. Hole should be perpendicular to surface & difference in dia on both sides of flange should not be more than 0.8mm, Hole Ovality not acceptable.	Routine Sheet	P	R	-	
(e)	PUNCHING / DRILLING	- Do -	IS 802 PART II/ IS 7215 / approved drwg. For 13.5 mm Dia Hole Sheared Edge 20 MM & Rolled Edge 16 MM For 17.5 mm Dia Hole Sheared Edge 23 MM & Rolled Edge 20 MM For 21.5 mm Dia Hole Sheared Edge 28 MM & Rolled Edge 25 MM For 25.0 mm Dia Hole Sheared Edge 38 MM & Rolled Edge 33 MM /As per Approved Drawing. Tolerance cumulative and between consecutive Hole shall be within ± 2 mm & ± 1 mm respectively & ± 0.5 mm Gauge distance.	Routine Sheet	P	R	-	
<p>“THIS DOCUMENT IS PROPERTY OF GETCO AND SHALL NOT BE USED OR PASSED ON TO OTHERS WITHOUT WRITTEN CONSENT OF GETCO”</p>								
(f)	EDGE SECURITY	1st Piece and every 40th Piece			P	R	-	
(g)	DRILLING & PUNCHING Hole to Hole Distance/Spacing/Gauge distance	1st Piece and every 40th Piece		Routine Sheet	P	R	-	
(h)	NOTCHING, FLANGE, CORNER, BEVEL CUT	1st Piece and every 40th Piece	+ 5.0 mm on specified length of cut operation by shearing upto 12 mm thick and by Gas Cutting for material above 12mm.	Routine Sheet	P	R	-	

Signature of the Manufacturer:	Signature of the Contractor:	LOA-AT No/Estimate No:
Name:	Name:	
Designation:	Designation:	
Date :	(Only Furnish if Applicable i.e. GETCO PROJECT/DEPOSIT WORK)	
Authorised common rubber Stamp / seal of the Manufacturer:	Authorised common rubber Stamp / seal of the Contractor:	Tender/Project Specific Stamp :

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/CE(Engg)/III/D/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.	GETCO STANDARD APPROVAL	Page No
GETCO/MQP/20-21/TOWER&SS STRUCTURES	STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV	5 of 13
Rev. No	Date	
0	20.11.2020	

S.No	Component / Operation & Description of Test	Sampling Plan with basis	Ref. Doc & Acceptance norm	Record Format	Testing Agency			Testing Agency
					M	C	TPIA	
(i)	HEEL CUTTING	- Do -	For Member > 12 mm thick. Gas cutting to be adopted followed by grinding/Machine cutting. Tolerance on heel cutting length + 10 MM.	Routine Sheet	P	R	-	
(j)	BENDING	100%	(i) Angle Sections : Upto 75x75x6 (Upto 10deg)- Cold Bend Upto 100x100x8 (Upto 5deg)- Cold Bend Above 75x75x6 (above 10deg)- Hot Bend Above 100x100x8 (above 5deg)- Hot Bend All HT sections and plates shall be Hot bend. (ii) MS Plates Upto 12mm thick (upto 15 degree)-Cold Bend Others (Any degree) - Hot Bend	Routine Sheet	P	R	-	
(k)	Welding /Fitting/ a) Marking,Cutting,Edge Preparation b) Fft Up, Dimensional Control "THIS DOCUMENT IS PROPERTY OF GETCO AND SHALL NOT BE USED OR PASSED ON TO OTHERS WITHOUT WRITTEN CONSENT OF GETCO"	100% 100%	IS 9595 a) As per Drawing/Specification of GETCO b) As per Drawing/ Specification of GETCO	Routine Sheet	P	R	-	

Signature of the Manufacturer: Name: Designation: Date : Authorised common rubber Stamp / seal of the Manufacturer:	Signature of the Contractor: Name: Designation: (Only Furnish if Applicable i.e. GETCO PROJECT/DEPOSIT WORK) Authorised common rubber Stamp / seal of the Contractor:
	LOA-AT No/Estimate No:
	Tender/Project Specific Stamp :

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/CE(Engg)/III/D/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.	GETCO STANDARD APPROVAL	Rev. No	Date	Page No
GETCO/MQP/20-21/TOWER&SS STRUCTURES	STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV	0	20.11.2020	6 of 13

S.No	Component / Operation & Description of Test	Sampling Plan with basis	Ref. Doc & Acceptance norm	Record Format	Testing Agency			Remarks
					M	C	TPIA	
1	PROTO ASSEMBLY Visual & Dimensional Inspection "THIS DOCUMENT IS PROPERTY OF GETCO AND SHALL NOT BE USED OR PASSED ON TO OTHERS WITHOUT WRITTEN CONSENT OF GETCO"	One Structure of each Tower Type.	As per GETCO approved Drawings & BOM. All parameters from (a) to (k) above are checked and record maintained shall be verified by GETCO Inspector before releasing the materials for galvanizing.	Proto Inspection Report	P	W		Proto Corrected BOM must be verified and signed by GETCO Inspector & Manufacturer. Deviation in tower member must be clearly indicated in BOM & MOM with tech'cal justification and same shall be thoroughly inspected by GETCO Inspector

Signature of the Manufacturer: Name: Designation: Date : Authorised common rubber Stamp / seal of the Manufacturer:	Signature of the Contractor: Name: Designation: (Only Furnish if Applicable i.e. GETCO PROJECT/DEPOSIT WORK) Authorised common rubber Stamp / seal of the Contractor:	LOA-AT No/Estimate No: Tender/Project Specific Stamp :
---	---	---

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/CE(Engg)/III/D/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.	GETCO STANDARD APPROVAL	Rev. No	Date	Page No
GETCO/MQP/20-21/TOWER&SS STRUCTURES	STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV	0	20.11.2020	7 of 13

*THIS DOCUMENT IS PROPERTY OF
GETCO AND SHALL NOT BE USED OR
PASSED ON TO OTHERS WITHOUT
WRITTEN CONSENT OF GETCO*

3. GALVANIZING

S.No	Component / Operation & Description of Test	Sampling Plan with basis	Ref. Doc & Acceptance norm	Record Format	Testing Agency			Remarks
					M	C	TPIA	
(a)	DEGREASING 1. Caustic solution / alkali based degreaser to be followed by Rinsing Water or 2. Acid based degreaser	One sample daily One sample daily	IS 2629 with Latest amendments. 10-15Kg of NaOH/100 Litres of H ₂ O. Temp of Solution : 85-90 °C As per Manufacturers recommendation.	Process Report/ Register	P	R	-	
(b)	PICKLING 1. Acid content 2. Iron Content	One sample daily One sample daily	HCL : @ Room Temp. Conc : 100-150g/l. H ₂ SO ₄ : @ 60-80 °C. Conc : 100-150g/l. (Inhibitor to be used with Both types of Acid.) When iron content reaches 100-120g/l, the solution shall be discarded.	-Do-	P	R	-	
(c)	RINSING Only in absence of Auto Neutralization of Pre Flux solution	One sample daily	IS: 2629 with latest amendments (ph = 4 to 7)	-Do-	P	R	-	
(d)	PREFLUXING In Zinc chloride and Ammonium Chloride solution patent fluxing reagent	One sample daily	Iron Content : 50 Gms/ltr Max. Sp. Gravity : 1.16 to 1.24 pH : 3 to 6	-Do-	P	R	-	

Signature of the Manufacturer: Name: Designation: Date : Authorised common rubber Stamp / seal of the Manufacturer:	Signature of the Contractor: Name: Designation: (Only Furnish if Applicable i.e. GETCO PROJECT/DEPOSIT WORK) Authorised common rubber Stamp / seal of the Contractor:
LOA-AT No/Estimate No:	
Tender/Project Specific Stamp :	

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/CE(Engg)/III/D/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.	GETCO STANDARD APPROVAL	Rev. No	Date	Page No
GETCO/MQP/20-21/TOWER&SS STRUCTURES	STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV	0	20.11.2020	9 of 13

S.No	Component / Operation & Description of Test	Sampling Plan with basis	Ref. Doc & Acceptance norm	Record Format	Testing Agency			Remarks
					M	C	TPIA	
3.2	GALVANIZING CHECKING							
(a)	VISUAL CHECKING	100%	IS 2629, 4759, 6745, 2633 Free from harmful galvanizing defects	IR	P	R	-	
(b)	Thickness of Zinc Coating (a) Below 5mm thick (b) 5mm thick & above	8 samples / shift	IS 2629 (a) 65 micron Avg Min. (b) 87 micron Avg Min. (c) Refer Note, Page 11 of 13 of QAP	IR	P	R	-	
(c)	Mass of Zinc coating	3 samples / shift	(a) 460 g/m ² . (b) 610 g/m ² . (c) Refer Note Page 11 of 13 of QAP	IR	P	R	-	
(d)	Uniformity of Zinc coating	3 samples / shift	IS 2633 (4 dips of 1 minutes without showing sign of copper deposits)	IR	P	R	-	
(e)	Adhesion Test of Zinc coating(Pivot Hammer test/knife test)	1 samples / shift	IS 2629 (No peel out of Zinc coating in areas between hammer impressions)	IR	P	R	-	

THIS DOCUMENT IS PROPERTY OF GETCO AND SHALL NOT BE USED OR PASSED ON TO OTHERS WITHOUT WRITTEN CONSENT OF GETCO

Signature of the Manufacture: Name: Designation: Date : Authorised common rubber Stamp / seal of the Manufacturer:	Signature of the Contractor: Name: Designation: (Only Furnish if Applicable i.e. GETCO PROJECT/DEPOSIT WORK) Authorised common rubber Stamp / seal of the Contractor:
	LOA-AT No/Estimate No:
	Tender/Project Specific Stamp :

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/CE(Engg)/III/D/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.	GETCO STANDARD APPROVAL	Rev. No	Date	Page No
GETCO/MQP/20-21/TOWER&SS STRUCTURES	STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV	0	20.11.2020	10 of 13

4. FINAL INSPECTION AND TESTING

S.No	Component / Operation & Description of Test	Sampling Plan with basis	Ref. Doc & Acceptance norm	Record Format	Testing Agency			Remarks
					M	C	TPIA	
(a)	VISUAL & DIMENSIONAL INSPECTION Refer CL.1.1.5-1.2.4 Page 01-02 of QAP	Sample as Per Table-II Page 13 of 13 of QAP	As per GETCO approved drawing & BOM	IR	P	W	-	Inspection Reports
(b)	PHYSICAL / MECHANICAL PROPERTIES (i) UTS Tests (ii) Yield Stress Test (iii) % Elongation Test (iv) Bend Test	1 Sample/ 40 MT for each type.	Refer CL.1.1.1 Page 01 of 13 of QAP for Physical/Mechanical Properties	Test Report	P	W	-	Test perform by Manufacturer in presence of GETCO representative
(c)	GALVANIZING TESTS (i) Thickness of Zinc Coating (ii) Mass of Zinc coating (iii) Uniformity of Zinc Coating (iv) Adhesion of Zinc coating	1 Sample/ 40 MT for each type.	Refer CL.3.2 Page 08 of 12 of QAP for Galvanizing Checking.	Test Report	P	W	-	Test perform by Manufacturer in presence of GETCO representative
(d)	CHEMICAL TEST	1 Sample/ 40 MT for each type.	IS 2062 : 2011 As per Annexure A & Table 3 Page 11 of 12 of QAP	Test Report	P	W	-	Test perform by Manufacturer in presence of GETCO representative
(e)	TOWER ERECTION MARKING	Sample as Per Table-II, Page 13 of 13 of QAP	Refer Project Specific GETCO approval Letter for Tower Erection Marking.	Visual	P	W	-	To be verified by GETCO Inspector during Inspection & shall be mentioned in MOM.
(f)	Packing/Bundling Tower Wise/Section wise	100 %	As per GETCO specification	BP, Packing List	P	W	-	Bundling Plan, Packing List shall be provide by Manufacturer.

Signature of the Manufacture: Name: Designation: Date : Authorised common rubber Stamp / seal of the Manufacturer:	Signature of the Contractor: Name: Designation: (Only Furnish if Applicable i.e. GETCO PROJECT/DEPOSIT WORK) Authorised common rubber Stamp / seal of the Contractor:
LOA-AT No/Estimate No:	
Tender/Project Specific Stamp :	

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/CE(Engg)/III/D/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.	GETCO STANDARD APPROVAL	Rev. No	Date	Page No
GETCO/MQP/20-21/TOWER&SS STRUCTURES	STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV	0	20.11.2020	12 of 13

Annexure - A

IS 2062 : 2011	Physical / Mechanical Properties				Bend Test	Chemical Properties						
	Grade	Quality	Minimum Values			Min	Maximum Values in %					
			Yield Stress N/mm ² (Min.)	UTS N/mm ² (Min.)			% of Elongation (Min.)	C	Mn	S	P	Si
E 250	A	T<20 mm : 250	410	23%	3t	0.23	1.50	0.045	0.045	0.40	0.42	
	BR / BO	T >20-40 mm : 240	410	23%	2t	0.22	1.50	0.045	0.045	0.40	0.41	
	C	T >40 : 230	410	23%	3t	0.20	1.50	0.040	0.040	0.40	0.39	
E 350	A	T<20 mm : 350	490	22%	---	0.20	1.55	0.045	0.045	0.45	0.47	
	BR / BO	T >20-40 mm : 330	490	22%	2t	0.20	1.55	0.040	0.040	0.45	0.45	
	C	T >40 : 320	490	22%	2t	0.20	1.55	0.040	0.040	0.45	0.45	
IS 2062 : 2011 TABLE -3 Permissible Variation for product Analysis												
Note for Bend Test: For bend test, the test piece at room temperature shall withstand bending through 180° to an internal diameter not greater than that given in Table 2 without cracking as per IS 2062-2011 with latest amendment.												

*THIS DOCUMENT IS PROPERTY OF
GETCO AND SHALL NOT BE USED OR
PASSED ON TO OTHERS WITHOUT
WRITTEN CONSENT OF GETCO*

Signature of the Manufacture:	Signature of the Contractor:	LOA-AT No/Estimate No:
Name:	Name:	
Designation:	Designation:	
Date:	(Only Furnish if Applicable i.e. GETCO PROJECT/DEPOSIT WORK)	
Authorised common rubber Stamp / seal of the Manufacturer:	Authorised common rubber Stamp / seal of the Contractor:	Tender/Project Specific Stamp :

GUJRAT ENERGY TRANSMISSION CORPORATION LTD.

STANDARD APPROVAL

STANDARD MANUFACTURING QUALITY PLAN

GETCO/CE(Engg)/III/D/O-006499
Date:06.04.2021

MATERIAL DESCRIPTION : STANDARD MQP GALVANIZED STEEL STRUCTURES FOR GETCO SUPPLY

QAP No.	GETCO STANDARD APPROVAL	Rev. No	Date	Page No
GETCO/MQP/20-21/TOWER&SS STRUCTURES	STANDARD MQP HDG TOWER & SS STRUCTURES UPTO 400KV	0	20.11.2020	13 of 13

"THIS DOCUMENT IS PROPERTY OF GETCO AND SHALL NOT BE USED OR PASSED ON TO OTHERS WITHOUT WRITTEN CONSENT OF GETCO"

Sampling Plan

TABLE-I
Sampling plan for Visual & Dimensional Check of Raw Materials As Per IS-2500, Level II, AQL 1.5

S.No.	Lot Size	Sample Size	Acceptance No.	Rejection No
1	2 to 8	100%	0	0
2	9 to 15	8	0	1
3	16 to 25	8	0	1
4	26 to 50	8	0	1
5	51 to 90	8	0	1
6	91 to 150	20	1	2
7	151 to 280	32	1	2
8	281 to 500	50	2	3
9	501 to 1200	80	3	4
10	1201 to 3200	125	5	6
11	3201 to 10,000	200	7	8
12	10,001 to 35,000	315	10	11
13	35,001 to 1,50,000	500	14	15
14	1,50,001 & Above	800	21	22

TABLE-II
Sampling plan for Visual & Dimensional Characteristics of Structural Steel for Final Inspection (Dimension Check)
(Refer Para 4.4 Final Inspection & Testing)
As Per IS-2500, Level II, AQL 1.5
NUMBER OF PIECES

S.No.	Lot Size	Sample Size	Acceptance No.	Rejection No
1	2 to 8	100%	0	0
2	9 to 15	8	0	0
3	16 to 25	8	0	0
4	26 to 50	8	0	0
5	51 to 90	8	0	0
6	91 to 150	20	0	1
7	151 to 280	32	0	1
8	281 to 500	50	0	2
9	501 to 1200	80	0	3
10	1201 to 3200	125	0	5
11	3201 to 10,000	200	0	7
12	10,001 to 35,000	315	0	10
13	35,001 to 1,50,000	500	0	14
14	1,50,001 & Above	800	0	21

Signature of the Manufacturer: Name: Designation: Date : Authorised common rubber Stamp / seal of the Manufacturer:	Signature of the Contractor: Name: Designation: Date : Authorised common rubber Stamp / seal of the Contractor:
LOA-AT No/Estimate No:	
Tender/Project Specific Stamp :	

