Schedule of Work

Name of Work: Operation & Maintenance of E&M Services at Sankalp Bhawan, K.G. Marg, New Delhi during 2026-27 [SH: Misc. El Works]

S.no.	Description of items	Quantity.		Rate	Unit	Amount
1	Wiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS/HFFR PVC insulated copper conductor single core cable in surface/ recessed steel conduit, with modular switch, modular plate, suitable GI box and earthing the point with 1.5 sq.mm FRLS/HFFR PVC insulated copper conductor single core cable etc. as required.					
(a)	Group C	10	Points	2,101.00	Point	21,010.00
2	Wiring for light/ power plug with 2X4 sq.mm FRLS/HFFR PVC insulated copper conductor single core cable in surface/ recessed steel conduit along with 1 No. 4 sq. mm FRLS PVC insulated copper conductor single core cable for loop earthing as required.	100	Mtr.	480.00	P/Mtr.	48,000.00
3	Wiring for light/ power plug with 4X4 sq. mm FRLS/HFFR PVC insulated copper conductor single core cable in surface/ recessed steel conduit along with 2 Nos. 4 sq.mm FRLS/HFFR PVC insulated copper conductor single core cable for loop earthing as required	50	Mtr.	724.00	P/Mtr.	36,200.00
4	Rewiring for light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq.mm FRLS/HFFR PVC insulated copper conductor single core cable and 1.5 sq.mm FRLS/HFFR PVC insulated copper conductor single core cable as earth wire in existing surface/ recessed steel/PVC conduit including dismantling as required.					
(a)	Group C	20	Points	1,064.00	Point	21,280.00
5	Supplying and fixing modular blanking plate on the existing modular plate & switch box excluding modular plate as required.	20	Nos.	47.00	Each	940.00
6	Wiring for group controlled (looped) light point/fan point/exhaust fan point/ call bell point (without independent switch etc.) with 1.5 sq. mm FRLS/HFFR PVC insulated copper conductor single core cable in surface/ recessed steel conduit, and earthing the point with 1.5 sq. mm FRLS/HFFR PVC insulated copper conductor single core cable etc. as required.					
(a)	Group C	20	Points	1,246.00	Point	24,920.00
7	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc as required:-					
(a)	1 or 2 Module (75 mmX75 mm)	50	Nos.	354.00	Each	17,700.00
(b)	3 Module (100mmX75mm)	50	Nos.	384.00	Each	19,200.00
(c)	6 Module (200mm x 75mm)	50	Nos.	462.00	Each	23,100.00
(d)	8 Module (125mmX125mm)	50	Nos.	517.00	Each	25,850.00
8	Providing and fixing following rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, Ics=100% Icu and Operational Voltage 690V etc. as required.					
(a)	100 A, 16 KA,TPMCCB	1	Nos.	4,003.00	Each	4,003.00
(b)	125 A, 16 KA,TPMCCB	1	Nos.	5,103.00	Each	5,103.00
(c)	100 A,30KA,FPMCCB	1	Nos.	8,127.00	Each	8,127.00
(d)	125 A,36KA,FPMCCB	1	Nos.	8,644.00	Each	8,644.00
(e)	400 A, 35 KA,TPMCCB	1	Nos.	22,644.00	Each	22,644.00
(f)	630 A, 50 KA,TPMCCB	1	Nos.	29,222.00	Each	29,222.00
9	Supplying and fixing following way, single pole and neutral, sheet steel, MCB distribution board, 240 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator)					
(a)	12 way , Double door	1	Nos.	2,871.00	Each	2,871.00
(b)	16 way , Double door	1	Nos.	3,367.00	Each	3,367.00
10	Supplying and fixing following way, horizontal type three pole and neutral, sheet steel, MCB distribution board, 415 V, on surface/ recess, complete with tinned copper bus bar, neutral bus bar, earth bar, din bar, interconnections, powder painted including earthing etc. as required. (But without MCB/RCCB/Isolator).					
(a)	8 way (4 + 24), Double door	1	Nos.	6,337.00	Each	6,337.00

S.no.	Description of items	Quantity.		Rate	Unit	Amount
11	Supplying and fixing 20 A, 240 V, SPN Industrial type socket outlet, with 2 pole and earth, metal enclosed plug top along with 20 A "C" curve, SP, MCB, in sheet steel enclosure, on surface or in recess, with chained metal cover for the socket out let and complete with connections, testing and commissioning etc. as required.	1	Nos.	1,806.00	Each	1,806.00
12	Supplying and installaton following size of perforated painted with powder coating M.S. cable trays with perforation not more than 17.5%, in convenient sections, joined with connectors, suspended from the ceiling with two numbers MS/GI Suspenders i/c base of suitable size MS/GI angle, bolts & nuts, painting suspenders, fastener etc as required.					
(a)	100 mm width X 50 mm depth X 1.6 mm thickness	50	Mtrs	623.00	P/Mtr	31,150.00
(b)	150 mm width X 50 mm depth X 1.6 mm thickness	50	Mtrs	686.00	P/Mtr	34,300.00
13	Supplying and installation following size of perforated painted with powder coating M.S. cable trays bends with perforation not more than 17.5%, joined with connectors, suspended from the ceiling with two numbers MS/GI Suspenders i/c base of suitable size MS/GI angle, bolts & nuts, painting suspenders, fastener etc as required.					
(a)	100 mm width X 50 mm depth X 1.6 mm thickness	2	Nos.	948.00	Each	1,896.00
(b)	150 mm width X 50 mm depth X 1.6 mm thickness	2	Nos.	1105.00	Each	2,210.00
14	Supplying and installation following size of perforated painted with powder coating M.S. cable trays Tee with perforation not more than 17.5%, joined with connectors, suspended from the ceiling with two numbers MS/GI Suspenders i/c base of suitable size MS/GI angle, bolts & nuts, painting suspenders, fastner etc as required.					
(a)	100 mm width X 50 mm depth X 1.6 mm thickness	2	Nos.	1089.00	Each	2,178.00
(b)	150 mm width X 50 mm depth X 1.6 mm thickness	2	Nos.	1281.00	Each	2,562.00
15	Supplying and installing following size of perforated painted with powder coating M.S. cable trays Cross Member with perforation not more than 17.5%, joined with connectors, suspended from the ceiling with two numbers MS/GI Suspenders i/c base of suitable size MS/GI angle, bolts & nuts, painting suspenders, fastner etc as required.					
(a)	100 mm width X 50 mm depth X 1.6 mm thickness	2	Nos.	1231.00	Each	2,462.00
(b)	150 mm width X 50 mm depth X 1.6 mm thickness	2	Nos.	1498.00	Each	2,996.00
16	Supplying and installing following size of perforated painted with powder coating M.S. cable trays Reducer with perforation not more than 17.5%, joined with connectors, suspended from the ceiling with two numbers MS/GI Suspenders i/c base of suitable size MS/GI angle, bolts & nuts, painting suspenders, fastner etc as required.					
(a)	100 mm width X 50 mm depth X 1.6 mm thickness	2	Nos.	1089.00	Each	2,178.00
(b)	150 mm width X 50 mm depth X 1.6 mm thickness	2	Nos.	1281.00	Each	2,562.00
17	Supplying, Installation, Testing and commissioning of Passive Infrared(PIR) technology based occupancy sensor with day light dimming(lighting level shall be regulated as per availability of natural day light in an area along with occupancy detection.) having high performance, regulating programmable type, suitable for connected load upto 10Amp , for mounting height up to 3 mtr and for 5 m diameter coverage area along with necessary fixing arrangements i/c programming at site etc. complete as required.	1	Nos.	9,670.00	Each	9,670.00
18	Supplying and making end termination with brass compression gland and aluminium lugs for following size of PVC insulated and PVC sheathed / XLPE aluminium conductor cable of 1.1 KV grade as required.					
(a)	3 X 70 sq. mm (35mm)	2	Nos.	495.00	Each	990.00
(b)	3 X 35 sq. mm (28mm)	2	Nos.	419.00	Each	838.00
(c)	3 X 50 sq. mm (32mm)	2	Nos.	442.00	Each	884.00
(d)	4 X 16 sq. mm (28mm)	5	Nos.	366.00	Each	1,830.00
(e)	4 X 10 sq. mm (25mm)	5	Nos.	325.00	Each	1,625.00
19	Supplying, drawing, Installation, Testing and commissioning of CAT6 UTP LSZH 23AWG Twisted Pair Cable in existing conduit/ on surface, Category 6 Unshielded Twisted Pair, 4 pair should be complied as per UL/ETL verification program for compliance with ANSI/TIA-568.2-D standard. Outer diameter should be in the range of 6.1mm nominal with Operating Temperature Range : -5° to +60℃, Bending Radius : 4 X Cable Diameter at –5℃ ± 1℃ and Pulling Force: 11.5Kg etc. complete as required					
(a)	1 Run of cable	3000	Mtr	60.00	P/Mtr.	1,80,000.00

S.no.	Description of items	Quantity.		Rate	Unit	Amount
(b)	2 Run of cable	3000	Mtr	96.00	P/Mtr.	2,88,000.00
20	Supplying, drawing, Testing and commissioning of Cat6A UTP 4 pair, 23 AWG solid copper cable in existing conduit/ on surface, U/FTP, LSZH, NonPlenum, Horizontal (solid) Cable suitable for high speed data networking application supporting upto 10Gbps over a 100 meter channel. The 4 Unshielded Twisted Pairs (UTP) cable with color coded insulation for easy indentification should have FLAME PROPERTIES i.e. Flammability Test - IEC 60332-1, Smoke Density - IEC 61034, LSZH standards compliance: ANSI/TIA-568 C.2, ISO/IEC 11801, IEEE 802.3an, RoHS. Delay Skew should be < 45NS. The outer Cable Diameter should be 7.5 + 2 mm. Cable should have been tested and verified by UL/ ETL etc. complete as required.					
(a)	1 Run of cable	800	Mtrs	62.00	P/Mtr	49,600.00
(b)	2 Run of cable	400	Mtrs	99.00	P/Mtr	39,600.00
21	Supplying, Installation, Testing and commissioning of following CAT6 Patch Cord should have ETL/UL verification program certificate for compliance with ANSI/TIA-568.2-D etc. complete as required.					
(a)	Copper Patch Cords of length 1m (3ft)	50	Nos.	151.00	Each	7,550.00
(b)	Copper Patch Cords of length 3m (10ft)	50	Nos.	227.00	Each	11,350.00
22	Supplying, Installation, Testing and commissioning of following CAT6A Patch Cord should have ETL/UL verification program certificate for compliance with ANSI/TIA-568.2-D etc. complete as required.					
(a)	Copper Patch Cords of length 1m (3ft)	5	Nos.	173.00	Each	865.00
(b)	Copper Patch Cords of length 3m (10ft)	5	Nos.	405.00	Each	2,025.00
23	Supplying, Installation, Testing and commissioning of CAT6 Copper Information Outlet (IO) with face plate of color as per site requirement, should have ETL/UL verification program certificate for compliance with ANSI/TIA-568.2-D. All copper Cable and Components should be from same OEM to maintain compatibility and interoperability etc. complete as required.	80	Nos.	212.00	Each	16,960.00
24	Supplying, Installation, Testing and commissioning of CAT6A Copper Information Outlet (IO) with face plate of color as per site requirement, should have ETL/UL verification program certificate for compliance with ANSI/TIA-568.2-D. All copper Cable and Components should be from same OEM to maintain compatibility and interoperability etc. complete as required.	200	Nos.	302.00	Each	60,400.00
25	Supplying, Installation, Testing and commissioning of RJ45 Connector for CAT 6/6A Cables. RJ45 modular plug supports 4 twisted pairs, 8 positions, 8 connectors. Housing: PC, UL94V-2, transparent color, Use for 24- 26 AWG stranded wires etc. complete as required.	150	Nos.	9.00	Each	1,350.00
26	Supplying & Laying of one number PVC insulated and PVC sheathed/ XLPE Aluminium conductor armoured power cable of 1.1 KV grade of following size on wall surface/RCC/Hume/ Metal Pipe etc as required.					
(a)	3.5 x 70 Sq.mm	20	Mtr.	1,389.00	P/Mtr.	27,780.00
(b)	3.5 x 35 Sq.mm	20	Mtr.	746.00	P/Mtr.	14,920.00
(c)	3.5 x 50 Sq.mm	20	Mtr.	1,060.00	P/Mtr.	21,200.00
(d)	4 x 16 Sq.mm	20	Mtr.	543.00	P/Mtr.	10,860.00
(e)	4 x 10 Sq.mm	20	Mtr.	506.00	P/Mtr.	10,120.00
(f)	4 x 6 Sq.mm	20	Mtr.	345.00	P/Mtr.	6,900.00
27	Supplying and fixing following size/ modules, PVC box alongwith modular base & cover plate for modular switches in recess etc as required:-					
(a)	1 or 2 Module (75 mmX75 mm)	200	Nos.	382.00	Each	76,400.00
(b)	3 Module (100mmX75mm)	200	Nos.	416.00	Each	83,200.00
(c)	6 Module (200mm x 75mm)	200	Nos.	515.00	Each	1,03,000.00
(d)	8 Module (125mmX125mm)	100	Nos.	534.00	Each	53,400.00
28	Supplying and fixing of following sizes of medium class PVC casing caping along with accessories in surface/recess including cutting the wall and making good the same etc. as required.					
(a)	25 mm	500	Mtr.	80.00	P/Mtr.	40,000.00
29	Supplying of the following items required for the day to day maintenance work of internal Electrical installations & external electrical installations at Sankalp Bhawan, New Delhi as per terms and conditions attached.					
29.1	1.5 sq. mm ISI marked, FRLS/HFFR PVC insulated, single core copper conductor cable	1000	Meter	23.00	Per Meter	23,000.00

S.no.	Description of items	Quantity.		Rate	Unit	Amount
29.2	2.5 sq. mm ISI marked, FRLS/HFFR PVC insulated, single core copper conductor cable	100	Meter	36.00	Per Meter	3,600.00
29.3	4.0 sq. mm ISI marked, FRLS/HFFR PVC insulated, single core copper conductor cable	4000	Meter	54.00	Per Meter	2,16,000.00
29.4	6.0 sq. mm ISI marked, FRLS/HFFR PVC insulated, single core copper conductor cable	500	Meter	82.00	Per Meter	41,000.00
29.5	10 sq. mm ISI marked, FRLS/HFFR PVC insulated, single core copper conductor cable	50	Meter	137.00	Per Meter	6,850.00
29.6	16 sq. mm ISI marked, FRLS/HFFR PVC insulated, single core copper conductor cable	50	Meter	212.00	Per Meter	10,600.00
29.7	20 mm dia, ISI marked, PVC conduit	1000	Meter	27.00	Per Meter	27,000.00
29.8	25 mm dia, ISI marked, PVC conduit	3000	Meter	38.00	Per Meter	1,14,000.00
29.9	32 mm dia, ISI marked, PVC conduit	1500	Meter	60.00	Per Meter	90,000.00
29.10	20 mm dia, ISI marked, steel conduit	50	Meter	94.00	Per Meter	4,700.00
29.11	25 mm dia, ISI marked, steel conduit	200	Meter	120.00	Per Meter	24,000.00
29.12	32 mm dia, ISI marked, steel conduit	100	Meter	168.00	Per Meter	16,800.00
29.13	S.P. 5/6 A, one way modular switch, ISI marked	100	Nos.	44.00	Each	4,400.00
29.14	S.P. 15/16 A, one way modular switch, ISI marked	150	Nos.	96.00	Each	14,400.00
29.15	3 pin 5/6 A modular socket outlet, ISI marked	100	Nos.	82.00	Each	8,200.00
29.16	6 pin 15/16 A modular socket outlet, ISI marked	150	Nos.	136.00	Each	20,400.00
29.17	Modular bell push, ISI marked	10	Nos.	80.00	Each	800.00
29.18	Telephone Socket outlet modular type	2	Nos.	88.00	Each	176.00
29.19	T.V. Socket outlet modular type	20	Nos.	88.00	Each	1,760.00
29.20	6 A, to 32 A, ratings, SP MCB, "C" curve, 10 KA breaking capacity	100	Nos.	175.00	Each	17,500.00
29.21	63 A, 2 pole isolator	2	Nos.	440.00	Each	880.00
29.22	63 A, 4 pole isolator	2	Nos.	859.00	Each	1,718.00
29.23	25 A, rating, 2 pole RCCB, 30mA	2	Nos.	1,887.00	Each	3,774.00
29.24	40 A, rating, 2 pole RCCB, 30mA	2	Nos.	2,233.00	Each	4,466.00
29.25	63 A, rating, 2 pole RCCB, 30mA	2	Nos.	2,565.00	Each	5,130.00
29.26	40 A, rating, 4 pole RCCB, 30mA	2	Nos.	3,043.00	Each	6,086.00
29.27	3 Core 4.0 Sq mm Flat Cable	50	Meter	167.00	Per Meter	8,350.00
29.28	Water curtain nozzle, nickel chrome plated brass	5	Nos.	405.00	Each	2,025.00
30	Supplying of LED Recessed/ surface Down lighter (Round/ square/ Rectangular) SMD type of following body material with PMMA and prismatic diffuser and construction as per IS: 10322 with driver as per the requirement with Driver efficiency >85%, Operating voltage AC 140-270 Volt, frequency 50/60 hz, Operating temp range -5° C to 40℃, internal surge protection of 2.5 KV with Short & Open circuit protection, THD < 10% , P. F.≥0.95, IP20, CRI ≥80 , UGR (Unified Glare Rating) < 19, Flicker free (flicker should be below 5%), life time (LED, Driver & electrical circuitry), of minimum 50000 Burning Hours with 70% of initial Lumen maintained till life ends, CCT 3000℃K / 4000℃K / 5700℃K / 6500℃K (As per ANSI Bin), SDCM (Standard Deviation Colour Matching) <3, Maximum power consumption should not more than the specified rating and Fixture shall be confirming to relevant BIS standards and trade mark certificate (T.C.). Manufactures Word Mark/ Name Engraved/ Embossing/ Screen printing on housing Complete in all respect with Minimum 5 year OEM warranty. System lumen efficacy ≥120 <135 lm/Watt output. LM79 & LM80 Test report and all testing required for LED fixtures as per BIS shall be submitted. Shape size and CCT shall be as approved by Engineer-in-Charge as per requirement. (Thermal management: heat sink of aluminium housing such that LED junction temperature shall not rise above 90℃). Powder coated die cast/ Extruded aluminium Body including trim					
(a)	12 -15 watt	25	Nos.	426.00	Each	10,650.00
(b)	18 Watt	10	Nos.	639.00	Each	6,390.00

S.no.	Description of items	Quantity.		Rate	Unit	Amount
31	Supplying of Panel light 2x2 ft., of following body material and construction as per IS: 10322 with driver as per the requirement with Driver efficiency >85%, Operating voltage AC 140-270 Volt, freq 50/60 hz, Operating temp range -5 deg to 40 deg centigrade, internal surge protection of 2.5 KV with Short & Open circuit protection, THD < 10% , P. F.≥0.95, IP20, CRI ≥80, UGR (Unified Glare Rating) < 19, Flicker free, (flicker should be below 5 %), life time (LED, Driver & electrical circuitry), of minimum 50000 Burning Hours with, 70% of initial Lumen maintained till life ends as per LM80 extrapolation IES TM-21-11 report, CCT 3000°K / 4000°K/ 5700°K /6500°K (As per ANSI Bin), SDCM (Standard Deviation Colour Matching) <3, Maximum power consumption should not more than the specified rating and Fixture shall be of relevant BIS standard and trade mark certificate (T.C.). Manufactures Word Mark/ Name Engraved/ Embossing/ Screen printing on housing. complete in all respect with Minimum 5 year OEM warranty. System lumen efficacy ≥120 ≤135 lm/Watt output. LM79 & LM80 Test report and all testing required for LED fixtures as per BIS shall be submitted. Shape size and CCT shall be as approved by Engineer-in-Charge as per requirement. Powder Coated CRCA Sheet Body (Thickness >0.50 mm).					
(a)	36 Watt	2	Nos.	1,837.00	Each	3,674.00
32	Supplying of LED surface mounted Batten light of following body material and construction as per IS : 10322 with driver (Replaceable) as per the requirement with Driver efficiency >85%, Operating voltage AC 140- 270 Volt, frequency 50/60 hz, Operating temp range -5 0C to 40 0C, internal surge protection of 2.5 KV with Short & Open circuit protection ,THD < 10% , P. F.≥0.95, IP20, CRI >80, Flicker free (flicker should be below 5 %), life time (LED,Driver & electrical circuitry), of minimum 50000 Burning Hours with 70% of initial Lumen maintained till life ends, CCT 3000°K / 4000°K / 5700°K /6500°K (As per ANSI Bin), SDCM(Standard Deviation Colour Matching) <3, Maximum power consumption should not more than the specified rating and Fixture shall be of relevant BIS standard. Manufactures Word Mark/ Name Engraved/ Embossing/ Screen printing on housing. complete in all respect. as required with Minimum 5 year OEM warranty. System lumen efficacy ≥120 <135 lm/Watt output . LM79 & LM80 Test report and all testing required for LED fixtures as per BIS shall be submitted. Shape size and CCT shall be as approved by Engineer-in-Charge as per requirement. (Thermal management: heat sink of aluminium housing such that LED junction temperature shall not rise above 90°C).					
(a)	18- 22 Watt	10	Nos.	444.00	Each	4,440.00
(b)	36 watt	10	Nos.	469.00	Each	4,690.00
33	Supply of ceiling fan with Brush Less Direct Current (BLDC) Motor, class of insulation: B, 3 nos. metal(Aluminium alloy) blades, 30 cm long down rod, 2 nos. canopies, shackle kit, safety rope, copper winding, steel/Al body Power Factor not less than 0.9, Service Value (CM/M/W) minimum as below, 350 RPM (tolerance as per IS : 374-2019), THD (Total Harmonic Distortion) less than 10%, remote (preferably mobile app based) for speed control and all remaining accessories including safety pin, nut bolts, washers, temperature rise=75 degree C (max.), insulation resistance more than 2 mega ohm, suitable for 230 V, 50 Hz, single phase AC Ceiling Fan compliant to IS 374:2019 fan Supply, earthing etc. complete as reqd.					
(a)	900mm, service value ≥ 5.1 CM/Min/Watt, air delivery 130 CM/Min (Minimum)	2	Nos.	2,310.00	Each	4,620.00
(b)	1200mm, service value ≥ 6.0 CM/Min/Watt, air delivery 210 CM/Min (Minimum)	2	Nos.	2,446.00	Each	4,892.00
34	Supplying of 20-25W LED linear surface/suspended mounted luminaire, PureLine Slim or equivalent, with aluminium extruded housing of 75 mm width and 1120 mm length, 6500K colour temperature, with LED light source, suitable integral LED driver/PSU, up and down light distribution, complete with all accessories required for surface/suspended mounting, including necessary suspension arrangement, end plates, connectors, complete as required.	20	Nos.	4,167.00	Each	83,340.00

S.no.	Description of items	Quantity.		Rate	Unit	Amount
35	supplying of LED Post Top Luminaire, complete with LED light source and integral driver, having rated power consumption 40 W, luminous flux 4000 lumen, system efficacy 100 lm/W, correlated colour temperature 5700 K (cool white), colour rendering index CRI ≥70, symmetrical light distribution with 120° beam angle, die-cast aluminium housing with UV-stabilized polycarbonate optical cover, suitable for pole mounting, IP66 ingress protection and IK10 impact protection, power factor ≥0.90, Class-I electrical protection, suitable for 120–277 V, 50 Hz AC supply, dimmable through analogue interface, LED life L70B50 ≥50,000 hours, complete with integral control gear/driver, mounting accessories and all other accessories required for proper installation and satisfactory operation, as required.	4	Nos.	10,418.00	Each	41,672.00
36	Supplying of recessed mounted aluminium extruded square LED luminaire of size 600 mm x 600 mm, complete with high-efficiency LED light source and integral LED driver, having rated power 32 W, luminous flux 3000 lumens or better, colour temperature 3000-6500 K (cool white), CRI ≥80, suitable for general office/institutional indoor applications, with suitable optical system/diffuser with diffused compartment for uniform and glare-controlled illumination, high-quality aluminium housing with white finish, suitable for recessed ceiling mounting, operating on 220–240 V AC, 50 Hz supply, power factor 0.90 or better, complete with all necessary accessories, connectors, mounting clips and other fittings required for proper installation and operation, LM 79 & 80 test report as per BIS etc. complete as required.	25	Nos.	6,305.00	Each	1,57,625.00
37	Supplying of LED bulkhead with IP65 protection, suitable for surface and wall mounting application, 6.5 W LED, CCT 3000-6500 K, 700 lumen, with integral driver, aluminium die-cast housing and polycarbonate cover, complete as required.	10	Nos.	548.00	Each	5,480.00
38	Supplying of 25 mm dia flexible pipe/tube, suitable for protection and routing of electrical wires/cables, manufactured from good quality flame-retardant PVC material, flexible, lightweight and resistant to moisture, corrosion and normal mechanical stresses, etc. complete as required.	1000	Mtrs	16.00	Each	16,000.00
	Total					**25,57,223.00**

Assistant Engineer (E)(P)
VBED, CPWD, Jodhpur Officer Hostel
New Delhi-110003

Executive Engineer (E)
VBED, CPWD, Jodhpur Officer Hostel
New Delhi-110003