GOVERNMENT OF INDIA
CENTRAL PUBLIC WORKS DEPARTMENT

NIT No. 22/EE/ BFD-IV/ IBBZ-I/2026-2027

For the work

Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.

Executive Engineer
Border Fencing Division-IV, IBBZ-I, CPWD,
Nabapally Co-operative Bank Building, Barasat-700126
Phone No: (033)-25422870, Email: ntfpee-bfc4@cpwd.gov.in

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. EE/BFD-IV.

BLANK

Addition	**-**	**Nil**
Deletion	**-**	**Nil**
Overwriting	**-**	**Nil**
Correction	**-**	**Nil**

AE(P)/BFD-IV. **EE/BFD-IV.**

Notice to be uploaded on website

Name of work	Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.
Estimated cost	**₹ 69,94,739.00**
Earnest Money	**₹ 1,39,895.00**
Performance Guarantee	PG shall be : a) 5% of tendered value or Estimated Cost Put to Tender (ECPT) (Whichever is Higher). b) Where the tendered amount is less than eighty percent (80%) of the Estimated Cost Put to Tender (ECPT), the Performance Guarantee, in addition to the requirement under (a) above, shall be increased by an amount equal to the difference between eighty percent (80%) of the ECPT and the tendered amount.
Security Deposit	**2.50 % of Tendered Value**
Period of Completion	**45(forty-five) days**
NIT No.	**22/EE/ BFD-IV/ IBBZ-I/2026-2027**
Last date for submission of Bid	**Up to 03.00 pm on 05.12.2026**

Executive Engineer,
Border Fencing Division-IV,
CPWD, IBBZ-I, Barasat-700126

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

BLANK

Addition	**-**	**Nil**
Deletion	**-**	**Nil**
Overwriting	**-**	**Nil**
Correction	**-**	**Nil**

AE(P)/BFD-IV. **EE/BFD-IV.**

INDEX

Name of Work: Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.

Sl.No.	Description	Page
1	Index Page	05
2	Notice Inviting e-Tender	06
3	Check List For Contractors For Submission of Tenders Online	07
4	Information and instructions for bidders for e-tendering	08-10
5	Proforma for receipt to be issued by the EE receiving the EMD	11
	Part-A	12
6	C.P.W.D - 6 for e-Tendering	13-17
7	Percentage rate of e-tender & contract for works CPWD – 7	18-19
8	Acceptance	20
9	Form of Bank Guarantee for Performance Guarantee/Security Deposit	21-23
	Part-B	24
10	Proforma of Schedules	25-31
11	Amendments to GCC 2023 for Maintenance Works	32
12	List Of Minimum Equipment "Annexure-A"	33
13	List Of Machinery, Tools & Plants. "Annexure-B"	34
14	General Rules and Directions	35-40
15	Salient Requirements for the Tender	41
16	Additional conditions	42-45
17	Special conditions	46
18	Particular specification for Road work	47-49
19	List of Preferred Makes of Materials	50
20	Schedule of quantities	51-52
21	Proforma for quoting tender	53

This NIT contains 1 to 53 (One to Fifty-three) Pages.

NIT No : 22/EE/ BFD-IV/ IBBZ-I/2026-2027

"This NIT is approved for an amount of ₹ 69,94,739.00 (Rupees Sixty-Nine Lakh Ninety-Four Thousand Seven Hundred Thirty -Nine only)."

Addition	**- Nil**
Deletion	**- Nil**
Overwriting	**- Nil**
Correction	**- Nil**

AE(P)/BFD-IV. **EE/BFD-IV.**

CENTRAL PUBLIC WORKS DEPARTMENT
NOTICE INVITING e-TENDER

The Executive Engineer, **The Executive Engineer, BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal** on behalf of the President of India invites online percentage rate e-bids from approved and eligible contractors of CPWD in Building and Roads category of appropriate class for the following work:-

NIT No : 22/EE/ BFD-IV/ IBBZ-I/2026-2027

Name of Work: Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to BP No. 31/7-S including link Road (3.30 Km) during the year 2025-2026. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.

Estimated Cost : ₹ 69,94739.00

Earnest Money :₹1,39,895.00

Period of Completion: 45(forty five) days.

Last date and time of submission of bid on **05.12.2026 Upto 15:00 Hrs.**

The bid forms and other details can be obtained from website https://etender.cpwd.gov.in or https://eauction.cpwd.gov.in or https://www.cpwd.gov.in

Addition	**- Nil**
Deletion	**- Nil**
Overwriting	**- Nil**
Correction	**- Nil**

AE(P)/BFD-IV. **EE/BFD-IV.**

Check List For Contractors For Submission Of Tenders Online:

1. Tender to be witnessed at specified page of tendered documents at the time of drawing agreement with the successful bidder.

2. The tender / tenders containing conditions contrary to those specified in this document shall
be summarily rejected.

3. In schedules of quantities appended to the tender documents, the rates in terms of overall
percentage above or below the total estimated amount put to tender must be filled both in
figures and words on specified page of tender document.

4. The contractor/ agency shall quote the rate keeping in view that they have to give a undertaking before award of work that "they will install/ arrange field testing instruments and essential T&P/ technical representatives specified in the tender document/specification.

5. It will be mandatory to first refer any dispute related to execution of this work to the conciliator. Contractor or department can only seek arbitration if not satisfied with the decision of the conciliator. This should be read along with provisions of clause 25 of GCC 2023 for Maintenance works duly amended & modified with corrections up to date of submission of tender.

6. All expenditure to be incurred for testing of samples e.g. packaging, sealing, transportation, loading, unloading etc. including testing charges shall be borne by the contractor.

Addition	**- Nil**
Deletion	**- Nil**
Overwriting	**- Nil**
Correction	**- Nil**

AE(P)/BFD-IV. **EE/BFD-IV.**

INFORMATION & INSTRUCTIONS FOR BIDDERS for e-TENDERING

The **Executive Engineer, Border Fencing Division-IV, CPWD, Barasat, West Bengal (e- mail:** : **ntfpee-bfd4@cpwd.gov.in)(Phone no *033-25422870, Mobile No. 9433581744)** on behalf of the President of India invites online percentage E-bids from CPWD enlisted contractor of appropriate class in Building & Roads category for the following work:

NIT No	**22/EE/ BFD-IV/ IBBZ-I/2026-2027**
Name of work	**Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to BP No. 31/7-S including link Road (3.30 Km) during the year 2025-2026. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.**
Location	**North 24 Paraganas at IBBZ-I under BFD-IV, Barasat**
Estimated cost put to bid	**₹ 69,94,739.00**
Earnest Money	**₹ 1,39,895.00**
Period of Completion	**45(forty five) days.**
Last date & time of online submission of bid, copy of earnest money declaration and other documents as specified in NIT	**Up to 15:00 Hrs. on 05.12.2026**
Time & date of opening of bid	**At 15:30 Hrs. on 05.12.2026**

1. The intending bidder must read the terms and conditions of CPWD-6 carefully. He should only submit his bid if he considers himself eligible and he is in possession of all the documents required.
2. Information and instructions for bidders posted on website shall form part of bid document.
3. The bid document consisting of plans, the schedule of quantities of various types of items to be executed and the set of terms & conditions of the contract to be complied with and other necessary documents can be seen and downloaded from website https://etender.cpwd.gov.in or https://eauction.cpwd.gov.in or https://www.cpwd.gov.in**free of cost.**
4. But the bid can only be submitted after deposition of original EMD either in the office of Executive Engineer inviting bids or division office of any Executive Engineer, CPWD within the period of bid submission and uploading the mandatory scanned documents such **as Insurance Surety Bonds, Account Payee** Demand draft or Bankers Cheque or Fixed Deposit Receipts or/ and Bank Guarantee (**for balance amount as prescribed)** from any of **the Commercial** Bank towards EMD in favour of **The Executive Engineer, BFD-IV, CPWD, IBBZ-I, Barasat,** as mentioned in NIT, receipt for deposition of original EMD to division office of any Executive Engineer (including NIT issuing EE/AE), CPWD and other documents as specified. **(AS PER DG/SOP/37 dt.04.05.2022).**
   A part of earnest money is acceptable in the form of Bank Guarantee also. In such case, 50% of Earnest Money of Rs. 20 lacs, whichever is less, shall have to be deposited in the said prescribed above, and balance may be deposited in shape of Bank Guarantee of any schedule bank having validity for

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

6(six) months or more from the last date of receipt of Bids which is to be scanned and uploaded by the intending bidders.

5. Those bidders, not registered on the website mentioned above, are required to get registered themselves beforehand. If needed they can be imparted training on online bidding process as per details available on the website.

6. The intending bidder must have valid class-III digital signature to submit the bid.
7. On opening date, the Bidder can login and see the bid opening process. After opening of bids, he will receive the competitor bid sheets.
8. Contractor can upload documents in the form of JPG format and PDF format.
9. Contractor must ensure to quote percentage rate of Civil and Electrical component as given in the template. In addition to this, while selecting any of the cells a warning appears that if any cell is left blank the same shall be treated as **"0"**. Therefore, if any cell is left blank and no rate is quoted by the bidder, rate of such item shall be treated as **"0" (ZERO).**However, if a tenderer quotes nil rates against ~~each item in item rate tender~~ or does not quote any percentage above/below on the total amount of the tender or any section / sub head in percentage rate tender, the tender shall be treated as invalid and will not be considered as lowest tenderer.
10. Contractor should quote the percentage above or below to two places of decimal only.
11. The officer inviting tenders shall have the right of rejecting all or any of the tenders and will not be bound to accept the lowest or any other tender.
12. The Contractor shall be deemed to have satisfied himself before tendering as to the correctness and sufficiency of his tender for the works and of the rates and prices quoted in the Schedule of Quantities, which rates and prices shall, except as otherwise provided, cover all his obligations under the Contract and all matters and things necessary for the proper completion and maintenance of the works.(if any)
13. If there are varying or conflicting provisions made in any one document forming part of the contract, the Accepting Authority shall be the deciding authority with regard to the intention of the document and his decision shall be final and binding on the contractor.
14. Any error in description, quantity or rate in Schedule of Quantities or any omission there from shall not vitiate the Contract or release the Contractor from the execution of the whole or any part of the works comprised therein according to drawings and specifications or from any of his obligations under the contract.
15. In Case of extension of agreement due to delay/reduction in scope of work; no claim on account of reduction in value of work, loss of business, loss of profit, consequently overheads, any type of interest etc shall be entertained.
16. The bidder may see the site of work physically, its accessibility, way and means for mobilization, manpower at project site etc. and other related activities, before quoting his rates. If any repairs / restorations required in connecting feeder road / link road / approach road for making it motorable during execution period, nothing extra shall be payable to the bidder and also no hindrance / delay on this a/c shall be entertained. The rates shall be inclusive of all the activities for carrying out to complete the work including material, T & P, labour and other inputs required, unless otherwise specified in the bid document, nothing extra shall be paid on these accounts.

17. Intending Bidders are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their bids as to the nature of the ground and sub-soil (so far as is practicable), the form and nature of the site, the means of access to the site, the accommodation they may require and in general shall themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their bid. A bidders shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charge consequent on any misunderstanding or otherwise shall be allowed. The bidders shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work unless otherwise specifically provided for in the contract documents. Submission of a bid by a bidder implies that he has read this notice and all other contract documents and has made himself aware of the scope and specifications of the work to be

done and of conditions and rates at which stores, tools and plant, etc. will be issued to him by the Government and local conditions and other factors having a bearing on the execution of the work.

18. In addition to above the tenderer shall fully acquaint himself about the conditions with regard to site , nature of soil , availability of material , suitable location for construction of godowns , stores and labour huts ,the extend of leads and lifts involved in the work (over the entire duration of the contract) including local conditions , landslides , avalanches , snowfalls, terrain , atmospheric temperature, rainfall , humidity, altitude , labour availability , working window in the different season, working culture , traffic restrictions and other conditions ,as required for satisfactory execution of the works. His rates shall take into consideration all such factors and contingencies. No claim whatsoever shall be entertain by the department on this account. No claim against monsoon (Rainy) season w.e.f June to September every year whatsoever shall be entertained by the department as hindrance.

19. List of Documents to be scanned and uploaded within the period of bid Submission:

1	Copy of receipt for deposition of original EMD to division office of any Executive Engineer (including NIT issuing EE/AE), CPWD. Form of earnest money deposit in **Form – A. <u>The EMD document shall only be issued from the place in which the office of receiving division office is situated.</u>**
2	Insurance Surety Bond, Account Payee Demand draft, Fixed Deposit Receipts, Bankers Cheque or Bank Guarantee against EMD. EMD deposit to be drawn in favour of **The Executive Engineer, BFD-IV, CPWD, IBBZ-I, Barasat, W.B**. Copy of EMD document is also to be uploaded.
3	Enlistment Order of Contractor.
4	GST Registration Certificate of the State in which the work is to be taken up, if already obtained by the bidder. If the bidder has not obtained GST registration in the state as applicable, then in such case the bidder shall scan and upload following undertaking along with other bid documents."If work is awarded to me, I/We shall obtain GST registration Certificate as applicable, within one month from the date of receipt of award letter or before release of any payment by CPWD, whichever is earlier, falling which I/We shall be responsible for any delay in payments which will be due towards me/us on a/c of the work executed and/or for any action taken by CPWD or GST department in this regard."
5	ERP Training Certificate of Bidder.
6	Valid PAN as issued by Income tax department.
7	Any other Document as specified in the NIT.

<u>If the above-mentioned documents are not scanned and uploaded within the period of bid submission, the bid shall be treated as invalid and cancelled.</u>

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

Form – A.

PROFORMA FOR THE RECEIPT TO BE ISSUED BY THE EE RECEIVING THE EMD

Receipt of deposition of original EMD (Receipt……/ dated……)

Name of work :- Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.

NIT No. **22/EE/ BFD-IV/ IBBZ-I/2026-2027**

Estimated Cost: **₹ 69,94,739.00**

Amount of Earnest Money Deposit: **₹ 1,39,895.00**

Last date of submission of bid : **05.12.2026 up to 15:00 Hrs.**

Name of contractor ……*

Form of EMD……*

Amount of Earnest Money Deposit……*

Date of Submission of EMD……*

Signature, Name and Designation of EMD receiving Officer
(EE/AE(P)/AO/AAO) along with Office Stamp

(*To be filled by EMD receiving EE)

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

PART - A

Addition	-	Nil
Deletion	-	Nil
Overwriting	-	Nil
Correction	-	Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

CPWD-6 FOR e-Tendering

1. The Executive Engineer, BFD-IV, IBBZ-I, Central Public Works Department, Barasat on behalf of President of India invites online percentage rate Single Bid Tender from approved and eligible contractors of CPWD enlisted in appropriate class & category of CPWD for the work of:

Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.

The enlistment of the contractors should be valid on the last date of submission of tender. In case the last date of submission of bid is extended, the enlistment of contractor should be valid on the original date of submission of bids.

1.1 The work is estimated to cost **₹ 69,94,739.00** this estimate, however, is given merely as a rough guide.

1.1.1 The authority competent to approve NIT for the combined cost and belonging to the major discipline will consolidate NITs for calling the bids. He will also nominate Division which will deal with all matters relating to the invitation of bids. For composite bid, besides indicating the combined estimated cost put to bid, should clearly indicate the estimated cost of each component separately. The eligibility of bidders will correspond to the combined estimated cost of different components put to bid.

2. Agreement shall be drawn with the successful bidder on prescribed Form No. CPWD 7 (or other Standard Form as mentioned) which is available as a Govt. of India Publication and also available on website www.cpwd.gov.in. Bidders shall quote his rates as per various terms and conditions of the said form which will form part of the agreement.

3. The time allowed for carrying out the work will be **03 (Three) Months** from the date of start as defined in schedule 'F' or from the first date of handing over of the site, whichever is later, in accordance with the phasing, if any, indicated in the tender documents.

4. (i) The site for the work is available. The site for the work is available.
(ii) The architectural and structural drawing for the work is available.
(iii) The architectural and structural drawings shall be made available in phased manner, as per requirement of the same as per approved program of completion submitted by the Contractor after award of work.

5. The bid document consisting of plans, specifications, the schedule of quantities of various types of items to be executed and the set of terms and conditions of the contract to be complied with and other necessary documents except Standard General Conditions of Contract Form can be seen on website **https://etender.cpwd.gov.in or www.cpwd.gov.in** free of cost.

6. After submission of the bid the contractor can re-submit revised bid any number of times but before last time and date of submission of tender as notified.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

7. While submitting the revised bid, contractor can revise the rate of one or more item(s) any number of times (he need not re-enter rate of all the items) but before last time and date of submission of bid as notified.

8. Earnest Money in the form of Insurance Surety Bonds, Account Payee Demand Draft, Fixed Deposit Receipt, Banker's Cheque or Bank Guarantee including e- Bank Guarantee (for balance amount as prescribed) from any of the Commercial Banks **(drawn in favour of Executive Engineer, BFD-IV, CPWD, IBBZ-I, Barasat)** shall be scanned and uploaded on the e-Tendering website within the period of bid submission. The original EMD should be deposited either in the office of Executive Engineer inviting bids or division office of any Executive Engineer, CPWD within the period of bid submission. The EMD receiving Executive Engineer (including NIT issuing EE/AE) shall issue a receipt of deposition of earnest money deposit to the bidder in a prescribed format (enclosed) uploaded by tender inviting EE in the NIT. A part of earnest money is acceptable in the form of bank guarantee also. In such case, minimum 50% of earnest money or **₹ 20 lakh**, whichever is less, shall have to be deposited in shape prescribed above, and balance may be deposited in shape of Bank Guarantee including e- Bank Guarantee of any Commercial bank having validity for a period of 90 days for single bid works and 180 days for two bid system or more from the last date of receipt of bids which is to be scanned and uploaded by the intending bidders.

The earnest money given by all the tenderers except the lowest tenderer shall be refunded immediately after the expiry of stipulated bid validity period or immediately after acceptance of the bid of successful bidder, whichever is earlier. However, in case of two/three bid system, earnest money deposit of bidders unsuccessful during technical bid evaluation etc. should be returned within 30 days of declaration of result of technical bid evaluation.

Copy of Enlistment Order and certificate of work experience and other documents as specified in the notice inviting e- tender shall be scanned and uploaded on the e-Tendering website within the period of bid submission. However, certified copy of all the scanned and uploaded documents as specified in e- tender notice shall have to be submitted by the lowest bidder only, within a week physically in the office of tender opening authority. Online tender documents submitted by intending bidders shall be opened only of those bidders, whose original EMD deposited in prescribed manner with any division of CPWD and other documents scanned and uploaded are found in order.

The tender submitted shall be opened at **15:30 Hrs on 05.12.2026**

9. The bid submitted shall become invalid and e-Tender processing fee (if applicable) shall not be refunded if:

(i) The bidder is found ineligible.
(ii) The bidder does not upload scanned copies of all the documents stipulated in the bid document.
(iii) If any discrepancy is noticed between the documents as uploaded at the time of submission of bid and hard copies as submitted physically by the lowest bidder in the Office of tender opening authority.
(iv) If a tenderer quotes nil rates against each item in item rate tender or does not quote any percentage above/below on the total amount of the tender or any section / sub head in percentage rate tender, the tender shall be treated as invalid and will not be considered as lowest tenderer. (OM No. DG/SOP 2022/07 dated 09.11.2022)

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

10. The contractor shall not be permitted to bid for works in the CPWD Circle (Division in case of contractors of Horticulture/ Nursery category) responsible for award and execution of contracts, in which his near relative is posted a Divisional Accountant or as an officer in any capacity between the grades of Superintending Engineer and Junior Engineer (both Inclusive). He shall also intimate the names of persons who are working with him in any capacity or are subsequently employed by him and who are near relatives to any gazetted officer in the Central Public Works Department or in the Ministry of Housing and Urban Affairs. Any breach of this condition by the contractor would render him liable to be removed from the approved list of contractors of this Department.

11. The contractor whose bid is finally accepted will be required to furnish performance guarantee of specified amount within the period as specified in **Schedule F**. This guarantee shall be in the form Insurance Surety Bonds, Account payee Demand Draft, Fixed deposit Receipt or Bank Guarantee from any of the commercial banks in accordance with the prescribed form given in NIT. In case the contractor fails to deposit the said performance guarantee within the period as indicated in Schedule F, including the extended period if any, the Earnest Money deposited by the contractor shall be forfeited automatically without any notice to be contractor. The earnest money deposited along with bid shall be returned after receiving the aforesaid performance guarantee. The contractor whose bid is accepted will also be required to furnish either copy of applicable licenses/registrations or proof of applying for obtaining labour licenses, registration with EPFO, ESIC, and BOCW Welfare Board including Provident Fund Code No. if applicable and also ensure the compliance of aforesaid provisions by the sub-contractors, if any engaged by the agency for the said work within the period specified in Schedule-F.

12. The description of the work is as follows:

Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.

Intending Bidders are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their bids as to the nature of the ground and sub-soil (so far as is practicable), the form and nature of the site, the means of access to the site, the accommodation they may require, the limited working hours, difficulties in access to site and in general shall themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their bid. A bidders shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charge consequent on any misunderstanding or otherwise shall be allowed. The bidders shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity access, facilities for workers and all other services required for executing the work unless otherwise specifically provided for in the contract documents. Submission of a bid by a bidders implies that he has read this notice and all other contract documents and has made himself aware of the scope and specifications of the work to be done and of conditions and rates at which stores, tools and plant, etc. will be if issued to him by the Government and local conditions and other factors having a bearing on the execution of the work.

In addition to above the tenderer shall fully acquaint himself about the conditions with regard to site , nature of soil , availability of material , suitable location for construction of godowns, stores

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

and labour huts, the extent of leads and lifts involved in the work (over the entire duration of the contract) including local conditions of site, bad weather, landslides, avalanches, snowfalls, hilly terrain, atmospheric temperature, rainfall, humidity, altitude, labour availability, working window in the different season, working culture, traffic restrictions and other conditions as required for satisfactory execution of the works. His rates shall take into consideration all such factors and contingencies. No extra claim whatsoever on this account shall be entertained by the department. **No hindrance shall be allowed for normal monsoon seasons from June to Sept every year**.

13. The competent authority on behalf of the President of India does not bind itself to accept the lowest or any other bid and reserves to itself the authority to reject any or all the bids received without the assignment of any reason. All bids in which any of the prescribed condition is not fulfilled or any condition including that of conditional rebate is put forth by the bidders shall be summarily rejected.

14 Canvassing whether directly or indirectly, in connection with bidders is strictly prohibited and the bids submitted by the contractors who resort to canvassing will be liable for rejection.

15. The competent authority on behalf of President of India reserves to himself the right of accepting the whole or any part of the bid and the bidders shall be bound to perform the same at the rate quoted.

16. No Engineer of Gazetted Rank or other Gazetted Officer employed in Engineering or Administrative duties in an Engineering Department of the Government of India is allowed to work as a contractor for a period of one year after his retirement from Government service, without the prior permission of the Government of India in writing. This contract is liable to be cancelled if either the contractor or any of his employees is found any time to be such a person who had not obtained the permission of the Government of India as aforesaid before submission of the bid or engagement in the contractor's service.

17. The bid for the works shall remain open for acceptance for a period of **30 (Thirty) days** from the date of opening of bids in case of single bid system and 75 (seventy five) days from the date of opening of technical bids in case bids are invited in 2 or 3 bid system. Further :

(i) If any tenderer withdraws his tender or makes any modification in the terms & conditions of the tender which is not acceptable to the department within 7(seven) days after last date of submission of bids, then the Government shall without prejudice to any other right or remedy, be at liberty to forfeit 50% of the earnest money absolutely irrespective of letter of acceptance for the work is issued or not.

(ii) If any tenderer withdraws his tender or makes any modification in the terms & conditions of the tender which is not acceptable to the department after expiry of 7(seven) after last date of submission of bids, then the Government shall without prejudice to any other right or remedy, be at liberty to forfeit 100% of the earnest money absolutely irrespective of letter of acceptance for the work is issued or not.

(iii) In case of forfeiture of earnest money for the reasons as described in para (i) and (ii) above, the bidders shall not be allowed to participate in the rebidding process of the same work. Further disciplinary proceedings may be recommended by the EE-in-charge to the Enlistment Authority for disciplinary action against the Contractor.

18. This notice inviting Bid shall form a part of the contract document. The successful bidder/ contractor, on acceptance of his bid by the Accepting Authority shall within 07 days from the stipulated date of start of the work, sign the contract consisting of:-

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

a) The Notice Inviting Bid, all the documents including additional conditions, specifications and drawings, if any, forming part of the bid as uploaded at the time of invitation of bid and the rates quoted online at the time of submission of bid and Acceptance thereof together with any correspondence leading thereto.

b) Standard C.P.W.D. Form 7 or other Standard C.P.W.D. Form as applicable.

19. Integrity Pact: The contractor shall download the Integrity Pact, which is a part of tender documents, affix his signature in the presence of a witness, and upload the same while submitting online bids for all works of estimated cost put to tender equal or more than the threshold value given in Schedule-F. In the event of his failure to sign and upload the Integrity Pact along with other bid documents, his bid shall be rejected.

20. The intending bidders are required to update their profile in CPWD e- tender portal and to upload their bids well in advance of last date of submission of tender. Any issue related to updating profile / uploading tender can be resolved through the concerned Executive Engineer/ Assistant Engineer (P) (Phone No. *033-25422870, Mobile No. 9433581744, e-mail Id: ntfpee-bfd4@cpwd.gov.in or ERP helpline No. 18001803286 or e-mail ld cpwd.support@techmahindra.com. The e- tendering bidders are also advised not to wait to raise any issues till the last date of submission of bid in their own interest.

Executive Engineer,
Border Fencing Division-IV,
CPWD, IBBZ-I, Barasat-700126
(For and on behalf of President of India)

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

CPWD – 7

GOVERNMENT OF INDIA
CENTRAL PUBLIC WORKS DEPARTMENT

State	:	West Bengal.	Circle	:	BFC-II, Krishnanagar
Branch	:	B & R.	Division	:	BFD-IV, Barasat.
Zone	:	IBB Zone-I.			

Percentage Rate of e-tender & Contract for Works

Tender for the work of: Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.

(i) To be submitted by 03:00 PM on 05.12.2026

(ii) To be opened online at 03:30 PM on 05.12.2026 in the office of Executive Engineer, BFD-IV, IBBZ-I, CPWD, Barasat.

T E N D E R

I/We have read and examined the notice inviting tender, schedule, A, B, C, D, E & F, Specifications applicable, Drawings & Designs, General Rules and Directions, Conditions of contract, clauses of contract, Special conditions, Schedule of Rate & other documents and Rules referred to in the conditions of contract and all other contents in the tender document for the work.

I/We hereby tender for the execution of the work specified for the President of India within the time specified in Schedule 'F', viz., schedule of quantities and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule-1 of General Rules and Directions and in Clause 11 of the conditions of contract and with such materials as are provided for, by, and in respects in accordance with, such conditions so far as applicable.

I/We agree to keep the tender open for **thirty (30) days** from the due date of its opening and not to make any modifications in its terms and conditions.
I/We have deposited EMD for the prescribed amount in the office of concerned Executive Engineer as per the bid document.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

A copy of the earnest money deposit receipt of prescribed amount deposited in the form of Insurance surety Bonds, A/C payee Demand Draft, Fixed Deposit Receipt, Banker's Cheque or Bank Guarantee (as prescribed) issued by commercial banks is scanned and uploaded.

If I/We, fail to furnish the prescribed performance guarantee of tender form within prescribed period, I/We agree that the said President of India or his successors in office shall, without prejudice to any other right or remedy, be at liberty to forfeit the said earnest money absolutely. Further, if I/we fail to commence work as specified, I/we agree that President of India or his successors in office shall without prejudice to any other right or remedy available in law, be at liberty to forfeit the said performance guarantee absolutely. The said Performance Guarantee shall be a guarantee to execute all the work referred to in the tender document upon the term and condition contained or referred to those in excess of that limit at the rates to be determined in accordance with the provision contained in clause 12.2 and 12.3 of the tender form.

Further I/We agree that in case of forfeiture of earnest money or performance guarantee as aforesaid, I/We shall be debarred for participation in the re-tendering process of the work.
I/We undertake and confirm that eligible similar work(s) has / have not been got executed through another contractor on back to back basis. Further that, if such a violation comes to the notice of Department, then I/we shall be debarred for tendering in CPWD in future forever. Also, if such a violation comes to the notice of Department before date of work, the Engineer-in-Charge shall be free to forfeit the entire amount of Earnest Money Deposit /Performance Guarantee.
I/We hereby declare that I/We shall treat the tender documents drawings and other records connected with the work as secret/confidential documents and shall not communicate information derived there from to any person other than a person to whom I/we am/are authorized to communicate the same or use the information in any manner prejudicial to the safety of the state.

Dated _____*_____

Signature of Contractor
Postal Address_____*_____
_____*_____

Witness: **_____ _____
Address: **_____
Occupation: **_____

Telephone No._____*_____
Fax _____*_____
E-Mail_____*_____

(*) To be filled in by the Contractor

(**) To be filled in by the Witness.

****** - To be filled in by EE**

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

ACCEPTANCE

The above tender (as modified by you as provided in the letters mentioned hereunder) is accepted by me for and on behalf of the President of India for a sum of Rs…..... (Rupees…….. ……)

The letters referred to below shall form part of this contract Agreement:-

(i)

(ii)

(iii)

For & on behalf of the President of India

Signature…… ……

Dated…… ……

Designation…… ……

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV**.

On non-judicial stamp paper of minimum Rs. 100

(Guarantee offered by Bank to CPWD in connection with the execution of contracts)

Form of Bank Guarantee for Earnest Money Deposit / Performance Guarantee / Security Deposit / Mobilization Advance

1.

2. Whereas the Executive Engineer ..... (name of division) ..... CPWD on behalf of the President of India (hereinafter called "The Government") has invited bids under ..... (NIT number) ..... dated ..... for..... (name of work) ..... The Government has further agreed to accept irrevocable Bank Guarantee for Rs. ..... (Rupees .... only) valid upto ..... (date)*..... as Earnest Money Deposit from ..... (name and address of contractor) ..... (hereinafter called "the contractor") for compliance of his obligations in accordance with the terms and conditions of the said NIT.

OR**

Whereas the Executive Engineer ..... (name of division) ....., CPWD on behalf of the President of India (hereinafter called "The Government") has entered into an agreement bearing number ..... with ..... (name and address of the contractor) ..... (hereinafter called "the Contractor") for execution of work .... (name of the work) .... The Government has further agreed to accept an irrevocable Bank Guarantee for Rs. ..... (Rupees .... only) valid upto ..... (date) ..... as Performance Guarantee / Security Deposit/ Mobilization Advance from the said Contractor for compliance of his obligations in accordance with the terms and conditions of the agreement.

3. We, ... (indicate the name of the bank) ..... (herein after referred to as "the Bank"), hereby undertake to pay to the Government an amount not exceeding Rs ..... (Rupees ..... only) on demand by the Government within 10 days of the demand.

4. We, ... (indicate the name of the Bank) ....., do here by undertake to pay the amount due and payable under this guarantee without any demur, merely on a demand from the Government stating that the amount claimed is required to meet the recoveries due or likely to be due from the said contractor. Any such demand made on the Bank shall be conclusive as regards the amount due and payable by the Bank under this Guarantee. However, our liability under this guarantee shall be restricted to an amount not exceeding Rs. ..... (Rupees ..... only)

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

5. We, ... (indicate the name of the Bank) ..... , further undertake to pay the Government any money so demanded notwithstanding any dispute or disputes raised by the contractor in any suit or proceeding pending before any Court or Tribunal, our liability under this Bank Guarantee being absolute and unequivocal. The payment so made by us under this Bank Guarantee shall be a valid discharge of our liability for payment there under and the contractor shall have no claim against us for making such payment.

6. We, ... (indicate the name of the Bank) ....., further agree that the Government shall have the fullest liberty without our consent and without affecting in any manner our obligation here under to vary any of the terms and conditions of the said agreement or to extend time of performance by the said Contractor from time to time or to postpone for any time or from time to time any of the powers exercisable by the Government against the said contractor and to forbear or enforce any of the terms and conditions rerating to the said agreement and we shall not be relieved from our liability by reason of any such variation or extension being granted to the said Contractor or for any forbearance, act of omission on the part of the Government or any indulgence by the Government to the said Contractor or by any such matter or thing whatsoever which under the law relating to sureties would, but for this provision, have effect of so relieving us.

7. We, ... (indicate the name of the Bank) ....., further agree that the Government at its option shall be entitled to enforce this Guarantee against the Bank as a principal debtor at the first instance without proceeding against the Contractor and notwithstanding any security or other guarantee the Government may have in relation to the Contractor's liabilities.

8. This guarantee will not be discharged due to the change in the constitution of the Bank or the Contractor.

9. We, ... (indicate the name of the Bank) ....., undertake not to revoke this guarantee except with the consent of the Government in writing.

10. This Bank Guarantee shall be valid up to .....unless extended on demand by the Government. Notwithstanding anything mentioned above, our liability against this guarantee is restricted to Rs. ..... (Rupees ..... only) and unless a claim in writing is lodged with us within the date of expiry or extended date of expiry of this guarantee, all our liabilities under this guarantee shall stand discharged. with us within the date of expiry or extended date of expiry of this guarantee, all our liabilities under this guarantee shall stand discharged.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

Date .....

Witnesses:

1. Signature .....
   Name and address

Authorized signatory
Name

Designation

Staff code no.

2. Signature .....
   Name and address

Bank seal

* Date to be worked out on the basis of validity period of 90 days where only financial bids are invited and 180 days for two / three bid system from the date of submission of tender.

** In Paragraph 1, strike out the portion not applicable. Bank Guarantee will be made either for earnest money or for performance guarantee / security deposit / mobilization advance, as the case may be.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

PART B

Addition	-	Nil
Deletion	-	Nil
Overwriting	-	Nil
Correction	-	Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

PROFORMA OF SCHEDULES

SCHEDULE 'A'

Schedule of Quantities : See at pages from: **51 to 52**.

SCHEDULE 'D'

Extra schedule for specific requirements/ documents for the work, if any.— : **As mentioned in tender document**

SCHEDULE 'E'

Reference to General Conditions of contract : General Condition of Contract for CPWD Maintenance Works–2023 (with upto date amendment upto last date of submission of bid).

Name of work: -" Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal".

Estimated cost of work : **₹ 69,94,739.00**

(i) **Earnest Money** : **₹1,39,895.00** (To be returned after receiving Performance Guarantee).

Performance Guarantee : PG shall be :
a) 5% of tendered value or Estimated Cost Put to Tender (ECPT) (Whichever is higher).
b) Where the tendered amount is less than eighty percent (80%) of the Estimated Cost Put to Tender (ECPT), the Performance Guarantee, in addition to the requirement under (a) above, shall be increased by an amount equal to the difference between eighty percent (80%) of the ECPT and the tendered amount.

(ii) **Security Deposit** : 2.5% of tendered value.

SCHEDULE 'F'
General Rules & Directions:

Officer inviting tender : **Executive Engineer, BFD-IV,CPWD, IBBZ-I, Barasat -700126 or his successor thereof**

Maximum percentage for quantity of items of work to be executed beyond which rates are to be determined in accordance with clauses 12.2 & 12.3 : See under Clause 12 of this proforma of schedule

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

Definitions:

2 (v) Engineer-in-Charge	:	**Executive Engineer, BFD-IV, CPWD, IBBZ-I, Barasat or his successor thereof**
2(vii) Accepting of tender authority	:	**Executive Engineer, BFD-IV, CPWD, IBBZ-I, Barasat -700126**
2(x)Percentage on cost of materials and labour to cover all overheads and profits.	:	15% (fifteen percent)
2(xi) Standard schedule of Rates	:	Market Rate based on DSR- 2023 with up to date correction slips and MoRTH data book
2(xii) Department	:	**CPWD**
9(ii) Standard CPWD contract Form	:	CPWD Form-7 of General Condition of Contract 2023 for Maintenance Work (with upto date amended up to last date of submission of Bid).

Clause 1

i) Time allowed for submission of Performance Guarantee from the date of issue of letter of acceptance, in days.	.....	07
ii) Maximum allowable extension with late fee @0.1% per day of performance guarantee amount beyond the period as provided in (i) above, in days.	.....	03

Clause 2

Authority for fixing compensation under Clause 2	:	Superintending Engineer Border Fencing Circle-II, CPWD, IBBZ-I, Krishnanagar. Or his successor thereof
Whether clause 2A shall be applicable	:	No

Clause 5

Number of days from the date of issue of letter of acceptance for reckoning date of start	:	**10 days**

Mile stone(s) as table given below:

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

Sl. No.	Description of Mile Stone (Physical Progress)	Time allowed in days (from date of start)	Amount to be withheld in case of Non-achievement of each physical Mile stone(s)
1.	**Submission of Job Mix/ Design Mix of appropriate grade of Bituminous Macadam & Bituminous Concrete** as per the schedule and getting proof check. Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal. in **0.50 Km.**	**10 (Ten) Days**	1.00% of tender amount
2.	Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal. In **1.00 Km**	**20(Twenty)Days**	1.00% of tender amount
3.	Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal. In **1.50 Km**	**30(Thirty) Days**	1.00% of tender amount
4.	Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal. In **2.50 Km**	**40(Forty) Days**	1.00% of tender amount
5.	Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal. In **2.804 Km and Completion the work in all respect.**	**45 (Forty five) Days**	1.00% of tender amount
Time allowed for execution of work	:	**45(forty five) days** including non-working period on account of rainy seasons from July to Sept every year. Non-working period will not be considered for hindrance.	

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

Authority to decide:

(i)	Extension of time (Engineer-in-Charge or Engineer-in-Charge of Major Component in case of Composite Contracts, as the case may be) :	Executive Engineer, BFD-IV, CPWD, IBBZ-I, Barasat
(ii)	Rescheduling of mile stones :	Superintending Engineer Border Fencing Circle-II, CPWD, IBBZ-I, Krishnanagar. Or his successor thereof
(iii)	Shifting of date of start in case of delay in handing over of site :	Superintending Engineer Border Fencing Circle-II, CPWD, IBBZ-I, Krishnanagar. Or his successor thereof

Clause 6 :

Computerised measurement book (CMB) / Electronic measurement book (EMB) **:** CMB/EMB (Computerised Measurement Book)

Clause 7 :

Gross work to be done together with net payment / adjustment of advances for material collected, if any, since the last such payment for being eligible to interim payment: **:** **Rs. 0.30 Crore**

Clause 7A

Yes, applicable

Clause 10 A :

List of testing equipment to be provided by the contractor at site lab : As required to conduct the test in the field lab as per specifications/tender documents.

Clause 10 B(i)(ii)(iii)

Clause 10 C

Component of labour expressed **as percent of value of work** **:** ..... **15%**.....

Clause 10 CA: Not Applicable

10C Not Applicable

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

Clause 11	**Specification to be followed for execution of work**	CPWD Specification for works-2019 Vol-I & II with up to date correction slips and as well as IRC recommendation is followed as per applicability till last date of submission of tender (Hereinafter called CPWD specifications also).
Clause 12	Authority to decide deviation upto 1.25 times of tendered amount.	Engineer-in-Charge or successor thereof
	Authority to decide deviation beyond 1.25 times &upto1.5 times of tendered amount.	Superintending Engineer, BFC-II, CPWD, Krishnanagar his successor there of
12.2	The extra item(s) which are available in DSR 2023 shall be paid as per the said schedule rate plus cost index (considered in the estimated cost put to tender) plus/minus percentage above/below quoted on estimated cost put to tender. The extra items(s) which are not available in DSR 2023, the rates shall be determined on the basis of market rates during period of consideration and attached amendment vide No. DG/CON/Construction 2023/03 dt. 06.12.2023 &Page No. – 34 to 41.	
12.3	All the deviated quantities shall be paid at agreement rates.	

Note: However the total cost of works done should not exceed by 1.25 time of Contract value without prior approval of the T.S authority.

Type of work	**Maintenance of road in comprehensive nature**

Clause 16	**Competent Authority for Deciding reduced rates:**	
	For deciding reduced rate for items having value up to 5% of Tendered Amount	Superintending Engineer, BFC-II, CPWD, Krishnanagar or his successor there of
	For deciding reduced rate for items having value more than 5% of Tender Amount	Chief Engineer, IBBZ-I, CPWD, Matigara, Siliguri or successor thereof
Clause 18	List of mandatory machinery, tools & plants to be deployed by the contractor at site.	As per Annexure B (Page 35)
Clause 19C	Authority to decide penalty for each default	Engineer-in-charge
Clause 19D	Authority to decide penalty for each default	Engineer-in-charge
Clause19G	Authority to decide penalty for each default	Engineer-in-charge

Clause 25

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

AS PER OFFICE ORDER NO ISSUED FROM DG, CPWD, Nirman Bhawan, New Delhi vide no DG/CON/317 Dated 28.06.2021

Sl No	Constitution	DRC Committee
1.	Conciliator	ADG Border, CPWD, New Delhi.
2.	Arbitrator Appointing Authority	Chief Engineer, IBBZ-I, CPWD, Siliguri
3.	Place of Arbitration	Kolkata

Clause 32: Requirement of Technical Representative(s) & recovery Rate:

Sl. No	Minimum Qualification of Technical representative	Discipline	Designation	Minimum Experience (Years)	Nos.	Rate at which recovery shall be made from the contractor in the event of not fulfilling provision
1	Graduate Engineer or Diploma Engineer	Civil	Project Manager cum Planning/ quality/site/billing Engineer	2 or 5 respectively	02	**Rs. 15,000/- per month**

Each of the key technical personnel prescribed above shall be provided one mobile communication system (Cell phone) by the contractor for which recovery rate shall be Rs. 2000/- per month per person in case of default.

Assistant Engineers retired from Government services that are holding Diploma will be treated at par with Graduate Engineers.

Clause 38

i) a) Schedule/ statement for determining theoretical quantity of cement & bitumen on the basis of Delhi Schedule of Rates 2023 printed by CPWD. — **D.S.R. 2023 with correction slips up to date, and MoRTH data book**

ii) **Variations permissible on theoretical quantities**

a) Cement — **2% plus/minus**

b) Bitumen all works — **2.5% plus only & nil on minus side**

c) Steel reinforcement and structural steel Sections for diameter, section and category. — **2% plus/minus**

d) All other materials — **Nil.**

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

RECOVERY RATES FOR QUANTITIES BEYOND PERMISSIBLE VARIATION

Sl. No.	Description of Item	Rates in figures and words at which recovery shall be made from the Bidder	
		Excess Beyond permissible variation	Less use beyond the permissible variation
1.	Cement (PPC) conforming to IS: 1489(part-I)	**NIL**	**Not accepted**
2.	Steel reinforcement	**NIL**	**Not accepted**

Amendments to General Conditions of Contract 2023 Maintenance Works

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

The GCC 2023 for maintenance works with upto date correction slips till last date of submission of bid.

Following clauses of GCC 2023 maintenance work are modified as per modification includes in below: -

Sl. No.	O.M. No.	Subject
1.	DG/CON/Maintenance 2023/01 Dated : 10.11.2023	Modification in GCC Maintenance Works 2023 Receipt and refund of EMDs online through e-gateway of SBI for e-tendering as pilot cases – reg
2.	DG/CON/Maintenance 2023/02 Dated : 08.12.2023	Modifications in Conditions of Contract, Clause 5 and schedule F in clause 5 of GCC 2023 Maintenance Works
3.	DG/CON/Maintenance 2023/03 Dated : 18.12.2023	Modifications in Conditions of Contract, Clause 12 and Schedule E and F of GCC 2023 for Maintenance Works
4.	DG/CON/Maintenance 2023/04 dated: 08.02.2024	Modifications in Conditions of Contract and Clause 19 of GCC 2023 for Maintenance Works
5.	DG/CON/Maintenance 2023/05 dated: 01.03.2024	Modifications in Conditions of Contract, Clause 19 and 20 of GCC 2023 for Maintenance Works
6.	DG/CON/Maintenance 2023/06Dated :01.03.2024	Modifications in Clause 7 of GCC 2023 for Maintenance Works
7.	DG/CON/Maintenance 2023/07Dated :05.03.2024	Modification in clause 19 of GCC 2023 for Maintenance Works
8.	DG/CON/Maintenance 2023/08Dated :03.06.2024	Modifications in Clause 36 of GCC 2023 for Maintenance Works
9.	DG/CON/Maintenance 2023/09 Dated: 03.06.2024	Additions in General rules and Directions of GCC 2023 for Maintenance Works
10.	DG/CON/Maintenance 2023/10 Dated: 09.10.2024	Modifications in clause 10A of GCC 2023 for Maintenance Works
11	DG/CON/Maintenance 2023/11 Dated: 29.10.2024	Modification in Conditions of contract Clause 10A of GCC Maintenance works 2023
12	DG/CON/Maintenance 2023/12 Dated: 03.01.2025	Modifications in General Rules and Directions of GCC 2023 for Maintenance Works
14	DG/CON/Construction 2023/14 3Dated: 03.01.2025	Modifications in General Rules and Directions of GCC 2023 for Construction Works
15	DG/CON/Construction 2023/15 3Dated:31.01.2025	Modification in Clause 7A of GCC 2023 for Construction Works

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

Annexure-"A"

LIST OF MINIMUM EQUIPMENTT TO BE PROVIDED IN THE FIELD TESTING LABORATORY BY THE CONTRACTOR AT HIS OWN COST

Sl. No.	Name of Equipment	Numbers
1	Oven – Electrically operated, thermostatically controlled, range upto 200 C sensitivity 1 C	1 No.
2	Platform balance 300 kg capacity	1 No.
3	Balance 20 kg capacity-self indicating type	1 No.
4	Electronic Balance 5 kg capacity accuracy 0.5 gm	2 Nos.
5	Thermometers: Mercury-in-glass thermometer range0 to 250 C Mercury-in-steel thermometer with 30 cmStem, range upto 300 C for bituminous work	2 Nos.
6	Kerosene or gas stove or electric hot plate	1 No.
7	Glass wares, spatulas, wire gauzes, Steel scales, measuring tape, casseroles, Karahis, enamelled trays of assorted sizes, Pestle-mortar, porcelain dishes, gunny bags, Plastic bags, chemicals, digging tools like Pickaxes, shovels etc.	As required
8	Water testing kit	1 set
9	First aid box	1 set
10	Standard measures of 30, 15 and 3 litres capacity along with standard tamping rod	1 set
11	3 m straight edge	1 No.
12	Camber board	1 No.
13	Leveling Instrument	1 No.
14	Set of Brass and metal sieves of required size for testing coarse and fine aggregate.	1 set
15	Graduated measuring cylinder.	2 set

Annexure-"B"

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

LIST OF MACHINERY, TOOLS & PLANTS REQUIRED FOR EXECUTION AT SITE BY THE BIDDER:

Sl. No.	Name of Equipment	Numbers
1	Excavator cum loader	1 No.
2	Vibratory Roller	1 No.
3	Tandem rollers	1 No.
4	Paver finisher equipped with electronic sensor	1 No.
5	Light power road roller	1/~~2~~ Nos.
6	Smooth wheeled roller	1 No.
7	Tippers	2 Nos.
8	Trucks	2 Nos.
9	Sprayer	1 No.
10	Air Compressor (diesel)	1 No.
11	Diesel generator	1 No.
12	Mechanical Broom (Hydraulic)	2 Nos.
13	Water Tanker	2 Nos.
14	Tractor	2 Nos.
15	8-10 tonne smooth wheeled roller	1 No.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

General Rules and Directions

1. In the event of the tender being submitted by a firm, it must be signed separately by each partner thereof or in the event of the absence of any partner, it must be signed on his behalf by a person holding a power holding a power-of attorney authorizing him to do so, such power of attorney to be produced with the tender, and it must disclose that the firm is duly registered under the Indian Partnership Act, 1932.

2. The receipt of an accountant or clerk for any money paid by the contractor will not be considered as any acknowledgment or payment to the officer inviting tender and the contractor shall be responsible for seeing that he procures a receipt signed by the officer inviting tender or a duly authorized Cashier.

3. The contractor shall comply with the provisions of the Apprentices Act 1961, and the rules and orders issued there under from time to time. If he fails to do so, his failure will be a breach of the contract and the Superintending Engineer/Executive Engineer may in his discretion, without prejudice to any other right or remedy available in law, cancel the contract. The contractor shall also be liable for any pecuniary liability arising on account of any violation by him of the provisions of the said Act.

4. The structural and architectural drawings shall at all times be properly correlated before executing any work. However, in case of any discrepancy in the item given in the schedule of quantities appended with the tender and architectural drawings relating to the relevant item, the former shall prevail unless and otherwise given in writing by the Engineer-in-Charge.

5. The tenderer shall study carefully, the drawings, specifications, schedule of quantities and conditions of the tender documents to fully appreciate the scope of work before quoting his rates.

6. The contractors are advised to get acquainted with the proposed work and its site and also study the Architectural Drawings, specifications and special conditions carefully before tendering. No claim of any sort shall be entertained on account of any site conditions and ignorance of specifications and special conditions.

7. The civil work shall be carried out as per **CPWD specifications for works-2019 Vol. I & II** with up to date correction slips and as well as IRC recommendation is followed as per applicability unless otherwise specified in the nomenclature of individual item or in the specifications and special conditions, where specifications are silent, the decision of Engineer-in-Charge shall be final and binding on contractors. Road work shall be executed as per latest MORTH specifications.

8. The rates quoted by the contractor shall be taken as net and nothing extra shall be paid on any account i.e. royalty, cartage, GST and stacking at required places & working in restricted area etc.

9. The rates for different items of work shall apply for all heights and depths, leads and lifts unless otherwise specified in the agreement or specifications applicable to the agreement.

10. Any damage done by the contractor to any existing work during the course of execution of the work shall be made good by him at his own cost.

11. Articles manufactured by the reputed firms and approved by Engineer-in-Charge shall only be used. Only articles classified, as 'first quality' by the manufacturer shall be used unless otherwise specified. In case articles bearing ISI certification are not available in the market, quality of samples brought by the contractor shall be judged by standards laid down in the relevant CPWD specifications. For the items not covered by CPWD specifications relevant BIS standards shall apply. The sample of materials to be brought to site for use in work shall be got approved from the Engineer-in-Charge before actual execution of work.
12. Samples of materials required for testing shall be provided free of cost by the contractor. Testing charges, if any, shall be reimbursed by the department in case the test results are satisfactory except where-ever

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

specifically mentioned otherwise in the NIT. All other expenditure to be incurred for taking samples, conveyance, packing etc. shall be borne by the contractor.

13. The quantities of each item shall not be exceeded beyond the agreement quantities without prior permission of Engineer-in-Charge.

14. Income tax as per Income tax rules, GST as per rules, 1% Labour Cess and 1% water charges (if departmental water used) will be recovered from the gross amount of the bill.

15. Contractor is to make own arrangement of electricity as department is not obliged to provide electricity, however if departmental electricity is used then 1% electricity charges will be recovered from the gross amount of work done but the contractor shall arrange the necessary electrical fittings and cables etc. for taking the electrical power from nearest electrical point to the work site at his own cost.

16. All types of mortars to be used in the work shall be mixed in the mechanical mixer and hand mixing shall not be permitted.

17. The contractor shall make his own arrangement for getting the permission to ply the trucks from the traffic police or any other authority in this regard.

18. No payment shall be made to the contractor for any damage caused by rain, snow fall, floods or any other natural causes whatsoever during the execution of work. The damage caused to work shall have to be made good by the contractor at his own cost and no claim on this account shall be entertained.

19. Some restrictions may be imposed by the security staff etc. on the working and or movement of labour and materials, etc, the contractor shall be bound to follow all such restrictions / instructions and nothing shall be payable on this account.

20. The contractor shall take all precautions to avoid accidents by exhibiting necessary caution boards. He shall be responsible for all damages and accidents caused due to negligence on his part. No hindrance shall be caused to traffic during the execution of the work by storing materials on the road, VIP's corridor extra.

21. The contractor shall be fully responsible for the safe custody of the material issued or brought by him to site for doing the work.

22. **Testing of materials**
Samples of various materials required for testing shall be provided free of cost by the contractor unless otherwise specified in the item. Testing charges shall be borne by the contractor. All other expenditures required to be incurred for taking the samples, conveyance, packing etc. shall be borne by the contractor himself.

23. The rate for all items of work, shall unless otherwise clearly specified include cost of all labour, material and other inputs involved in the execution of the items.

24. The order of preference in case of any discrepancy as laid down in condition no. 8.1 under "Conditions of Contract" given in the **General Conditions of Contract for Central P.W.D work 2023 for Maintenance work** may be read as under-

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

a) Nomenclature of item as per Schedule of Quantities

b) Particular specifications and special conditions if any.

c) General Conditions

d) Additional conditions

e) Contract Clauses of GCC for Central P.W.D work 2023 for maintenance work.

f) CPWD Specifications 2019 and MoRTH specification as applicable.

g) Architectural/structural drawings and specifications mentioned in drawings.

h) Indian Standard Specifications of BIS

i) Sound engineering practice as per directions of the Engineer-in-Charge.

j) Manufacturers specifications.

Any reference made to any Indian Standard Specifications and other specifications mentioned in the respective items in these documents, shall imply to the latest version of that standard, including such revisions / amendments as issued by the Bureau of Indian Standards up to last date of receipt of tenders. The contractor shall keep at his own cost all such publications of relevant Indian Standards applicable to the work at site.

25. The contractor will not have any claim in case of any delay by the Engineer-in-Charge in removal of trees or shifting, removing of telegraph, telephone or electric lines (overhead or underground), water and sewer lines and other structure etc., if any which may come in the way of the work. However, suitable extension of time can be granted to cover such delay.

26. The malba /garbage generated at site due to construction activities shall be removed from the site immediately & shall be disposed off by the contractor to the approved dumping site identified by the Engineer-in-charge. The surplus soil/earth shall be disposed of as per the directions of Engineer-in-charge separately.

27. The contractor shall clean the site thoroughly of scaffolding materials, rubbish, equipments left out of his work and dress the site around the fencing to the complete satisfaction of the Engineer-in-charge before the work is treated as completed.

28. **Maintenance of Register of Tests**- All the registers of tests carried out at construction site/site lab or in outside laboratories shall be maintained by the contractor which shall be issued to the contractor by Engineer-in-Charge.

29. **Maintenance of Material at Site (MAS) Register**- All the MAS Registers including Cement and Steel Registers shall be maintained by Contractor which shall be issued to the contractor by Engineer-in-Charge.

30. Contractor shall be responsible for safe custody of all the test registers.

31. Contractor shall provide permanent bench marks and other reference points for the proper execution of work and these shall be preserved till the end of work. All such reference points shall be in relation to the levels and locations, given in the Architectural and plumbing drawings

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV**.

32. The contractor shall fully comply with all legal orders and directions of the Public or local authorities or municipality and adhere by their rules and regulations and pay all fees and charges for which he may be liable in this regard. Nothing extra shall be paid/reimbursed for the same.

33. The fencing work shall be carried out in the manner complying in all respects with the requirements of the relevant bylaws and regulations of the local body under the jurisdiction of which the work is to be executed or as directed by the Engineer-in-charge and nothing extra shall be paid on this account.

34. It shall be ensured by the contractor that no electric live wire is left exposed or unattended to avoid any accidents in this regard.

35. The contractor shall maintain in perfect condition, all portions executed till completion of the entire work allotted to him. Where however phased delivery of work is contemplated these provisions shall apply separately to each phase.

36. Existing drains, pipes, cables, over-head wires, sewer lines, water lines and similar services encountered in the course of the execution of work shall be protected against the damage by the contractor at his own expense. The contractor shall not store materials or otherwise occupy any part of the site in a manner likely to hinder the operation of such services.

37. The contractor shall be responsible for the watch and ward/guard/safety/ of the Road, retaining/breast wall, Culverts and Bailly Bridge, signage's etc. provided by him against pilferage and breakage during the period of installations and thereafter till the work. is physically handed over to the department. No extra payment shall be made on this account.

38. The contractor shall bear all incidental charges for cartage, storage and safe custody of materials, if issued by department.

39. Any cement slurry added over base surface for continuation of concreting for better bond is deemed to have been built in the items and nothing extra shall be payable for extra cement considered in consumption on this account.

40. The contractor shall take instructions from the Engineer-in-charge for stacking of materials. No excavated earth or fencing materials etc. shall be stacked/ collected in areas where other buildings, roads, services, compound walls etc. are to be constructed.

41. The works shall be carried out in accordance with the Architectural drawings and structural drawings, to be issued from time to time by the Engineer-in-Charge. Before commencement of any item of work, the contractor shall correlate all the relevant architectural and structural drawings issued for the work and satisfy himself that the information available thereof is complete and unambiguous. The discrepancy, if any shall be brought to the notice of the Engineer-in-Charge before execution of the work. The contractor alone shall be responsible for any loss or damage executing by the commencement of work on the basis of any erroneous and or incomplete information.

42. All Architectural drawings given in the tender other than those indicated in nomenclature of items are only indicative of the nature of the work and materials/fixings involved unless and otherwise specifically mentioned. However, the work shall be executed in accordance with the drawings duly approved by the Engineer-in-Charge.

43. The contractor(s) shall inspect the site of work before tendering and acquaint himself with the site conditions and no claim on this account shall be entertained by the department. The contractor(s) shall also see the approaches to the site in case any approach from main road is required at, site or existing approach is to be improved and maintained for cartage of materials by the contractor, the same shall be provided,

improved and maintained by the contractor at his own cost. No extra payment whatsoever shall be made on this account.

44. All the materials such as stone aggregate, screening materials, sand, bricks, cement and pipes etc. to be used in the work, shall have to be got approved from the Engineer-in-charge or his authorized representative prior to use in the work failing which work shall not be measured & paid for.

45. Roadside proper accommodation for labour / workmen, as per contract labour regulation Act, shall be provided by the contractor at his own cost & nothing extra shall be paid by the department.

46. The contractor shall at all-time carry out the works on the road in a very systematic manner without interference to the flow of traffic and consistent with the satisfactory & timely execution of the work. For all works, the contractor shall maintain a passage for traffic either along a part of the existing carriage-way under improvement or along temporary diversion constructed close to the road for this purpose as directed by Engineer-in-Charge for which nothing extra shall be paid.

47. The contractor shall also provide necessary barricade, in formatory boards, lights and flagmen at either end of the execution area and at such intermediate points as required and as directed by the Engineer-in-charge at no extra cost.

48. The work shall have to be executed in Indo-Bangladesh Border areas. Contractor(s) should inspect the site, so as to apprise himself / themselves of the site condition, before tendering. Being a Border area, there could be some restriction by Security agencies and the contractor has to follow and no extra claim on this account shall be entertained by the department.

49. The Executive Engineer by prior notice in writing to the contractor may reduce/increase the scope of work. In case of deviation in quantities, no extra claim except as otherwise provided in the contract shall be entertained by the department.

50. The contractor(s) shall submit "Time & Progress chart" for execution of work in different reaches showing activities distinctly along with Bar-Chart within fifteen days of the letter of acceptance of work in direct relation to the time stated in the contract document for completion of items of the works as per different milestone fixed indicating the forecast of date of commencement and date of completion of various items / activities kilometre wise from start point to end point of road as per agreement for adherence during execution.

    If any time, it appears to the Engineer-in-charge that the actual progress of work does not conform to the approved programme referred above, the contractor shall produce a revised programme showing the modifications to the approved programme by additional inputs to ensure completion of the work within the stipulated time.

    In case the contractor fails to achieve individual milestone as specified in Schedule F, action shall be taken as per clause 5 & other relevant clauses of the General Conditions of Contract 2023 for maintenance work.

51. The item of concreting/premixing shall be started / executed strictly under prior written approval of the Executive Engineer at appropriate time indicating the quantities and reaches / length (BP No. / K.M.) In case the Contractor violates the directions, the responsibility shall evolve on him and shall be liable for any consequences of wastage / damage / loss / non-payment etc.

52. In case of any calamity or injury to any labour / workmen etc. or loss / wastage of materials due to nature or insurgency, contractor shall have to bear the cost of compensation and no claim to this effect shall be entertained by the department.

53. **The contractor may not carry more than 5 MT weight of material in 1 truck for execution of work on the Border Roads**. The decision of Engineer-in-Charge in this respect shall be final and binding to the contractor.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV**.

54. Royalty / Octroi at the prevalent rates and all other incidental expenditure shall have to be paid by the contractor, on all the boulders, road metal, stone aggregate, river bed shingle, earth, sand, bajri etc., collected by him for the execution of the work direct to the concerned Revenue Authority of the State or Central Government. The rates mentioned in the documents relating to this contract are deemed to include all such expenditure and nothing extra shall be paid on this account.

55. The tenderer shall abide by the rules and regulations of respective GST Act etc. Necessary deductions on account of taxes shall be made on the gross value of the work done from the bills of the contractor as per the provisions of above stated Acts. Necessary certificates for tax deduction at source shall be issued to the contractor by the Engineer in Charge. The decision of the Engineer in Charge regarding quantum of tax deducted at source shall be final and binding on the contractor.

56. Necessary permit etc. for utilization of forest product would be obtained by the contractor directly from the Forest Authority. Necessary Forest Royalty Clearance Certificate (FRCC) from the Forest Authority shall be submitted by the Contractor to the Engineer-in-Charge along with the Bills for the work. Engineer-in-Charge reserves the right to deduct any sum considered reasonable towards forest royalty from the Running Accounts Bills of the Contractor, in the event of non-submission of FRCC. In case the contractor does not submit FRCC a sum considered reasonable towards payment of forest royalty would be deducted by the Engineer-in-Charge from the final bill of the work and credited to the Government accounts. The Engineer-in-Charge would determine the quantum of materials consumed on which such royalty is payable and also the rate of royalty payable. The decision of the Engineer-in-Charge shall be final and binding on the matter.

57. The work has to be carried out at different stretches of different IBBR and nothing extra will be payable on account of shifting of T&P, Machinery, Labour and materials etc.

58. Unless otherwise specified in the schedule of quantities, the rates for all items of the work shall be considered as inclusive of pumping out or bailing out water if required and, therefore, no extra payment will be made on this account. This will include water encountered from any source, such as rains, floods, subsoil water or any other cause whatsoever.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV**.

Salient Requirements for the Tender

1. The tenderer is advised to read and examine the tender documents for the work and the set of drawings available with Engineer-in-charge. He should inspect and examine the site and its surroundings by himself before submitting his tender.

2. Time allowed for the execution of work is **45(Forty Five) days.**

3. The contractor(s) shall submit a detailed program of execution in accordance with the master programme/milestone within ten days from the date of issue of award letter.

4. Quality of the project is of utmost importance. This shall be adhered to in accordance with the provisions of CPWD specifications and guidelines given in the relevant paras.

5. The contractor (s) shall make his own arrangements for electricity and water required for the execution of work.

6. Bitumen shall be arranged by the contractor himself

7. ~~Cement shall be arranged by the contractor himself.~~

8. ~~Steel Reinforcement shall be arranged by the contractor himself.~~

9. Contractor has to deploy required Plant and machinery on the project. Minimum number of plant and machinery to be deployed by him is indicated at Page No. 43.In case the contractor fails to deploy the plant and machinery whenever required and as per the direction of the Engineer-in-charge, he (Engineer-in-charge) shall be at a liberty to get the same deployed at the risk and cost of the contractor.

10. The contractor shall submit the running bills in the shape of the computerized MB in pages of A-4 size as per the standard format of department and shall act as per clause6 of Standard CPWD contract form defined in Proforma of Schedules of this NIT document.

11. ~~Contractor has to provide reinforcement cover blocks made of approved proprietary prepacked free flowing mortars (Can be extra as manufactured by M/s Fosroc Chemical IndiaLtd. or equivalent as approved)of high early strength.~~

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

ADDITIONAL CONDITIONS

1. This is a maintenance rate contract for ordinary repair, flood damage repair, bridge repair to IBB Roads as mentioned in the name of work**.** Contractor shall be permitted only to execute the work as per requirement given by Engineer – in – charge.

2. Work is to be executed in phased manner over a period of **45(forty five) days** and being maintenance work, execution earlier than period specified is not ordinarily allowed. However, if need arises, due to specific requirement then the Executive Engineer may permit to execute work more than specified in mile stone.

3. Contractor shall have to take instruction from the concerned Executive Engineers/Assistant Engineers in charge of work.

4. The contractor shall take immediate action to attend any instruction issued to him in writing, by E-mail, SMS, telephone or assigned to him through site order book/verbal instructions followed in writing from Engineer-in-charge /Assistant Engineers in charge of work

5. In case contractor did not execute the work, the necessary recovery as specified below shall be applicable as per the table below

Sl. No.	Details of item	Time allowed to restore	Amount to be recovered
1	To restore traffic for breach of IBB road less than 20 meter	24 hrs to 48 hrs	For not attending the work. Rs. 10,000/- per day beyond specified time.
2	To restore traffic for breach of IBB road less than 20 metre to 50 metre.	7 days	
3	Pot hole repair in a stretch of 2km of IBB road.	15 days	

6. The contractor shall maintain in their store sufficient quantity of stone aggregate, bitumen, sand filled gunny bags, bamboo and back up of spare parts required for the machinery to operate uninterrupted and quick start of maintenance work.

7. The contractor shall prepare one sample of all items which should be got approved from the Engineer-in-Charge. Only on acceptance of sample work, contractor will be allowed to commence the work and sample is to be preserved by contractor till the whole work is completed. The quality of work should be as per approved samples.

8. The contractor and/ or his authorized representative should inspect the site order book every day and got the compliance noted by the JE/ AE/ Engineer-in-Charge.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

9. If the work is carried out in more than one shift or during night, no claim on this account shall be entertained.

10. The dismantling wherever required shall be done in a manner so that no other portions of the building or its fixtures are damaged. If any damage is done to the building it shall be made good by the contractor at his own cost and no claim whatsoever shall be entertained on this account.

11. Due to Security reason the contractor shall have to arrange time table of labour according to the requirement of security staff and the instructions of the Engineer-in-Charge. The contractor should see the site before tendering.

12. The contractor shall be responsible for behaviour and conduct of his worker. No worker with doubtful integrity or having a bad record shall be engaged by the contractor.

13. Defective work, sub-standard work or work not done according to the specifications of the contract shall be liable for summarily rejection and shall not be measured and paid for. This shall be without prejudice to taking any other action against the contractor in accordance with the other terms and conditions of the contract.

14. The agency can be asked to submit documentary proof of procurement from the mentioned agencies i.e. Bill/ Invoice etc.

15. The contractor shall take all precautions to avoid accidents by exhibiting caution boards, red flags, red lights and providing necessary barriers and all other measures required from time to time. The contractor shall be responsible for all damages and accidents due to negligence on his part.

16. No residential accommodation shall be provided to any of the staff engaged by the contractor.

17. All the key technical personnel deployed by the contractor shall carry mobile telephone(s) to enable the Engineer-in-charge to have easy and quick communication. Nothing extra shall be paid to the contractor on this account and his quoted rates for various items under this contract will be inclusive of this obligation.

18. Quality Assurance

18.1 The contractor shall ensure quality control measures on different aspects of construction including materials, workmanship and correct construction methodologies to be adopted. He shall have to submit quality assurance programme within two weeks of the award of work. The quality assurance programme should include method statement for various items of work to be executed along with check lists to enforce quality control.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

18.2 The contractor shall get the source of all materials, not specified elsewhere in the document, approved from the Engineer-in-Charge. The contractor shall stick to the approved source unless it is absolutely unavoidable. Any change shall be done with the prior approval of the Engineer-in-Charge for which tests etc. shall be done by the contractor at his own cost. Similarly, the contractor shall submit brand/ make of various materials not specified in the agreement, to be used for the approval of the Engineer-in-Charge along with samples and once approved, he shall stick to it.

18.3 Test Laboratories:

A) Laboratory at site:

The contractor shall establish a testing lab at site and provide testing equipment and materials as specified in tender document. Nothing extra shall be payable to him on this account.

The representatives of the department shall be at liberty to inspect the testing facilities at site and conduct testing at random in consultation with Engineer in charge. The contractor shall provide all necessary facilities for the purpose.

Not less than 90% tests for material be performed at site lab with above stated equipment's, however at least 10% testing of materials shall be got done from external laboratories. However, for the tests to be carried out by the external laboratories, the contractor shall supply free of charge all the materials required for testing, including transportation.

B) Other Laboratories:

B1 **The contractor shall arrange carrying out all tests required under the agreement through the laboratory as approved by the Engineer-in-Charge and shall bear all charges in connection therewith including initial charges for testing nothing will be paid on this account.**

B2 **If the tests, which were to be conducted in the site laboratory are conducted in other laboratories for any other reasons, the cost of such tests shall be borne by the contractor.**

18.4 Sampling of Materials:

18.4.1 Sample of building materials fittings and other articles required for execution of work shall be got approved from the Engineer-in-Charge. Articles manufactured by companies of repute and approved by the Engineer-in-Charge shall only be used. Articles bearing BIS certification mark shall be used in case the above are not available, the quality of samples brought by the contractor shall be judged by standards laid down in the relevant BIS specifications. All materials and articles brought by the contractor to the site for use shall conform to the samples approved by the Engineer-in-Charge which shall be preserved till the completion of the work.

18.4.2 The contractor shall ensure quality construction in a planned and time bound manner. Any sub-standard material/work beyond set out tolerance limit shall be summarily rejected by the Engineer-in-Charge.

18.4.3 BIS marked materials except otherwise specified shall be subjected to quality test at the discretion of the Engineer-in-Charge besides testing of other materials as per the specifications described for the item/materials. Wherever BIS marked materials are brought to the site of

work, the contractor shall if required, by the Engineer-in-Charge furnish manufacturers test certificate to establish that the material produced by the contractor for incorporation in the work satisfies the provisions of BIS codes relevant to the material and/or the work done.

18.4.4 The contractor shall procure all the materials in advance so that there is sufficient time to testing and approving of the materials and clearance of the same before use in work.

18.4.5 All materials brought by the contractor for use in the work shall be got checked from the Engineer-in-Charge or his authorized representative of the work on receipt of the same at site before use.

18.4.6 The contractor shall be fully responsible for the safe custody of the materials issued to him even if the materials are in double lock and key system.

19. In case there is any discrepancy in frequency of testing as given in the list of mandatory test and that in the individual sub-head of work as per CPWD specification 2019 Vol. 1 & 2 the higher of the two frequencies of testing shall be adopted.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV**.

SPECIAL CONDITIONS

Special Conditions to comply directives of Hon'ble National Green Tribunal and EIA Guidance Manual

1. The contractor shall not store/dump construction material or debris on metalled road.
2. The contractor shall get prior approval from Engineer-in-Charge for the area where the construction material or debris can be stored beyond the metalled road. This area shall not cause any obstruction to the free flow of traffic/inconvenience to the pedestrians. It should be ensured by the contractor that no accidents occur on account of such permissible storage.
3. The contractor shall take appropriate protection measures like raising wind breakers of appropriate height on all sides of the plot/area using CGI sheets or plastic and /or other similar material to ensure that no construction material dust fly outside the plot area.
4. The contractor shall ensure that all the trucks or vehicles of any kind which are used for construction purposes/or are carrying construction material like cement, sand and other allied material are fully covered. The contractor shall take every necessary precaution that the vehicles are properly cleaned and dust free to ensure that enroute their destination, the dust, sand or any other particles are not released in air/contaminate air.
5. The contractor shall provide mask to every worker working on the construction site and involved in loading, unloading and carriage of construction material and construction debris to prevent inhalation of dust particles.
6. The contractor shall provide all medical help, investigation and treatment to the workers involved in the construction of building and carry of construction material and debris relatable to dust emission.
7. The contractor shall ensure that C&D waste is transported to the C & D Waste site only and due record shall be maintained by the contractor.
8. The contractor shall compulsory use of wet jet in grinding and stone cutting.
9. The contractor shall comply all the preventive and protective environmental steps as stated in the MoEF guidelines, 2010.
10. The contractor shall carry out on-Road- Inspection for black smoke generating machinery. The contractor shall use cleaner fuel.
11. The contractor shall ensure that all DG sets comply emission norms notified by MoEF.
12. The contractor shall use vehicles having pollution under control certificate. The emissions can be reduced by a large extent by reducing the speed of a vehicle to 20 kmph. Speed bumps shall be used to ensure speed reduction. In cases where speed reduction cannot effectively reduce fugitive dust, the contractor shall divert traffic to nearby paved areas.
13. The contractor shall ensure that the construction material is covered by tarpaulin. The contractor shall take all other precaution to ensure that no dust particles are permitted to pollute air quality as a result of such storage.
14. The paving of the path for plying of vehicles carrying construction material is more permanent solution to dust control and suitable for longer duration projects. The NIT approving authority shall carry out cost benefit ratio analysis of the same.
15.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

Particular Specification for Road work

1. The contractor shall be responsible for sorting, stacking and handing over of serviceable materials obtained during scarifying and / or dismantling of existing roads or a portion of road, culvert and / or its head walls or wing walls, boulder pitching , G.I. crated netting etc. In case of any loss or damage to serviceable materials prior to handing over, the value of the same as assessed by the Engineer-in-charge, shall be recovered from the contractor.

2. The Contractor shall submit a statement of materials whenever brought to site to the department, in conformity with plan/ programme approved by the Engineer-in-Charge.

3. Any legal or financial implications resulting out of disposal of earth shall be sole responsibility of the contractor. Nothing extra shall be paid on this account.

4. Contractor shall take all precautionary measures to avoid any damage to adjoining property. All necessary arrangement shall be made at his own cost.

5. IBBR/BP No. given in the name of work is only for general guidance actual place / reach for work will be decided by the Engineer-in-charge.

6. Procurement and accounting of bitumen

a) The contractor shall procure bitumen emulsion medium setting confirming to IS:8887-1995 and bitumen of required grade from the manufactures as specified in approved list of manufacturers.

b) Mode of procurement

Bitumen of specified grade shall be brought at site in sealed drums only, bearing following marking (legible).

(i) Name of Manufacturer.

(ii) Net weight.

(iii) Type and Grade.

c) The contractor will produce original Challan / Voucher for purchase of bitumen as a proof of having purchased the material from manufacturer. The Challan / Voucher shall be returned to the contractor after verification and marking necessary endorsement.

d) The contractor shall have to obtain and furnish test certificates issued by manufacturer to the Engineer-in-Charge in respect of bitumen procured by him.

7. The day-to-day receipt and issue accounts of bitumen shall be maintained by the Junior/Assistant Engineer and signed daily by the contractor or his authorized agent on the following proforma.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

PROFORMA FOR THE BITUMEN REGISTER

Date of Receipt	Total Qty.	Receipt Progressive	Date of Issue
(1)	(2)	(3)	(4)

Qty. Issued	Total issued	Balance in hand	Contractor's initial	J.E's initial
(5)	(6)	(7)	(8)	(9)

DAILY COMPARISON OF ISSUE WITH REQUIRTEMENTS

Name of work to which issued	Approximate Qty of work done	Theoretical requirement of bitumen for work done on each day	Actual consumption for work done on each day	contractor Initial	Initial of JE	Remarks of	
						AE	EE
1	2	3	4	5	6	7	8

8. The bitumen in drums shall be stacked in fenced enclosures as directed by the Engineer-in-charge, on one side of the roadway.

9. All the drums brought to site shall be serially numbered indicating agreement no. and all materials obtained from Government stores or otherwise shall be got checked by the Junior Engineer / Assistant Engineer-in-charge of works on receipt of the same at site before use.

10. The contractor shall stack sufficient amount of stone aggregate required for premixing and pothole/depression filling work in various reaches as per approval of Engineer-in-charge. Written permission from Engineer-in-charge or his authorized representative not below the rank of Assistant Engineer is to be obtained before commencement of bituminous work in a particular reach.

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

11. The potholes / depression filling and premixing work has to be planned in a systemic manner. The potholes / depression filling work has to be completed in a phased manner for every 2 Km. reach. The same has to be measured record from the Engineer-in-Charge or his authorized representative before taking up premixing work in that reach.

12. AGGREGATE FOR WBM

The aggregates shall satisfy the physical requirements set forth as follows: -

Stone Aggregate size:

(i) 63mm to 45 mm

Sl. No.	Name of Test	Specification
1.	Aggregate Impact Value	Maximum 30%
2.	Water absorption	Maximum 2%
3.	Soundness	Maximum 12%
4.	Combined Flakiness and Elongation Indices (Total)	Maximum 35%

(ii) 53 mm to 22.4 mm

Sl. No.	Name of Test	Specification
1.	Aggregate Impact Value	Maximum 30%
2.	Water absorption	Maximum 2%
3.	Soundness	Maximum 12%
4.	Combined Flakiness and Elongation Indices (Total)	Maximum 35%

(iii) Grade 'A' 13.2 mm/Grade 'B' 11.2 mm

Sl. No.	Name of Test	Specification
1.	Aggregate Impact Value	Maximum 30%
2.	Water absorption	Maximum 2%
3.	Soundness	Maximum 12%
4.	Flakiness Index & Elongation Index(combined)	Maximum 30%

LIST OF PREFERRED MAKES of Materials

The materials of first/standard quality from the following preferred makes are to be used. In case it is established that the brands specified below are not available in the market, contractor shall submit alternative proposal for the approval of Engineer-in-Charge.

The contractor shall provide the materials as per the Make or Brand indicated below. The contractor shall obtain the approval of Engineer-in-Charge for the alterative brands, before the actual execution of items.

A. General Materials.

Sl. No.	Materials	Brand/Manufacturer Name
1.	~~Steel Primer~~	~~1st quality paints of Berger, Asian Paints, Nerolac& ICI paints.~~
2.	~~Acrylic exterior paint~~	~~1st quality of Berger, Asian Paints, Nerolac& ICI paints.~~
3.	~~Synthetic enamel~~	~~1st quality of Berger, Asian Paints, Nerolac& ICI paints.~~
4.	~~Exterior primer~~	~~1st quality of Berger, Asian Paints, Nerolac& ICI paints.~~
5.	VG-30 Bitumen	I.O.C.L.
6.	Medium setting emulsion	BIS certified
7.	~~Ppc/ Cement~~	~~Acc, Ultratech, Vikram,Shree Cement, Ambuja, JaypeeCement,Century&Jk Cement And Any Other Manufacturer Approved By Cpwd.~~
8.	~~NP3 RCC hume pipe~~	~~BIS Certified~~

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

SCHEDULE OF QUANTITIES

Name of work Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310 Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.

Item No.	DSR-2023 Item / MR	Description of item	Quantity	Unit	Rate ₹	Amount in ₹	
						As per MR	**As per DSR-23**
1.1	DSR'2023 It-16.3	Supplying and stacking at site.					
1.1.1	16.3.3	53 mm to 22.4 mm size stone aggregate	2.00	cum	1,842.30	0.00	3,685.00
1.1.2	16.3.7	Stone screening 11.2 mm nominal size (Type B)	0.90	cum	2,247.75	0.00	2,023.00
1.1.3	16.3.9	Good Earth	0.40	cum	775.50	0.00	310.00
2.1	M.R. Based on It.16.9	Scarifying metalled (water bound) road surface including disposal of rubbish lead upto 50m and stacking the scarified material received from scarifying.	45.00	sqm	19.00	855.00	0.00
3.1	DSR'2023 It-16.4	Laying, spreading and compacting stone aggregate of specified sizes to WBM specifications in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne capacity in stages to proper grade and camber, applying and brooming requisite type of screening / binding material to fill up interstices of coarse aggregate, watering and compacting to the required density .	3.40	cum	1,046.95	0.00	3,560.00
4.1	DSR'2023 It-16.31	Providing and applying tack coat using bitumen emulsion conforming to IS:8887, using emulsion pressure distributer including preparing the surface & cleaning with mechanical broom.					
4.1.1	16.31.2	With medium setting bitumen emulsion					
4.1.1.1	16.31.2.1	On W.B.M / W.M.M. @ 0.4kg/sqm	1,059.00	sqm	21.20	0.00	22,451.00
4.1.1.2	16.31.2.2	On bituminous surface @ 0.25kg/sqm	12,586.00	sqm	14.05	0.00	1,76,833.00

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

5.1	DSR'2023 It-16.55	Providing and laying bituminous macadam using crushed stone aggregates of specified grading premixed with bituminous binder, transported to site by tippers, laid over a previously prepared surface with paver finisher equipped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers as per specifications to achieve the desired compaction and density, complete as per specifications and directions of Engineer-in-Charge.					
5.1.1	16.55.2	50 to 100 mm average compacted thickness with bitumen of grade VG-30 @ 3.50% (percentage by weight of total mix) prepared in Drum Type Hot Mix Plant of 60-90 TPH capacity.	335.00	cum	8,413.00	0.00	28,18,355.00
6.1	DSR'2023 It-16.57	Providing and laying Bituminous concrete using crushed stone aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site by tippers, laying with paver finisher equiped with electronic sensor to the required grade, level and alignment and rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction and density as per specification, complete and as per directions of Engineer-in-Charge.\\					
6.1.1	16.57.5	40/50 mm compacted thickness with bitumen of grade VG- 30 @ 5.5% (percentage by weight of total mix) and lime filler @ 3% (percentage by weight of Aggregate) prepared in drum Type Hot Mix Plant of 60-90 TPH capacity.	268.00	cum	12,026.80	0.00	32,23,182.00
		Total :				**855.00**	**62,50,399.00**

Estimated Cost after using correction factor on DSR-2023 (Except Item No. 2.3 & 3) on account of GST @ 0.973 vide SE (TAS) File No. 158/SE(TAS)/GST/2024/02-E, dated 08-08-2024 on	₹ 62,50,399.00	₹ 60,81,638.00
Add for Cost Index @ 15% at Petrapole (W.B.) over Estimated Cost of DSR-2023 on	₹ 60,81,638.00	₹ 9,12,246.00
Estimated Cost of Non-DSR Items based on MR (Item No. 2.1)	₹ 855.00	₹ 855.00
Estimate Cost put to Tender :	**Total:**	**₹ ₹69,94,739.00**

Executive Engineer
Border Fencing Division-IV,
IBBZ-I, CPWD, Barasat-700126

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**

Central Public Works Department

NIT No. 22/EE/BFD-IV/1BBZ-I/2026-2027

Name of work: Periodical Repair to IBB Road in the North 24 Paraganas District of West Bengal from BP No. 29/6-S to Betna River Steel Bridge (L =2.310Km) & PWD Link Road near Kurulia to towards 31/7-S (0.494 Km), [Total Length of PR Work = 2.804 Km] during the year 2026-2027. SH: Scarifying existing Road surface, relaying WBM, 40 mm Bituminous Concrete as wearing coat over 50 mm Bituminous Macadam under BFD-IV, CPWD, IBBZ-I, Barasat, West Bengal.

PROFORMA FOR QUOTING TENDER

Name of the Contractor :

Sl. No.	Name of component	Estimated cost (₹)	Percentage rate above or below the estimated cost:	% in Figures	Total Cost: (₹)
1	2	3	4	5	6
1.	As per the total of Schedule of Quantity :	₹ 69,94,739.00			
	Estimated Cost put to Tender:	₹ 69,94,739.00			

1. The Column Nos 4 & 5 are mandatory to be filled by the bidders/ tenderers. If all these columns are left blank, the tender become invalid.

2. The amount in figures in column No.6 shall appear automatically corresponding to the percentage quoted in column No.4 & 5.

3. The tenderer is required to quote the percentage only above or below or at par with the estimated cost to cover all the rates of item covered under the respective packages.

4. The percentage shall be written in 2 (two) place of decimal.

5. If the percentage selection in column No 4 is "At Par", by default the percentage will be considered as "Zero" only. In other words if "At par" is selected in column No.4, then no need to fill column No.5.

6. The rate quoted is inclusive of all applicable taxes, royalty, levy or cess such as Income Tax, GST, Labour Cess etc.

Signature of Contractor.

Executive Engineer
Border Fencing Division-IV,
IBBZ-I, CPWD, Barasat-700126

Addition	- Nil
Deletion	- Nil
Overwriting	- Nil
Correction	- Nil

AE(P)/BFD-IV. **EE/BFD-IV.**