Govt. Of India
Central Public Works Department
Notice Inviting Quotation

NIQ No.: 06/EE(E)/CAPFIMS-1/2026-27 (Recall) **Date: 04.11.2026**

The **Executive Engineer (E), CAPFIMS-1, CPWD, Maidangarhi, New Delhi-110068** invites on behalf of "President of India" offline quotations containing certificate of Valid CPWD Registration, Valid Electrical Licence, GST Registration, PAN copy and Price Bid on percentage rate basis from CPWD contractor on or before 10.11.2026 at 3:00 PM for the following works in the office of Executive Engineer (E), CAPFIMS, CPWD, Maidangarhi, New Delhi - 110068 . Quotation so received will be open on the same day at 3: 30 PM.

Name of Work: Supplying Installation Testing and Commissioning of VRV/VRF AC System in MBBS/Nursing/N&P Hostels at AIIMS CAPFIMS, Maidangarhi, New Delhi - 110068. (SH:- Providing and Fixing of Armoured CT 6 Cable and other accessories at MBBS Hostel for configuration of Network.)

Schedule of Work

Name of Work: Supplying Installation Testing and Commissioning of VRV/VRF AC System in MBBS/Nursing/N&P Hostels at AIIMS CAPFIMS, Maidangarhi, New Delhi - 110068. (SH:- Providing and Fixing of Armoured CT 6 Cable and other accessories at MBBS Hostel for configuration of Network.)

Sr no	Item Description	Unit	Qty	Rate	Amount
1	Supplying, drawing, Installation, Testing and commissioning of CAT6 UTP LSZH 23AWG Twisted Pair Cable in existing conduit/ on surface, Category 6 Unshielded Twisted Pair, 4 pair should be complied as per UL/ETL verification program for compliance with ANSI/TIA-568.2-D standard. Outer diameter should be in the range of 6.1mm nominal with Operating Temperature Range : -5° to +60°C, Bending Radius : < 4 X Cable Diameter at –5°C ± 1°C and Pulling Force : 11.5Kg etc. complete as required.	Mtr	**4000**	60.00	240000
a)	1 Run of cable				
2	Supplying Installation Testing and Commissioning of 24 port Cat6 Patch Panel loaded. Must be of 1U height with clear label holders and white label with the panel. 24 Ports Cat-6 Patch Panel should have ETL/UL verification program certificate for compliance with ANSI/TIA-568.2-D etc. complete as required.	Nos	**28**	5278.00	147784
3	Supplying and fixing of following size Wall Mount Rack having Fixed Structure with 0.8mm CRCA Sheet, completely knocked-down condition (CKD) Shape, Vertical Mounting Rail 1.6 mm with 'U'Marking, Minimum 2 cable entry/exit provision at Top and bottom with rubber protection, Front 5mm Toughened Glass with lock, wall mounting kit, Powder coated Color- RAL- 7035, complied with UL & RoHS, 2 x 6 sockets 16A power distribution units, 3 numbers closed cable organizer, Hardware mounting screws packet of 20 x 1 number, etc. complete as required.				
a)	6U Rack	Nos	**15**	6939.00	104085

4	Supplying, Installation, Testing and commissioning of RJ45 Connector for CAT 6/6A Cables. RJ45 modular plug supports 4 twisted pairs, 8 positions, 8 connectors. Housing: PC, UL94V-2, transparent color, Use for 24- 26 AWG stranded wires etc. complete as required.	Nos	**500**	9.00	4500
			Total	**Rs**	**496369**
	Quoted Rate Above/Below				
	Total (Rate Inclusive of GST and all Taxes)		**Total**	**Rs**	

Terms and conditions:

1. The work shall be carried out as per direction of Engineer-in-charge.
2. The time limit for executing work is 15 days.
3. The rate shall be inclusive of all taxes i/c GST & nothing extra shall be paid on this account.
4. Payment shall be made after completion of work.

5/11/25

कार्यपालक अभियंता (वै0)
सी0ए0पी0एफ0आई0एम0एस0–1
के0लो0नि0वि0, नई दिल्ली।

प्रतिलिपिः–

1. सहायक लेखाधिकारी, सी0ए0पी0एफ0आई0एम0एस0, के0लो0नि0वि0, नई दिल्ली को सूचनार्थ।
2. सूचनापट्ट।

कार्यपालक अभियंता (वै0)