


Name of Work: Renovation of Departmental Canteen and painting to guest house at Akashvani, Siripuram, Visakhapatnam.

SCOPE OF WORK

1. Dismantling of (i) existing damaged kitchen platform of size 14 ft x 2 ft including supporting system, (ii) chajja of size 8 ft x 1.5 ft and (iii) wall tiles and mosaic provided to the walls in the kitchen of Canteen all complete as directed.
2. Construction of 2 Nos. of kitchen platforms of size 14 ft x 2 ft in Departmental canteen, & 10 ft x 2 ft kitchen platform in Engineer's rest room duly constructing brick masonry pillars supporting system with granite on top of the platform with edge polish, and providing & fixing steel sink on one side, all complete as directed.
3. Providing and fixing of ISI marked Ceramic/Vitrified wall tiles in the kitchen room of departmental canteen to the extent of 250 sq.ft with tiles of size 1 ft' x 1½ ft including adhesive, spacers, cutting, joint filling/grouting, and finishing, all complete as directed.
4. Supply and fixing of aluminium-framed sliding cupboard shutters of size 9'8" x 1'8" for kitchen cabinets, including aluminium sections, sliding tracks, rollers, handles, and with stainless steel netted enclosures, necessary hardware, and all fittings, all complete as directed.
5. Closing the gap between the existing wall and roofing sheet by constructing a brick masonry wall of size 36 ft x 1 ft, duly plastered with cement mortar, and providing and fixing GI/tin roofing sheets to cover the remaining gap & Providing and fixing GI sheets to the bottom portions of the canteen doors to prevent rat entry, all complete as directed.
6. Providing and laying UPVC water pipe line connection to the kitchen sink in Canteen and in Engineer's rest room from the nearby existing water line and providing & fixing water taps of approved quality and required size all complete as directed.
7. Repairs to cracks and damaged/loose plastering areas duly dismantling & cutting and plastering with cement mortar for the canteen building at Studio cum Office Building and guest house block in staff quarters with necessary scaffolding etc., all complete as directed.
8. Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete and applying priming coat with primer and Finishing walls with Acrylic Smooth exterior paint for old work Two or more coats on existing cement paint surface with necessary scaffolding all complete as directed. Total painting area is 5,000 sq. ft. (material shall be supplied by Department).


DY. DIRECTOR GENERAL(E)
AKSHVANI, VISAKHAPATNAM